

EXHIBIT A

Job No.	County	Route	Location	Proposed Improvement	Length (Miles)	Approx. Constr. Cost (thousands)	DBE Goal	Consultant Services Required	Other Comments	Anticipated Letting Date	Project Manager	Bridge Liaison
J4S3412 KU0096	Clay	1	72nd St to North of 42nd St./43rd to 44th St	Pavement reconstruction, upgrade pedestrian facilities, and upgrade signals from 72nd Street to North of 42nd Street (J4S3412) and upgrade/add Pedestrian Facilities from 43rd to 44th Street (KU0096)	3.7/0.1	\$17,812/\$759	14%/12%	Surveying - field surveying for minor items (driveway slopes, roadway slopes, etc), legal descriptions, right of way staking, geotechnical staking, and location survey. Roadway Design - preparation of preliminary plans, right of way plans (if needed), and final design plans. Consultant will submit milestone Requests for Environmental Services (RES) and estimates, public involvement and meeting/hearing support. Construction Inspection (Only for J4S3412) - all professional, technical and other personnel, equipment, material, and all other things necessary for providing project inspection and materials testing. Bridge Design (Only KU0096) - preparation of wall memorandum, geotechnical investigations, layout, and final design for a potential retaining wall underneath I-35 bridges L0653 & L0654 and along the pedestrian facilities. Right of Way Services, see Exhibit B	These projects are not being let in combination. Consultant Construction Inspection is requested for J4S3412 but not the other project of this bundle. New right of way may be necessary.	Jan 2024 (J4S3412) & Sep 2025 (KU0096)	Sean Domingo	Chris Shanks
KU0128	Platte	HH	at I-29	Modify Interchange Configuration	0.1	\$8,497	14%	Surveying - all field surveying including mapping, bridge survey report, geotechnical staking, legal descriptions, right of way staking, and location survey. Roadway Design - preparation of conceptual report with alternative options, Access Justification Report (AJR), preliminary plans, right of way plans (if necessary), public involvement and meeting/hearing support, geotechnical investigation/borings, milestone Requests for Environmental Services (RES) and estimates, FAA submittals, and final design plans. Construction Inspection - all professional, technical and other personnel, equipment, material, and all other things necessary for providing project inspection and materials testing. Right of Way Services, see Exhibit B	New right of way may be necessary.	January 2027	Heather Barrows	
J4I3494	Jackson	I-49	Over Little Blue River (s/o MO 150)	Bridge Replacements (L0530 and A0478)	0.5	\$3,694	10%	Surveying - surveying, including supplemental mapping, bridge survey report, geotechnical staking, legal descriptions, right of way staking, and location survey. Roadway Design - preparation of the conceptual report, sign truss inspection, geotechnical investigation, sign truss, public involvement and meeting support, preliminary plans, right of way plans, milestone Requests for Environmental Services (RES) and estimates, FAA submittals, and final design. Bridge Design - preparation of bridge memorandums, geotechnical investigations, layout, and final design for L0530 SB and A0478 NB over Little Blue River. Construction Inspection - all professional, technical and other personnel, equipment, material, and all other things necessary for providing project inspection and materials testing. Right of Way Services, see Exhibit B	New right of way may be necessary.	December 2025	Karlee Covington	Chris Shanks
J4S3490	Jackson	71	Over Rte W (Bannister Rd)	Bridge Replacements (L0842, H0033, and A2395)	0.7	\$8,669	14%	Surveying - surveying, including supplemental mapping, grade separation report, bridge survey report, geotechnical staking, legal descriptions, right of way staking, and location survey. Roadway Design - preparation of the conceptual report, sign truss inspection, geotechnical investigation, sign truss, supplemental traffic counts, preliminary plans, right of way plans, public involvement and meeting/hearing support, milestone Requests for Environmental Services (RES) and estimates, FAA submittals, and final design. Bridge Design - preparation of bridge memorandums, geotechnical investigations, layout, and final design for L0842 twin bridges over Route W/Bannister Rd (replacements), H0033 box culvert under US 71 (partial replacement), and A2395 box culvert under Bannister Rd (extension). Construction Inspection - all professional, technical and other personnel, equipment, material, and all other things necessary for providing project inspection and materials testing. Right of Way Services, see Exhibit B	New right of way may be necessary.	December 2025	Allan Ludiker	Chris Shanks