From: Debra M. Beckwith
To: BR
Subject: Bridge Advertisement (DSI 21-003) Compression Joint Seal Limits
Date: Wednesday, February 10, 2021 2:46:38 PM

The EPG & Bridge Standard Drawings have been updated as described below:

Implementation Statement: Effective immediately for design checks not started.

(The Implementation Statement is a recommendation by the Development Section. The SPM is responsible for the level of implementation for any particular job.)

Revision Date	Items Revised	Description of Change
Feb. 2020	EPG: 751.13, 751.50	Updated EPG 751.13.1.1.12, 751.13.2, 751.13.3, and 751.50 and Bridge standard drawings Seal01, Seal02, P_Com01, P_Com02, and P_Com03 to implement open cell foam joint seal in EPG and update preformed compression seal for revised manufacturer data. The skew limit for preformed compression seals has dropped from 20 to 15 degrees. Reduced movement limits for 20 degree skews have been retained to allow for possible in-kind replacement of seals that functioned adequately over their service life.
	Bridge Standard Drawings: SEAL01-02, P_COM01-03	
	MicroStation Cells: NA	
	Std. Specifications: NA	
	Standard Plans: NA	
	Bridge Special Provisions: NA	

to view more details about this (or any) revision, use the Revision Index Database.
Instructions:

1. Select the Revision Index Database.
2. Select "Read Only" and Click "O.K."
3. Under Tables (left-hand side) double-click on Table1.
4. Scroll down to the bottom of the list to find the latest Revision.
5. Click on the link under the Effective Date to open the storage location for the Completed Revision.

DEBRA (DEBBIE) M. BECKWITH

Structural Specialist

Missouri Department of Transportation
Central Office – Bridge Division
105 W. Capitol Ave., P.O. Box 270, Jefferson City, MO 65102
573-522-8718
Mon. & Fri. 7:00 a.m. to 3:30 p.m.; Tues, Wed, Thur 6:30 a.m. to 3:00 p.m.
www.modot.org