

**From:** [Debra M. Butchart](#)  
**To:** [BR](#)  
**Subject:** Bridge Advertisement (DSI 24-043) Prestressed Girder Limits  
**Date:** Wednesday, July 16, 2025 10:16:25 AM

---

The [EPG](#) has been updated as described below:

**Implementation Statement:** Effective immediately for design checks not started.

*(The Implementation Statement is a recommendation by the Development Section. The SPM is responsible for the level of implementation for any particular job.)*

Revision Date	Items Revised	Description of Change
<a href="#">July 2025</a>	EPG: <a href="#">751.22.2.3</a> ; <a href="#">751.21.2</a>	Added language for limiting stress after losses at the top of prestressed (PS) girders/beams near interior supports, limiting stress after losses near midspan of PS girders/beams, and limiting stress before losses for PS girders/beams.
	Bridge Standard Drawings: NA	
	MicroStation Cells: NA	
	Std. Specifications: NA	Note that the limiting stress, after losses at the top of PS girders/beams near interior supports, shall be met even though the girders/beams are designed as reinforced concrete members at these locations.
	Standard Plans: NA	
	Bridge Special Provisions: NA	The new EPG guidance was previously provided in Development Section Bulletin No. 17-06. That bulletin covers some other items so it will remain on the website.

Follow links above for more information (internal only).

Debra (Debbie) Butchart  
(formerly Debra Beckwith)  
Structural Specialist  
Development Section  
Bridge Division  
MoDOT- 105 West Capitol Ave  
573-522-8718