

ADDENDUM NO. 1

ISSUED BY: Howe Company LLC
804 E. Patton Street
Macon, MO 63552

Am
3-31-2025

DATE: March 31, 2025

FOR: LEWIS COUNTY BRIDGE 12200071
BRO-R056(015)

The attached revisions hereby supersede any and all data with which they may conflict as indicated on the Drawings, Specifications and related documents issued in the original set. Each trade is responsible for changes in its work caused by changes in the work of other trades. This addendum is a part of and shall be attached to the original set of plans and specifications for the work.

THIS ADDENDUM SHALL BECOME A PART OF THE SPECIFICATIONS NOTED ABOVE.
RECEIPT OF THIS ADDENDUM SHOULD BE ACKNOWLEDGED ON THE BID FORM.

The completion date of the project has been changed to July 31, 2026, or 180 calendar days after the road is closed, whichever comes first.

Construction of all roadway embankments shall conform to Section 203.6. The following is added as part of 203.6:

The contractor shall proof-roll the full width of each lane of the embankment at mid-height of fill prior to placement of the roadway aggregate. The truck used for proof rolls shall be either a dump truck or semi-truck with dual wheel, tandem axles loaded to at least the maximum legal load and have tire pressures no less than 110 psi. The speed of the truck doing the test shall be about walking speed. Passing criteria is deflection no more than 1" and no pumping, and no cracking. All areas which do not pass shall be reworked, replaced as necessary. No direct compensation will be made for proof-rolling, reworking the failed areas, nor replacement of unsuitable fill materials.

There is no change in the bid date or time.