

**CITY OF BRANSON, MISSOURI
PURCHASING DEPARTMENT**

**REQUEST FOR BID 2869-05A, 2869-05B, 2869-05C, 2869-05D
W 76 Country Blvd Streetscape – Segments 1 and 2**

**James Morris, Bid Coordinator
City of Branson, Purchasing Office
110 W. Maddux St., Suite 200
Branson, MO 65616**

**Date Issued: September 10, 2026
Buyer's Email: jmorris@bransonmo.gov
Telephone: (417) 337-8553 Ext. 1407
DUE DATE: September 14, 2026, at 1:00 PM**

Addendum No. 3

Vendors are directed to the documents attached following this Addendum Acknowledgement. Vendors are solely responsible for reviewing all attached materials in their entirety and ensuring their bid submission reflects any applicable changes contained therein.

**ALL BIDDERS ARE REQUESTED TO SIGN THE ACKNOWLEDGMENT BELOW AND
INCLUDE WITH BIDS TO CONFIRM RECEIPT OF ADDENDUM #3**

**Signature
Acknowledged by Bidder**

End of Addendum No. 3

Addendum NO 3

ISSUED BY: *Great River Engineering*
2826 S. Ingram Mill Rd.
Springfield, Missouri 65804
(417) 886-7171
(417) 886-7591 --- FAX



DATE: September 10, 2026

FOR: W 76 Country Boulevard Streetscape Improvements,
Contracts EN7622, SNS0032 &
W 76 Country Blvd Median Improvements
Contracts TAP-9901(886) and STP-0761(023)
GRE Project 4515

The attached revisions hereby supersede all data with which they may conflict as indicated on the Drawings, Specifications and related documents issued in the original set. Each trade is responsible for changes in its work caused by changes in the work of other trades. This addendum is a part of and shall be attached to the original sets of plans and specifications for the work.

CHANGES: To Contract EN7622 Bid Form and Bid Plans

1. Clarification on Plan sheet RW03 of 06 regarding the scupper drain detail:

The risers and the scuppers pipes that penetrate the retaining wall should be cast iron. The connector pipes draining horizontally from the risers to the scuppers that discharge thru the wall are PVC but could be cast iron (contractor option).

2. Change the Bid Form under bid item 152 SCUPPER DRAIN 12" to SCUPPER DRAIN 6"

CHANGES: To Contract TAP-9901(886)

1. Change Bid Form to remove TAPCO Safewalk Illuminator and TAPCO Vizmark Illuminator.

CLARIFICATIONS:

ATTACHMENTS:

- a. Revised TAP Bid Form
- b. Revised EN7622 Bid Form

There are no other clarifications or changes included with this Addendum.

W. 76 COUNTRY BLVD. MEDIAN IMPROVEMENTS
TAP - 9901(886)
BID FORM - ADDENDUM 3

<u>Item No</u>	<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Price</u>	<u>Extension</u>
<u>TAP-9901(886) BID ITEMS</u>					
1	MOBILIZATION	1	LS	_____	_____
2	CONTRACTOR SUPPLIED TESTING - QUALITY CONTROL	1	LS	_____	_____
3	CONTRACTOR SUPPLIED SURVEY STAKING	1	LS	_____	_____
TAP MEDIAN PLANS					
4	SIGNS W/MOUNTING BRACKETS	169	SF	_____	_____
5	THERMOPLASTIC PAVEMENT MARKING - SOLID YELLOW 6"	3559	LF	_____	_____
6	THERMOPLASTIC - YELLOW DIAGONAL CHEVRONS 24"	945	SF	_____	_____
7	THERMOPLASTIC PAVEMENT MARKING - 6" SOLID WT STRIPE	438	LF	_____	_____
8	THERMOPLASTIC - DIAGONAL CHEVRONS WT 24"	177	SF	_____	_____
9	THERMOPLASTIC - 24" SOLID WT STOP BAR	330	SF	_____	_____
10	POST, TYPE CL, 15 FT. ARM W/ A-9 BASE	7	EA	_____	_____
11	POST, TYPE CL, 18.5 FT. ARM W/ A-9 BASE	1	EA	_____	_____
12	POST, W TYPE C BASE	16	EA	_____	_____
13	4" POST, W 4" BREAKAWAY BASE	8	EA	_____	_____
14	PED SIGNAL HEAD	16	EA	_____	_____
15	ACCESSIBLE PEDESTRIAN SIGNAL DET	16	EA	_____	_____
16	CONDUIT, 2 IN. RIGID, IN TRENCH	445	LF	_____	_____
17	CONDUIT, 3 IN. RIGID, IN TRENCH	954	LF	_____	_____
18	TRENCHING TYPE I	1399	LF	_____	_____
19	POWER SUPPLY	4	EA	_____	_____
20	CONTROLLER CABINET W/MCCAIN ATC FLEX CONTROLLER	4	EA	_____	_____
21	PULL BOX, PREFORMED CLASS 1	12	EA	_____	_____

TAP - 9901(886)
BID FORM - ADDENDUM 3

<u>Item No</u>	<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Price</u>	<u>Extension</u>
<u>TAP-9901(886) BID ITEMS</u>					
22	CABLE, 2 AWG 1 CONDUCTOR	1146	LF	_____	_____
23	CABLE, 12 AWG 1 CONDUCTOR	11403	LF	_____	_____
24	CABLE, 16 AWG 1 CONDUCTOR	26104	LF	_____	_____
25	CABLE, 6 AWG GROUNDING 1 CONDUCTOR	1519	LF	_____	_____
26	4" PVC IRRIGATION CONDUITS	384	LF	_____	_____
27	MIOVISION SMARTVIEW 360 CAMERA WITH CORE DCM (IN CONTROLLER CAB)	4	EA	_____	_____
28	2" STEEL SIGN POSTS W/RECIEVER BASE.	9	EA	_____	_____
29	SPARE CONDUIT, 4 IN. RIGID, IN TRENCH	388	LF	_____	_____
30	HYBRID HAWK SIGNAL HEAD W/BACKPLATE	16	EA	_____	_____
TAP-9901(886) BID TOTAL:					_____

W. 76 COUNTRY BLVD. STREETSCAPE - SEGMENTS 1 & 2 - EN7622
BID FORM - BASE BID - ADDENDUM 3

<u>Item No</u>	<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Price</u>	<u>Extension</u>
1	MOBILIZATION	1	LS		
2	CONTRACTOR SUPPLIED TESTING - QUALITY CONTROL	1	LS		
3	CONTRACTOR SUPPLIED SURVEY STAKING	1	LS		
	REMOVALS				
4	REMOVALS AND DISPOSAL	1	LS		
	TRAFFIC CONTROL				
5	CHANGEABLE MESSAGE BOARDS	8	EA		
6	SHOULDER CLOSURES - PHASING	1	LS		
7	LANE CLOSURES - PHASING	1	LS		
8	SW CLOSURES - PHASING	1	LS		
9	SINGLE LANE FLAGGER CONTROL - PHASING	1	LS		
10	CENTER LANE CLOSURE - PHASING	1	LS		
11	CONSTRUCTION SIGNS	895	SF		
12	FLASHING ARROW PANEL	2	EA		
13	TYPE III MOVEABLE BARRICADE (SW)	10	EA		
14	CHANNELIZER (TRIM LINE)	453	EA		
15	SW TEMP CONSTRUCTION FENCING	1200	LF		
16	TEMP ACRYLIC WATRBORN 4" YELLOW PVMT MARKING	23071	LF		
	STORM SYSTEM IMPROVEMENTS				
17	CURB - DROP INLET REPLACEMENT 4X4	2	EA		
18	GRATE INLET (2'X3')	21	EA		
19	NEW GRATE DROP INLET (24"X24")	2	EA		
20	NEW JUNCTION BOX (4X4)	2	EA		
21	CONVERT EX INLETS TO JB'S	3	EA		
22	ADJUST MANHOLE RIM TO FINISH GRADE	4	EA		
23	CONCRETE HEADWALLS	3	CY		
24	CONCRETE FLUME W/GRATE	3	CY		
25	24" RCP FLARED END SECTION	1	LF		
26	24" RCP STORM SEWER PIPE	3	LF		

W. 76 COUNTRY BLVD. STREETSCAPE - SEGMENTS 1 & 2 - EN7622
BID FORM - BASE BID - ADDENDUM 3

<u>Item No</u>	<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Price</u>	<u>Extension</u>
27	18" RCP STORM SEWER PIPE	36	LF		
28	15" RCP STORM SEWER PIPE	169	LF		
29	12" STORM SEWER PIPE	640	LF		
30	NEW GRATE INLET (4X4)	4	EA		
	SEDIMENT AND EROSION CONTROL				
31	SILT SOXX	4288	LF		
32	INLET GRAVEL BAGS	70	EA		
33	TEMPORARY GRAVEL ENT	4	EA		
34	CONCRETE WASHOUT	3	EA		
35	TEMPORARY SEEDING	1.50	AC		
36	TRM	6	SY		
37	CHANNEL CHECKS	4	EA		
	WATER SYSTEM IMPROVEMENTS				
38	6" FIRE HYDRANT ASSEMBLIES (TEE, VALVE & HYD)	32	EA		
39	COMMERCIAL FIRE LINE CONNECTIONS	3	EA		
40	10" WATERLINE RJ - C900 (NEW)	198	LF		
41	12" WATERLINE RJ - C900 (NEW)	9209	LF		
42	12" WATERLINE RJ 11.25 BEND (NEW)	10	EA		
43	12" WATERLINE RJ 22.50 BEND (NEW)	11	EA		
44	12" WATERLINE RJ 45 BEND (NEW)	18	EA		
45	12" WATERLINE RJ 90 BEND (NEW)	2	EA		
46	12"x6" RJ REDUCER (NEW)	1	EA		
47	12" RJ PLUG (NEW)	1	EA		
48	8" RJ PLUG (NEW)	2	EA		
49	24" STEEL SLEEVE (NEW)	475	LF		
50	4" C900 PVC WATERMAIN (TIE IN)	10	LF		
51	8" C900 PVC WATERMAIN - TIE IN	264	LF		
52	8" WATERLINE RJ 11.25 BEND (NEW)	1	EA		
53	6" C900 PVC WATERMAIN (FIRE CONNECTION EXT)	40	LF		
54	NEW 2" METER, SETTER AND PIT	18	EA		
55	NEW 2" DBL METER, SETTER AND PIT (INC 2 METERS)	3	EA		
56	NEW 4" METER ASSEMBLY AND VAULT	1	EA		
57	3/4" METER, SETTER, AND PIT	7	EA		
58	1" METER, SETTER, AND PIT	11	EA		

W. 76 COUNTRY BLVD. STREETSCAPE - SEGMENTS 1 & 2 - EN7622
BID FORM - BASE BID - ADDENDUM 3

<u>Item No</u>	<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Price</u>	<u>Extension</u>
59	NEW 6" METER IN EXISTING VAULT	1	EA		
60	16" RJ BUTTERFLY VALVES	2	EA		
61	12" RJ GATE VALVES	47	EA		
62	10" RJ GATE VALVES	8	EA		
63	8" RJ GATE VALVES	6	EA		
64	6" RJ GATE VALVES	1	EA		
65	4" RJ GATE VALVES	1	EA		
66	ABANDON EXISTING WATER MAINS	1	LS		
67	16"X12" RJ TEE TIE IN CONNECTION	1	EA		
68	16" X 12" MJ REDUCER	1	EA		
69	12"X12"X4" RJ TEE	1	EA		
70	12"X12"X6" RJ TEE	1	EA		
71	12"X12"X8" RJ TEE	6	EA		
72	12"X12"X10" RJ TEE	8	EA		
73	12"X12"X12" RJ TEE	2	EA		
74	STRADDLE BLOCKS	7	EA		
75	BORE AND JACK 24" STEEL CASING	91	LF		
UTILITY CORRIDOR					
76	TRENCHING - 5' CORRIDOR	8829	LF		
77	TRENCHING - 4' CORRIDOR (NO WATERMAIN)	320	LF		
78	TRENCHING - 8' CORRIDOR (W/NAT GAS)	730	LF		
79	OUT OF CORRIDOR TIE IN TRENCHING (W/SURFACE REST)	381	LF		
80	2" PE CONDUIT - ALTICE - COPPER AND FIBER	14342	LF		
81	2" GREY PE CONDUIT - WRC	20282	LF		
82	3" GREY PVC CONDUIT - WRE (INSTALL ONLY)	6342	LF		
83	3" GREY PVC CONDUIT - WRE	194	LF		
84	3" GREY PVC 90DEG ELBOW/SWEEP - WRE (INSTALL ONLY)	18	EA		
85	3" GREY PVC 90DEG ELBOW/SWEEP - WRE	8	EA		
86	3" GREY PVC 45DEG ELBOW/SWEEP - WRE	22	EA		
87	3" GREY PVC 22 1/2DEG ELBOW/SWEEP - WRE	11	EA		
88	3" GREY PVC11 1/4DEG ELBOW/SWEEP - WRE	1	EA		
89	3" GREY PVC11 1/4DEG ELBOW/SWEEP - WRE (INSTALL ONLY)	18	EA		
90	4" RED PVC CONDUIT - WRE	26592	LF		
91	4" RED PVC EXT. FML ADAPTER - WRE	200	EA		

W. 76 COUNTRY BLVD. STREETSCAPE - SEGMENTS 1 & 2 - EN7622
BID FORM - BASE BID - ADDENDUM 3

<u>Item No</u>	<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Price</u>	<u>Extension</u>
92	4" RED PVC 22 1/2DEG ELBOW/SWEEP - WRE	24	EA		
93	4" RED PVC 11 1/4 DEG ELBOW/SWEEP - WRE	23	EA		
94	4" GALV 90 DEG ELBOW - WRE	48	EA		
95	4" GALV 45 DEG ELBOW - WRE	52	EA		
96	4" GREY PVC CONDUIT - BS - SHO-ME - ALTICE	42796	LF		
97	4" GREY PVC 90DEG ELBOW/SWEEP - BS-SHO-ME - ALTICE	362	EA		
98	4" GREY PVC 45DEG ELBOW/SWEEP - BS-SHO-ME - ALTICE	90	EA		
99	4" GREY PVC 22 1/2DEG ELBOW/SWEEP - BS-SHO-ME - ALTICE	35	EA		
100	4" GREY PVC 11 1/4DEG ELBOW/SWEEP - BS-SHO-ME - ALTICE	56	EA		
101	WRE - 600 AMP 3PH JCT VAULT (INSTALL ONLY)	9	EA		
102	WRE - 200 AMP 3PH JCT VAULT (INSTALL ONLY)	10	EA		
103	WRE - 1PH TRANSFORMER VAULT (INSTALL ONLY)	2	EA		
104	WRE - 3PH TRANSFORMER VAULT (INSTALL ONLY)	1	EA		
105	WRE - FIBER VAULT (INSTALL ONLY)	12	EA		
106	WRE - SWITCHGEAR VAULT (INSTALL ONLY)	2	EA		
107	ALTICE VAULTS	40	EA		
108	ALTICE PEDESTALS	30	EA		
109	ALTICE POWER SUPPLY CONNECTIONS	2	EA		
110	SHO-ME TECH VAULT	10	EA		
111	BRIGHTSPEED HAND HOLE VAULTS	39	EA		
112	DUAL 2" PVC CONDUIT AT TIE IN	29	LF		
113	2" 90 DEG SWEEP RISERS AT BRIGHTSPEED PED/HANDHOL	36	EA		
114	BRIGHTSPEED PEDESTALS	39	EA		
115	WRC - VAULTS	26	EA		
116	DUAL 2" WHT PE CONDUIT - LIGHTING	8125	LF		
117	6" PVC CONDUIT - BRANSON	19116	LF		
118	6" PVC 90 DG SWEEPS - BRANSON	200	EA		
119	6" PVC 45 DG SWEEPS - BRANSON	36	EA		
120	6" PVC 22 1/2 DG SWEEPS - BRANSON	14	EA		
121	6" PVC 11 1/4 DG SWEEPS - BRANSON	24	EA		
122	BREAKOUT VAULTS 5X5 - BRANSON	26	EA		
123	BORE AND JACK 20" STEEL CASING - COMM	91	LF		
124	BORE AND JACK 14" STEEL CASING - POWER	91	LF		

W. 76 COUNTRY BLVD. STREETSCAPE - SEGMENTS 1 & 2 - EN7622
BID FORM - BASE BID - ADDENDUM 3

<u>Item No</u>	<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Price</u>	<u>Extension</u>
LIGHTING					
125	LIGHTING POLE, 30 FT. TYPE AT W/ 20A GFI RECEPTACLE	56	EA		
126	BRACKET ARM, 6 FT	56	EA		
127	LUMINAIRE, LED-A - TYPE IV	56	EA		
128	BASE MOUNTED CONTROL STATION 240 VOLT - 4 CIRCUIT	3	EA		
129	2 IN STEEL, IN TRENCH	21	LF		
130	DUAL CONDUIT, 2.5 IN RIGID, IN TRENCH	38	LF		
131	SINGLE CONDUIT, 2 IN RIGID, IN TRENCH IRRIG & ACCENT	2421	LF		
132	TRENCHING TYPE I	2480	LF		
133	PULL BOX, PREFORMED CLASS 1	6	LF		
134	CABLE, 2 AWG 1 CONDUCTOR	64	EA		
135	CABLE, 6 AWG 1 CONDUCTOR	18822	LF		
136	CABLE, 8 AWG 1 CONDUCTOR	44951	LF		
137	POWER SUPPLY ASSEMBLY, TYPE 2, 240/120 VOLT SERVICE	3	EA		
138	POLE BASE, REINFORCED CONCRETE	56	EA		
139	CONTROLLER BASE, REINFORCED CONCRETE	3	EA		
140	ACCENT LIGHTING PULL BOX	13	EA		
141	IRRIGATION POWER PULL BOX	8	EA		
GRADING					
142	LINEAR GRADING ALONG CURBLINE AND WALKWAYS	11066	LF		
143	EMBANKMENT (RETAINING WALLS 1 & 2)	4665	CY		
144	EMBANKMENT STA 158+00 TO 161+00	555	CY		
145	ROADWAY EXCAVATION STA 120+85 TO 126+40	1344	CY		
146	LANDSCAPE EMBANKMENT/BERMING	60	CY		
147	CURB WALL TYPE-S	488	LF		
148	CURB WALL TYPE-A	120	LF		
149	GRADING FOR DRIVE STA 150+60	126	CY		
RETAINING WALLS					
150	REDI -ROCK RETAINING WALL - VERTICAL FACE	4032	SF		
151	SCUPPERS WITH RISERS FROM DRAIN PIPE	9	EA		
152	SCUPPER DRAIN 6"	379	LF		
153	SCUPPER OUTLET AND SPLASH PAD	2	EA		

W. 76 COUNTRY BLVD. STREETSCAPE - SEGMENTS 1 & 2 - EN7622
BID FORM - BASE BID - ADDENDUM 3

<u>Item No</u>	<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Price</u>	<u>Extension</u>
PAVEMENT					
154	ASPHALT MILLING 2"	12297	SY		
155	CONCRETE SIDEWALK, 4 IN. - BROOM FINISHED (TIE IN)	54	SY		
156	CONCRETE SIDEWALK - COLORED IMPRINTED, 6 IN.	6763	SY		
157	CONCRETE SIDEWALK SEALING	8834	SY		
158	CONCRETE SHOULDER - 6"	44	SY		
159	CONCRETE CURB RAMP APPROACH (DRIVE AND ROAD)	98	EA		
160	TRUNCATED DOMES - VANGUARD BLACK	224	SF		
161	TYPE 1 AGGREGATE FOR BASE (4 IN. THICK)	6997	SY		
162	TYPE 1 AGGREGATE FOR BASE (6 IN. THICK)	2085	SY		
163	ASPHALT FULL DEPTH PAVEMENT 11.5"	2085	SY		
164	ASPH SP125 (2" BITUMINOUS OVERLAY)	12297	SY		
165	CURB AND GUTTER TYPE A	760	LF		
166	CURB AND GUTTER TYPE CG-1	4906	LF		
167	CURB AND GUTTER MODOT TYPE A TO CG-1 TRANSITION	20	LF		
168	5' ASPHALT PAVED SHOULDER REPLACEMENT	422	SY		
DRIVEWAYS					
169	DRIVE SUBGRADE PREPARATION	8059	SY		
170	GRADING FOR GUTTER SWALE ALONG EDGE OF ROAD	3239	LF		
171	GRADING FOR ADA PATH CROSS SLOPE ACROSS DRIVE	1911	LF		
172	6" ASPHALTIC CONC PAVEMENT WITH 6" COMP AGG BASE	2519	SY		
173	8" CONCRETE DRIVEWAY APPROACH PAVEMENT W/AGG BASE	3794	SY		
174	DUAL 6" PVC ANCILLARY SERVICE CONDUITS	2965	LF		
175	MARKERS FOR CONDUIT ENDS	140	EA		
176	TYPE CG-1 CURB AND GUTTER - SPILL AND CATCH	2916	LF		
177	CONC DRIVE SIDEWALK CROSSING COLORED AND IMPRINTED 8"	1263	SY		

W. 76 COUNTRY BLVD. STREETSCAPE - SEGMENTS 1 & 2 - EN7622
BID FORM - BASE BID - ADDENDUM 3

<u>Item No</u>	<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Price</u>	<u>Extension</u>
STRIPING AND SIGNING					
178	THERMO PLASTIC STOP BARS - WT 24"	121	LF		
179	THERMO PLASTIC YIELD MARKERS - WT	14	LF		
180	THERMO PLASTIC 6" BROKEN STRIPE YELLOW	8730	LF		
181	THERMO PLASTIC 6" SOLID STRIPE YELLOW	9264	LF		
182	THERMOPLASTIC 6" CROSS WALK STRIPES	1083	LF		
183	THERMOPLASTIC LT ARROWS	34	EA		
184	2" STEEL SIGN POSTS	51	EA		
185	POST MOUNTED SIGNS W/MOUNTING BRACKETS	245	SF		
186	PAINTED 4" SOLID WHITE - PARKING LOT	316	LF		
187	PAINTED 4" SOLID BLUE - PARKING LOT	36	LF		
188	PAINTED HANDICAP LOADING ZONE - PARKING LOT	2	EA		
189	PAINTED HANDICAP SYMBOL - PARKING LOT	3	EA		
190	THERMO PLASTIC 12" DOTTED STRIPE WHITE	131	LF		
191	THERMOPLASTIC - DIAGONAL CHEVRONS WT 24"	90	SF		
LANDSCAPE ARCHITECTURAL ELEMENTS					
Specialty Pavement - Entertainment Plaza Only					
192	PIANO KEY SIDEWALK - BOMANITE MICRO-TOP XT	2178	SF		
193	FLAGSTONE PAVERS	2283	SF		
194	PAVE EDGE	50	LF		
195	SYNTHETIC TURF	2499	SF		
196	4" MODOT TYPE 5 AGGREGATE BASE (SPECIALTY PAVEMENT)	532	SY		
Landscape					
197	CONCRETE RIBBON CURB (9" W X 18" H)	1361	LF		
198	ALUMINUM LANDSCAPE EDGING	1177	LF		
199	SOD	11312	SY		
200	DECIDUOUS TREE (2.5" CAL. B&B)	36	EA		
201	ORNAMENTAL TREES (1.5" CAL.)	7	EA		
202	#5 CONTAINER PLANTINGS (LARGE SHRUBS)	19	EA		
203	#3 CONTAINER PLANTINGS (SHRUBS)	1472	EA		
204	#1 CONTAINER PLANTINGS (GRASSES & PERNNIALS)	9624	EA		
205	QUART CONTAINER PLANTINGS (SEDGES)	9624	EA		
206	DAFFODIL PLANTINGS	3556	EA		
207	NATURAL STONE LANDSCAPE BOULDER (5FT - 6FT)	82	EA		

W. 76 COUNTRY BLVD. STREETSCAPE - SEGMENTS 1 & 2 - EN7622
BID FORM - BASE BID - ADDENDUM 3

<u>Item No</u>	<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Price</u>	<u>Extension</u>
208	NATURAL STONE LANDSCAPE BOULDER (3FT - 4FT)	61	EA		
209	OZARK DRY CREEK BED (6"-12" DECORATIVE COBBLE)	760	SF		
210	OZARK DRY CREEK BED (3" - 6" DECORATIVE COBBLE)	2091	SF		
211	OZARK DRY CREEK BED (1"-2" DECORATIVE COBBLE)	835	SF		
212	DECORATIVE ROCK MULCH (2" - 3" OZARK RIVER ROCK)	3771	SF		
213	GEOTEXTILE FABRIC	5862	SF		
214	PLANTING SOIL (RAISED PLANTERS)	83	CY		
215	IMPORTED TOPSOIL (6" DEPTH IN ALL LANDSCAPE AREAS)	3078	CY		
	Site Features				
216	NATURAL STONE VENEER WALL (54" HEIGHT)	1098	SFF		
217	WEATHERED STEEL PLANTER WALL WITH LIGHTING TYPE A (HEIG	1060	LF		
218	WEATHERED STEEL PLANTER WALL WITH LIGHTING TYPE B (HEIG	278	LF		
219	WEATHERED STEEL PLANTER WALL BENCH	8	EA		
220	PARKING LOT BARRIER SCREEN	320	LF		
221	PEDESTRIAN GUARDRAIL	512	LF		
222	CONCRETE AND SYNTHETIC TURF WAVY WALK	1	LS		
223	MUSIC NOTE SCULPTURE ALLOWANCE	1	LS		
224	PERCUSSION PLAY COLOSSUS CHIMES	1	LS		
225	PERCUSSION PLAY DJEMBE DRUMS	1	LS		
226	PERCUSSION PLAY PAPILO BELLS	1	LS		
227	GFRC BOULDERS (AT TOY MUSEUM)	1	LS		
228	GATEWAY AND RIBBON SCULPTURES ALLOWANCE	1	LS		
	Site Furnishings				
229	6 FT BENCH (FORMS & SURFACES 'CAMBER')	16	EA		
230	LOUNGE CHAIR (MAGLIN '720')	11	EA		
231	BIKE RACK	10	EA		
232	CUSTOM PORCH SWING	1	LS		
233	TABLE (VESTRE 'STRIPES')	2	EA		
	Landscape Irrigation System Elements				
234	IRRIGATION SYSTEM INSTALLED IN PLACE	1	LS		

TOTAL BASE BID: _____

**W. 76 COUNTRY BLVD. STREETSCAPE - SEGMENTS 1 & 2 - EN7622
 BID FORM - BASE BID - ADDENDUM 3**

<u>Item No</u>	<u>Description</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Price</u>	<u>Extension</u>
----------------	--------------------	-----------------	-------------	-------------------	------------------

BID FORM - ALTERNATE BID

156 a	DELETE ITEM 156 - CONCRETE SIDEWALK - COLORED IMPRINTED 6 IN FROM BID	-6763	SY -	_____	_____
156 b	STD 6' CONCRETE BROOM FINISHED SIDEWALK IN LEIU OF COLORED AND IMPRINTED CONCRETE PAVEMENT.	6763	SY	_____	_____
177 a	DELETE CONC DRIVE SIDEWALK CROSSING COLORED AND IMPRINTED 8"	-1263	SY -	_____	_____
177 b	ADD QUANTITY 8" CONCRETE DRIVEWAY APPROACH PAVEMENT W/AGG BASE	1263	SY	_____	_____
	(REVISED TOTAL QUANTITY 8" CONC DRIVE APPROACH)	5057	SY		

TOTAL ALTERNATE BASE BID: _____

The Bidder acknowledges that all notes shown on the plan drawings regarding parking lot light poles, signage, entrance and exit signs, planters, flagpoles, sculptures, and similar features are incidental to the Project. The Contractor shall be solely responsible for coordinating with property owners and for all associated design, structural calculations, shop drawings, and related work required for such relocations. All costs associated shall be borne by the Contractor.

_____, Signature

 Date