

ITEMIZED PROPOSAL

SUMMARY OF QUANTITIES					
NO.	BID ITEM	QUANTITY	UNIT	UNIT PRICE	AMOUNT
1	MOBILIZATION	1	LS		
2	DEMOLITION AND REMOVALS	1	LS		
3	EXCAVATION	11,789(CUT) 6,911(FILL)	CY		
4	SEEDING	17,609	SY		
5	10" PORTLAND CEMENT CONCRETE PAVEMENT	21,121	SY		
6	8" PORTLAND CEMENT CONCRETE PAVEMENT (RED TINTED)(TRUCK APRON)	1,968	SY		
7	6" PORTLAND CEMENT CONCRETE PAVEMENT (MEDIAN)	3,653	SY		
8	8" PCCP CENTER OF ROUNDABOUT	3,088	SY		
9	MODOT TYPE A CURB	4,684	LF		
10	MODOT TYPE F LOW PROFILE CURB	1,072	LF		
11	6" TYPE A (INTEGRAL) BARRIER CURB	829	LF		
12	6" MODOT TYPE 5 AGGREGATE BASE (TRUCK APRON)	1,968	SY		
13	6" MODOT TYPE 5 AGGREGATE BASE (ROADWAY)	23,203	SY		
14	SILT FENCE	9,410	LF		
15	INLET PROTECTION	66	EA		
16	STORM SEWER (18")(R.C.P.)	670	LF		
17	STORM SEWER (24")(R.C.P.)	1,485	LF		
18	STORM SEWER (36")(R.C.P.)	528	LF		
19	STORM SEWER (48")(R.C.P.)	125	LF		
20	APWA STD. JUNCTION BOX (7'X7' INSIDE)	1	EA		
21	8' DIA. STD. MANHOLE	1	EA		
22	APWA STD. JUNCTION BOX (6'X6' INSIDE)	1	EA		
23	APWA TYPE-1 CURB INLET (6'X5' INSIDE)	1	EA		
24	APWA TYPE-1 CURB INLET (6'X3' INSIDE)	1	EA		
25	APWA TYPE-1 CURB INLET (5'X5' INSIDE)	2	EA		
26	APWA TYPE-1 CURB INLET (5'X4' INSIDE)	12	EA		
27	APWA GRATE INLET (6'X5' INSIDE)	1	EA		
28	APWA GRATE INLET (6'X4' INSIDE)	1	EA		
29	STORM SEWER (24")(F.E.S.)	2	EA		
30	TEMPORARY STORM SEWER 18" FES	2	EA		
31	GRATE INLET (4'X4')	5	EA		
32	APWA TYPE-1 CURB INLET (5'X3' INSIDE)	3	EA		
33	REMOVE CURB INLET	14	EA		

34	REMOVE JUNCTION BOX	5	EA		
35	CONVERT EXISTING CURB INLET TO JUNCTION BOX	1	EA		
36	CONVERT EXISTING JUNCTION BOX TO CURB INLET	1	EA		
37	CONVERT CI TO GRATE INLET	1	EA		
38	LANE LINE (6" SOLID WHITE)	6,145	LF		
39	LANE LINE (6" DOTTED WHITE W/ 2' MARK & 4' SKIP)	560	LF		
40	6" DOUBLE SOLID YELLOW LINE	89	LF		
41	12" 3'/3' WHITE EXTENSION LINE	482	LF		
42	DASHED WHITE LINE	1,770	LF		
43	6" SOLID YELLOW LINE	4,634	LF		
44	TURNING ARROWS	22	EA		
45	LIGHTING POLE 30 FT TYPE AT	17	EA		
46	BRACKET ARM 12FT	17	EA		
47	LED TYPE A	17	EA		
48	BASE MOUNTED CONTROL STATION (240 VOLT 4 CIRCUIT)	1	EA		
49	CONDUIT 2 IN. RIGID PUSHED	645	LF		
50	CONDUIT 2 IN. RIGID IN TRENCH	15	LF		
51	TRENCHING TYPE 1	2,332	LF		
52	PULLBOX CONCRETE CLASS 1	13	EA		
53	CABLE 2AWG 1 CONDUCTOR	70	LF		
54	CABLE 10 AWG CONDUCTOR POLE AND BRACKET	1,615	LF		
55	CABLE CONDUIT 1 IN. 2 CONDUCTORS (AND BARE NEUTRAL 8 AWG)	4,670	LF		
56	POLE FOUNDATION 30 FT M.H.	17	EA		
57	CONSTRUCTION FURNISHED SURVEY AND STAKING	1	LS		
58	TEMPORARY TRAFFIC CONTROL CHANNELIZERS	514	EA		
59	TEMPORARY TRAFFIC CONTROL PAVEMENT MARKING	2,734	LF		
60	TEMPORARY TRAFFIC CONTROL TRAFFIC SIGNS	25	EA		
61	TEMPORARY PAVEMENT	1	LS		
62	TEMPORARY STORM SEWER (18")(R.C.P.)	40	LF		
63	DETOUR CHANGEABLE MESSAGE SIGN	3	EA		
64	DETOUR SIGNAGE	29	EA		
65	CONCRETE FOOTINGS, EMBEDDED	1.02	CY		
66	CONCRETE FOOTINGS, BOLT DOWN	132	CY		
67	STRUCTURAL STEEL POSTS	630	LBS		
68	PIPE POSTS	205.01	LBS		

69	BREAKAWAY ASSEMBLY (PERFORATED SQUARE STEEL TUBE)	10	EA		
70	2 IN. PSST POST, 12 GA	504.50	LF		
71	DRIVEN POST ANCHOR FOR 2 IN. PSST., 12 GA	50	EA		
72	2.25 IN. PSST POST INSERT (6 FT.), 12 GA	10	EA		
73	2.5 IN PSST POST - 12 GA	116	LF		
74	DRIVEN POST ANCHOR FOR 2.5 IN PSST - 7 GA	10	EA		
75	SH-FLAT SHEET	533	SF		
76	ST-STRUCTURAL	1,074.50	SF		
77	MISC OVERHEAD SIGN TRUSS	6	EA		
78	RELOCATE MISC SIGNS	29	EA		
79	GUARDRAIL TYPE E, 6FT POSTS, 6FT.-3IN. SPACING	250	LF		
80	GUARDRAIL TRANSITION SECTION, 6.5FT. POSTS	1	EA		
81	TYPE A CRASHWORTHY END TERMINAL	1	EA		
82	6" SOLID HDPE UNDERDRAIN PIPE	300	LF		
83	6" PERFORATED HDPE UNDERDRAIN PIPE	860	LF		