

Project Cost & Impacts:

\$3.6M (Concrete Option) / \$3.5M (Asphalt Option)  
Tentative New Right-of-Way = 2 Acres.

Safety Performance:

- Signals reduce crashes, especially with added turn lanes to reduce rear-end collisions.
- Signals are less likely to reduce high speed and higher severity crashes.

Traffic Performance:

- Operates with minimal delay during normal traffic.
- Signals would provide left turn arrows for turning traffic and slow moving farm equipment.

