



ISSUE DATE: **March 3, 2017**

ADDENDUM NUMBER 2

Project Number: **TAP 3301-494**

Project Title: **Brush Creek and Blue River Confluence Trail**

Bidders are hereby notified that the Bidding and Contract Documents for the above project, for which Bids are to be received on **March 8, 2017**, are amended as follows:

Information to Bidders The following is provided to Bidders for information only:

1.04 ENGINEER: HDR

2.01 This Addendum forms a part of the Contract Documents and modifies the Bidding Documents, with amendments and additions noted below.

Item #1-Unit Sheet. Revised unit sheet is attached. Item 11 should be changed to 850 s.f. of retaining wall.

NOTE: Bidders must acknowledge receipt of this Addendum by listing the number and date, where provided, on the Bid Form - Document 00410.

CERTIFICATE BY BIDDER/PROPOSER

I acknowledge receipt of this Addendum No. 1 for Project No **TAP 3301-494: Brush Creek Confluence Trail Improvements** and that the bid/proposal is in accordance with the information, instructions, and stipulations set forth herein.

By _____

Company _____

NOTE: This signed addendum notice must accompany your bid.



UNIT PRICES

Project Number TAP 3301 (494) Contract Number _____

Project Title Brush Creek Pedestrian Trail

NOTE: IN THE EVENT OF DISCREPANCY, UNIT PRICE SHALL GOVERN.

Item No.	Unit	Quantity	Item Description:	Unit Price	Extension
1	L.S.	1	MOBILIZATION		
2	L.F.	2925	CONTRACTOR CONSTRUCTION STAKING		
3	L.S.	1	CLEARING AND TREE REMOVAL		
4	L.F.	2925	LINEAR GRADING		
5	L.F.	750	SUBGRADE STABILIZATION		
6	S.Y.	3746	6" AGGREGATE BASE (MODOT TYPE 5)		
7	S.Y.	3250	REINFORCED P.C.C.P. TRAIL (6")		
8	EACH	2	ADA RAMPS WITH DETECTABLE WARNING PAVERS		
9	EACH	2	ACCESS CONTROL POSTS		
10	S.Y.	253	ROCK BLANKET (TYPE 2)		
11	S.F.	850	RETAINING WALL		
12	L.F.	780	FENCE		
13	L.F.	175	GUTTER (TYPE A)		
14	L.F.	137	30" RCP (CLASS III, MASTIC JT.) STORM SEWER		
15	L.F.	202	24" RCP (CLASS III, MASTIC JT.) STORM SEWER		
16	EACH	2	30" PRECAST CONCRETE FLARED END SECTION		
17	EACH	2	24" PRECAST CONCRETE FLARED END SECTION		
18	EACH	2	APWA FL-1 PRECAST CONCRETE INLET		
19	ACRE	2	SEEDING		
20	L.F.	6000	PERIMETER CONTROL		
21	EACH	4	INLET PROTECTION		
22	EACH	1	PEDESTRIAN CANOPY		
23	C.Y.	150	CLASS 1 EXCAVATION (PEDESTRIAN CANOPY)		
24	C.Y.	82.8	CLASS B-1 CONCRETE (SUBSTRUCTURE)(PEDESTRIAN CANOPY)		
25	LBS	5150	REINFORCING STEEL (PEDESTRIAN CANOPY) GRADE 60		
26	EACH	1	PEDESTRIAN BRIDGE		
27	C.Y.	79.7	CLASS I EXCAVATION		
28	L.F.	490	STRUCTURAL STEEL PILE (12 IN.)		
29	EACH	12	PILE POINT REINFORCEMENT		
30	C.Y.	53.8	CLASS B-1 CONCRETE (SUBSTRUCTURE)		
31	LBS	5470	REINFORCING STEEL (BRIDGES) GRADE 60		
32	EACH	9	TRAIL SIGNAGE		

Bidder: _____

			Total Unit Prices: (LAST PAGE ONLY)		TOTAL \$ #VALUE!

Note: May be printed, for manual fill-in, or filled in on electronic excel spreadsheet version.

- 3.1
- 2.7
- 2.1
- 2.3