


**TABLE OF CONTENTS**

A. Construction Requirements

 <p>THIS SHEET HAS BEEN SIGNED, SEALED AND DATED ELECTRONICALLY.</p>	<p><b>MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION</b> 105 W. CAPITOL AVE. JEFFERSON CITY, MO 65101 Phone (888) 275-6636</p>
	<p>If a seal is present on this sheet, JSP's has been electronically sealed and dated.</p>
	<p>JOB NO. J7P0601 McDonald County, MO Date Prepared: 11/6/2019</p>
<p>Only the following items of the Job Special Provisions (Bridge) are authenticated by this seal: A</p>	

JOB SPECIAL PROVISIONS (BRIDGE)

---

A. CONSTRUCTION REQUIREMENTS

**1.0 Description.** This provision contains general construction requirements for this project.

**2.0 Construction Requirements.** Plans for existing structure(s) are not applicable for this project; however, geotechnical investigation information is included in the contract in the bridge electronic deliverables zip file for informational purposes only.

**2.1** In order to assure the least traffic interference, the work shall be scheduled so that a lane closure is for the absolute minimum amount of time required to complete the work. A lane shall not be closed until material is available for continuous construction and the contractor is prepared to diligently pursue the work until the closed lane is opened to traffic.

**2.2** Bridge work by contractor forces, including erection, rehabilitation, or demolition, shall not be allowed over traffic unless a bridge platform protection system is installed below the work area except for work performed above a deck that is intact. The protection system shall be capable of catching all falling objects such as tools, overhang brackets or materials. Lifting of objects that are heavier than the capacity of the bridge protection system shall not be allowed.

**2.3** Provisions shall be made to prevent any debris and materials from falling into the stream, lake or onto the roadway. Any debris and materials that falls below the bridge outside the limits mentioned previously and if determined necessary by the engineer, the debris shall be removed as approved by the engineer at the contractor's expense. Traffic under the bridge shall be maintained in accordance with the contract documents.

**2.4** Any damage sustained to the remaining structure as a result of the contractor's operations shall be repaired or the material replaced as approved by the engineer at the contractor's expense.

**2.5** Provisions shall be made to prevent damage to any existing utilities. Any damage sustained to the utilities as a result of the contractor's operations shall be the responsibility of the contractor. All costs of repair and disruption of service shall be as determined by the utility owners and as approved by the engineer.

**3.0 Consultant Plans per Previous Missouri Standard Specifications for Highway Construction.** The base plans for Bridge Structures A6380 and A7000 and MSE Retaining Walls A7595, A7596, A7800 and A7801 were prepared in 2009 by Consultant per the 2004 Missouri Standard Specifications for Highway Construction and are provided without modification as contract documents for this project. References in these Consultant-prepared plans to Special Provisions for corrugated metal pipe for use as pipe pile spacers shall be disregarded. Pipe pile spacers shall be in accordance with the current Missouri Standard Specifications for Highway Construction.

**4.0 Method of Measurement.** No measurement will be made.

**5.0 Basis of Payment.** Payment for the above described work will be considered completely covered by the contract unit price for other items included in the contract.