MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

PLANS FOR PROPOSED STATE HIGHWAY

PRELIMINARY PLANS

JASPER COUNTY



JOB NO. J7S3059B
DAVIS BLVD.
ROADWAY REALIGNMENT
LENGTH = 0.234 MILE

BEGIN PROJECT
RELOCATED DAVIS BLVD.
STA. 94+65.00
LOG MILE 0.896

END PROJECT
RELOCATED DAVIS BLVD
STA. 107+00.00
LOG MILE 1.130

BEGIN PROJECT
RTE. FF
STA. 34+56.24
LOG MILE 2.677

END PROJECT
RTE. FF
STA. 39+28.96
LOG MILE 2.767

JOB NO. J7S3059B
RTE. FF RIGHT TURN LANE
LENGTH = 0.09 MILE

PRELIMINARY PLANS
SUBJECT TO CHANGE
11/27/2023

THE EXISTENCE AND APPROXIMATE LOCATION OF UTILITY FACILITIES KNOWN TO EXIST, AS SHOWN ON THE PLANS, ARE BASED ON THE BEST INFORMATION AVAILABLE TO THE COMMISSION AT THIS TIME. THIS INFORMATION IS PROVIDED BY THE COMMISSION "AS-IS" AND THE COMMISSION EXPRESSLY DISCLAIMS ANY REPRESENTATION OR WARRANTY AS TO THE COMPLETENESS, ACCURACY, OR SUITABILITY OF THE INFORMATION FOR ANY USE. RELIANCE UPON THIS INFORMATION IS DONE AT THE RISK AND PERIL OF THE USER, AND THE COMMISSION SHALL NOT BE LIABLE FOR ANY DAMAGES THAT MAY ARISE FROM ANY ERROR IN THE INFORMATION. IT IS, THEREFORE, THE RESPONSIBILITY OF THE CONTRACTOR TO VERIFY THE EXISTENCE, LOCATION AND STATUS OF ANY FACILITY. SUCH VERIFICATION INCLUDES DIRECT CONTACT WITH THE LISTED UTILITIES.

¼ 0 ½ 1

SCALE IN MILES

DESIGN DESIGNATION

A.A.D.T. - 2022 = 3,766
A.A.D.T. - 2047 = 5,240
P.H.V. = 10%
T = 16.85%
V = 45 M.P.H.
D (N/S) = 52.7%/47.3%

FUNCTIONAL CLASSIFICATION - MAJOR COLLECTOR

PARTIAL CONTROLLED ACCESS HIGHWAY

THIS SHALL BE A PARTIAL CONTROLLED ACCESS HIGHWAY, EXCEPT AT LOCATIONS AND AS OTHERWISE SPECIFICALLY SHOWN ON THESE PLANS. NO ABUTTER'S RIGHTS IN OR OF DIRECT ACCESS TO, FROM, OR ACROSS THE HIGHWAY OR ITS RIGHT-OF-WAY SHALL ATTACH OR BELONG TO ANY PROPERTY ABUTTING ON SAID SECTION OF HIGHWAY, OR TO ANY PERSON MERELY BECAUSE OF OWNERSHIP OF SUCH ABUTTING PROPERTY WHERE THE SYMBOL SHOWN BELOW IS SHOWN ON THE RIGHT-OF-WAY LINE.

BEGINNING AND ENDING OF CONTROLLED ACCESS

NO RIGHT OF ACCESS OR CROSSING OF LINES BEARING THIS SYMBOL WILL BE PERMITTED UNDER ANY CIRCUMSTANCES.

CONVENTIONAL SYMBOLS
(USED IN PLANS)

	EXISTING	NEW
BUILDINGS AND STRUCTURES		
GUARD RAIL		
GUARD CABLE		
CONCRETE RIGHT-OF-WAY MARKER		
STEEL RIGHT-OF-WAY MARKER		
LOCATION SURVEY MARKER		
UTILITIES		
FIBER OPTICS	-FO-	FO
OVERHEAD CABLE TV	-OTV-	OTV
UNDERGROUND CABLE TV	-UTV-	UTV
OVERHEAD TELEPHONE	-OT-	OT
UNDERGROUND TELEPHONE	-UT-	UT
OVERHEAD POWER	-OE-	OE
UNDERGROUND POWER	-UE-	UE
SANITARY SEWER	-S-	S
STORM SEWER	-SS-	SS
GAS	-G-	G
WATER	-W-	W
MANHOLE	SAN	
FIRE HYDRANT	HYD	
WATER VALVE	WV	
WATER METER	WM	
DROP INLET		
DITCH BLOCK		
GROUND MOUNTED SIGN		SIGN
LIGHT POLE		
H-FRAME POWER POLE		
TELEPHONE PEDESTAL		PED
FENCE		
CHAIN LINK	-V-	
WOVEN WIRE	-X-	
GATE POST		
BENCHMARK		BM

NOTE: DASHED OR OPEN SYMBOLS INDICATE EXISTING FEATURES

INDEX OF SHEETS

DESCRIPTION	SHEET NUMBER
TITLE SHEET	1
TYPICAL SECTIONS (TS) (4 SHEETS)	2
QUANTITIES (QU) (0 SHEETS)	3
PLAN SHEETS (PL)	4-6
PROFILE SHEETS (PR)	7-9
RIGHT OF WAY SHEETS (RW)	10-12
COORDINATE POINTS (CP)	13
SIGNAL SHEETS (SG)	14
SPECIAL SHEETS (SS)	-
TRAFFIC CONTROL SHEETS (TC)	-
EROSION CONTROL SHEETS (EC)	-
CROSS SECTIONS (XS)	1-19

LENGTH OF PROJECT

DAVIS BLVD.:
BEGINNING OF PROJECT STA. 94+65.00
END OF PROJECT STA. 107+00.00

RTE FF:
BEGINNING OF PROJECT STA. 34+56.24
END OF PROJECT STA. 39+28.96

APPARENT LENGTH 1707.72 FEET

EQUATIONS AND EXCEPTIONS: NONE

TOTAL CORRECTIONS 0.00 FEET
NET LENGTH OF PROJECT 1707.72 FEET
STATE LENGTH 0.323 MILES

FOR INFORMATION ONLY
ESTIMATED DISTURBED ACRES 2.31 ACRES

Preliminary Plans - NOT FOR CONSTRUCTION

DATE PREPARED 11/27/2023
ROUTE FF | STATE MO
DISTRICT SW | SHEET NO. 1
COUNTY JASPER
JOB NO. J7S3059B
CONTRACT ID.
PROJECT NO.
BRIDGE NO.

DESCRIPTION | DATE

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL
JEFFERSON CITY, MO 65102
1-888-ASK-MODOT (1-888-275-6636)

Hg Consult inc engineers planners
9111 NE 79th Street; Kansas City, MO 64158; (816)912-4720
Hg CONSULT, INC.
PRO. ENGINEER 2010005873