



CONTRACTOR NAME: _____
 ADDRESS LINE 1: _____
 ADDRESS LINE 2: _____
 PHONE NUMBER: _____
 EMAIL: _____

PULASKI COUNTY
 BRIDGE 2060015
 BRO-B085 (4) and STP 9900(930)

DATE: _____

ITEMIZED BID FORM

LINE	ITEM	DESCRIPTION	UNITS	QUANTITY	UNIT PRICE	AMOUNT
ROADWAY ITEMS						
1	618	MOBILIZATION	L.S.	1		\$ _____
2	801/805	FERTILIZING AND SEEDING	AC.	1.2	\$ _____	\$ _____
3	802	TYPE 1 MULCH	AC.	1.2	\$ _____	\$ _____
4	616	MOVEABLE BARRICADES	EA.	4	\$ _____	\$ _____
5	616	CONSTRUCTION SIGNS	EA.	2	\$ _____	\$ _____
6	616	FURNISH & INSTALL LOAD LIMIT & LOW CLEARANCE SIGNS ON POSTS	EA.	4	\$ _____	\$ _____
7	616	FURNISH & INSTALL CLEARANCE DIMENSION SIGNS ON BRIDGE	EA.	2	\$ _____	\$ _____
8	806	SILT FENCE OR SILT SOCK	L.F.	160	\$ _____	\$ _____
9	203/401	REPAIR SOUTH APPROACH PAVEMENT	L.S.	1		\$ _____
SUBTOTAL ROADWAY ITEMS						\$ _____
BRIDGE ITEMS						
10	216	REMOVAL OF EXISTING CONCRETE DECK	S.Y.	940	\$ _____	\$ _____
11	206	REMOVAL OF EXPANSION JOINTS	EA.	3	\$ _____	\$ _____
12	706	REPLACE EXPANSION JOINTS	EA.	3	\$ _____	\$ _____
13	703	CLASS B CONCRETE WINGWALL	C.Y.	4.2	\$ _____	\$ _____
14	703	CLASS B-2 CONCRETE DECK	C.Y.	222.0	\$ _____	\$ _____
15	703	CLASS B-2 CONCRETE CURB	L.F.	806.0	\$ _____	\$ _____
16	712	REPLACE BOTTOM BRACE GUSSET PLATES	EA.	23	\$ _____	\$ _____
17	712	RELACE EXTERIOR STRINGERS	LB.	40,300	\$ _____	\$ _____
18	712	RELACE FLOOR BEAMS	LB.	6,426	\$ _____	\$ _____
19	712	STRENGTHEN PONY TRUSS TOP CHORD	LB.	1,998	\$ _____	\$ _____
20	712	STENGTHEN PONY TRUSS BOTTOM CHORD	LB.	1,082	\$ _____	\$ _____
21	712	REPAIR PONY TRUSS BOTTOM CHORD W/SPLICE	LB.	940	\$ _____	\$ _____
22	712	STRENGTHEN THROUGH TRUSS VERTICAL CROSS BRACES	LB.	976	\$ _____	\$ _____
23	712	REPAIR TRUSS HORIZONTAL CROSS BRACE	LB.	363	\$ _____	\$ _____
24	712	INSTALL BOLTS IN EMPTY RIVET HOLES	EA.	5	\$ _____	\$ _____
25	712	BRIDGE RAILING REPAIR	L.S.	1		\$ _____

26	704	REMOVE EFFLORESCENCE	S.F.	1,280	\$	\$
27	704	CONCRETE SUPERSTRUCTURE HAIRLINE CRACK SEAL	S. F.	36	\$	\$
28	704	CONCRETE OPEN CRACK REPAIR	S. F.	672	\$	\$
29	704	CONCRETE SPALL WITH EXPOSED REBAR REPAIR	S. F.	459	\$	\$
30	216	MILLING OF ASPHALT WEARING SURFACE	S.Y.	381.7	\$	\$
31	1036	EPOXY REINFORCING STEEL IN DECK	LB.	53,632	\$	\$
32	1036	PLAIN REINFORCING STEEL IN WINGWALL	LB.	292	\$	\$
33	712	CLEAN AND LUBRICATE ROCKER BEARINGS	EA.	8	\$	\$
34	712	CLEAN AND LUBRICATE STEEL PLATE BEARINGS	EA.	2	\$	\$
35	712	INSTALL DECK DRAINS IN EXISTING DECK	EA.	34	\$	\$
36	712	INSTALL DECK DRAINS IN NEW DECK	EA.	78	\$	\$
37	725	EXCAVATE AND INSTALL 6" ABUTMENT DRAIN	L.S.	1		\$
38	706 203/504	REPAIR ROCK WALL IN SOUTH ABUTMENT	S.Y.	6	\$	\$
39	1081.5	SP3 SURFACE PREPARATION STRUCTURAL STEEL	S.F.	34,300	\$	\$
40	1081.5	CALCIUM SULFONATE SYSTEM OVERCOATING OF STRUCTURAL STEEL	S.F.	34,300	\$	\$
TOTAL BASE AMOUNT						\$
SUBTOTAL BRIDGE ITEMS						
BID ALTERNATE 1 - RECOATING STRUCTURAL STEEL						
A2-1	712	SP6 SURFACE PREPARATION STRUCTURAL STEEL	S.F.	34,300	\$	\$
A2-2	712	FIELD APPLIED INORGANIC ZINC PRIMER	S.F.	34,300	\$	\$
A2-3	712	INTERMEDIATE FIELD COAT (SYSTEM G)	S.F.	34,300	\$	\$
A2-4	712	FINISH FIELD COAT (SYSTEM G)	S.F.	34,300	\$	\$
TOTAL BID ALTERNATE 1						\$
TOTAL BASE MINUS ITEMS 38 AND 39 PLUS BID ALTERNATE 1						\$

We acknowledge receipt of the following Addenda:

Addendum No.

Date

_____	_____
_____	_____
_____	_____
_____	_____

By: _____