

ADDENDUM NO. 1

**Sidewalk Improvements Project
New Bloomfield, Missouri
Federal Project No. TAP 9901311**

October 28, 2026

Dear Plan Holder:

Please read the following addendum carefully and make certain your bid proposal reflects the following information. Please acknowledge by completing the information at the end of this document and submitting this Addendum with the bid proposal.

1. The proposed concrete sidewalk section shall consist of 4" thick reinforced concrete (#4 bars at 24" O.C. E.W.) on 4" compacted aggregate base (1" rolled stone baserock – MoDOT Type 1 or Type 5 allowed). Reinforcement shall be considered subsidiary to Bid Form Item 1.03 – 4" Concrete Sidewalk.
2. The proposed concrete driveway section shall consist of 6" thick reinforced concrete (#4 bars at 24" O.C. E.W.) on 4" compacted aggregate base (1" rolled stone baserock – MoDOT Type 1 or Type 5 allowed). Reinforcement shall be considered subsidiary to Bid Form Item 1.04 – 6" Concrete Pavement.
3. Macro-synthetic fiber reinforcement is not required for the proposed concrete sidewalk or concrete driveway.

This addendum will be incorporated into the bid information and contract documents.

Acknowledge of Receipt

Bidder

Signature

Date

Printed Signature