



PART PLAN SHOWING REINFORCEMENT




With the approval of the engineer, the contractor may crown the bottom of the approach slab to match the crown of the roadway surface.




SECTION C-C

BRIDGE APPROACH SLAB (MAJOR)



UNDERSEAL ACCESS HOLE DETAIL

(If required)



CONSTRUCTION JOINT DETAIL

### General Notes:

All concrete for the bridge approach slab and sleeper slab shall be in accordance with Sec 503 ( $f'c = 4,000$  psi).

The reinforcing steel in the bridge approach slab and the sleeper slab shall be epoxy coated Grade 60 with  $f_y = 60,000$  psi.

Drain pipe may be either 6" diameter corrugated metallic-coated pipe underdrain, 4" diameter corrugated polyvinyl chloride (PVC) drain pipe, or 4" diameter corrugated polyethylene (PE) drain pipe.

Minimum clearance to reinforcing steel shall be 1 1/2", unless otherwise shown.

The reinforcing steel in the bridge approach slab and the sleeper slab shall be continuous. The transverse reinforcing steel may be made continuous by providing a minimum lap splice of 29 inches for #5 bars and 44 inches for #6 bars, or by mechanical bar splice.

Mechanical bar splices shall be in accordance with Sec 710.

All joint filler shall be in accordance with Sec 1057 for preformed fiber expansion joint filler except as noted.

The contractor shall pour and satisfactorily finish the bridge slab before placing the bridge approach slab.


Longitudinal construction joints in approach slab and sleeper slab shall be aligned with longitudinal construction joints in bridge slab.

For concrete approach pavement details, see roadway plans.

See Missouri Standard Plan 609.00 for details of Type A curb.

Payment for furnishing all materials, labor and excavation necessary to construct the approach slab, including the timber header, sleeper slab, underdrain, Type 5 aggregate base, joint filler and all other appurtenances and incidental work as shown on this sheet, complete in place, will be considered completely covered by the contract unit price for Bridge Approach Slab (Major) per square yard.

\* Seal joint between vertical face of approach slab and wing with sealant in accordance with Sec 717 for silicone joint sealant for saw cut and formed joints.



DETAILS OF TIMBER HEADER

Remove timber header when concrete pavement is placed.

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.


Sheet No. of

DATE PREPARED	
10/12/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	000
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-273-6636)	

Standard Drawing Guidance (do not show on plans):

See Structural Project Manager or Liaison for preference on revising details as follows to specify staged construction.

① Show & call out any required staged construction joints.



② Show any required construction joints and show and call out any mechanical bar splices.




③ When mechanical bar splices are required due to staged construction, add the following after the indicated note:  
(Estimated \_\_\_ splices per slab)


Input the estimated number of required mechanical bar splices including those in the sleeper slab.

④ See Notes K1.11 and K1.12 in EPG 751.50 for wording of notes when semi-deep abutments are used.

⑤ If the end of a wing wall extends beyond the end of the bridge approach slab, it will be necessary to revise the length of the sleeper slab shown and to redirect the perforated drain pipe adjacent to the sleeper slab to go under the sleeper slab and then turn to daylight. This should be nonperforated drain pipe at this point.




SECTION A-A




SECTION BETWEEN BARRIER AND CURB

ALTERNATE DETAILS FOR TYPE B BARRIER (SBC)






PART PLAN SHOWING REINFORCEMENT




SECTION B-B

With the approval of the engineer, the contractor may crown the bottom of the approach slab to match the crown of the roadway surface.




SECTION C-C

BRIDGE APPROACH SLAB (MAJOR)



UNDERSEAL ACCESS HOLE DETAIL

(If required)



CONSTRUCTION JOINT DETAIL

General Notes:

All concrete for the bridge approach slab and sleeper slab shall be in accordance with Sec 503 ( $f'c = 4,000$  psi).

The reinforcing steel in the bridge approach slab and the sleeper slab shall be epoxy coated Grade 60 with  $f_y = 60,000$  psi.

Drain pipe may be either 6" diameter corrugated metallic-coated pipe underdrain, 4" diameter corrugated polyvinyl chloride (PVC) drain pipe, or 4" diameter corrugated polyethylene (PE) drain pipe.

Minimum clearance to reinforcing steel shall be 1 1/2", unless otherwise shown.

The reinforcing steel in the bridge approach slab and the sleeper slab shall be continuous. The transverse reinforcing steel may be made continuous by providing a minimum lap splice of 29 inches for #5 bars and 44 inches for #6 bars, or by mechanical bar splice.

Mechanical bar splices shall be in accordance with Sec 710.

All joint filler shall be in accordance with Sec 1057 for preformed fiber expansion joint filler except as noted.

The contractor shall pour and satisfactorily finish the bridge slab before placing the bridge approach slab.


Longitudinal construction joints in approach slab and sleeper slab shall be aligned with longitudinal construction joints in bridge slab.

For concrete approach pavement details, see roadway plans.


See Missouri Standard Plan 609.00 for details of Type A curb.

Payment for furnishing all materials, labor and excavation necessary to construct the approach slab, including the timber header, sleeper slab, underdrain, Type 5 aggregate base, joint filler and all other appurtenances and incidental work as shown on this sheet, complete in place, will be considered completely covered by the contract unit price for Bridge Approach Slab (Major) per square yard.

\* Seal joint between vertical face of approach slab and wing with sealant in accordance with Sec 717 for silicone joint sealant for saw cut and formed joints.



SECTION BETWEEN CURB AND BARRIER



SECTION D-D

PART ELEVATION

DETAILS OF TIMBER HEADER


Remove timber header when concrete pavement is placed.

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of


DATE PREPARED	
10/12/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	2
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	

Standard Drawing Guidance (do not show on plans):

See Structural Project Manager or Liaison for preference on revising details as follows to specify staged construction.

① Show & call out any required staged construction joints.



② Show any required construction joints and show and call out any mechanical bar splices.





③ When mechanical bar splices are required due to staged construction, add the following after the indicated note:  
(Estimated \_\_\_ splices per slab)


Input the estimated number of required mechanical bar splices including those in the sleeper slab.

④ See Notes K1.11 and K1.12 in EPG 751.50 for wording of notes when semi-deep abutments are used.


⑤ If the end of a wing wall extends beyond the end of the bridge approach slab, it will be necessary to revise the length of the sleeper slab shown and to redirect the perforated drain pipe adjacent to the sleeper slab to go under the sleeper slab and then turn to daylight. This should be nonperforated drain pipe at this point.



ALTERNATE DETAILS FOR TYPE B BARRIER (SBC)




PART PLAN SHOWING REINFORCEMENT



SECTION A-A


SECTION B-B

With the approval of the engineer, the contractor may crown the bottom of the approach slab to match the crown of the roadway surface.




SECTION C-C

BRIDGE APPROACH SLAB (MAJOR)



UNDERSEAL ACCESS HOLE DETAIL

(If required)



CONSTRUCTION JOINT DETAIL

General Notes:

All concrete for the bridge approach slab and sleeper slab shall be in accordance with Sec 503 ( $f'c = 4,000$  psi).

The reinforcing steel in the bridge approach slab and the sleeper slab shall be epoxy coated Grade 60 with  $f_y = 60,000$  psi.

Drain pipe may be either 6" diameter corrugated metallic-coated pipe underdrain, 4" diameter corrugated polyvinyl chloride (PVC) drain pipe, or 4" diameter corrugated polyethylene (PE) drain pipe.

Minimum clearance to reinforcing steel shall be 1 1/2", unless otherwise shown.

The reinforcing steel in the bridge approach slab and the sleeper slab shall be continuous. The transverse reinforcing steel may be made continuous by providing a minimum lap splice of 29 inches for #5 bars and 44 inches for #6 bars, or by mechanical bar splice.

Mechanical bar splices shall be in accordance with Sec 710.

All joint filler shall be in accordance with Sec 1057 for preformed fiber expansion joint filler except as noted.

The contractor shall pour and satisfactorily finish the bridge slab before placing the bridge approach slab.


Longitudinal construction joints in approach slab and sleeper slab shall be aligned with longitudinal construction joints in bridge slab.

For concrete approach pavement details, see roadway plans.

See Missouri Standard Plan 609.00 for details of Type A curb.

Payment for furnishing all materials, labor and excavation necessary to construct the approach slab, including the timber header, sleeper slab, underdrain, Type 5 aggregate base, joint filler and all other appurtenances and incidental work as shown on this sheet, complete in place, will be considered completely covered by the contract unit price for Bridge Approach Slab (Major) per square yard.

\* Seal joint between vertical face of approach slab and wing with sealant in accordance with Sec 717 for silicone joint sealant for saw cut and formed joints.



SECTION D-D

PART ELEVATION

DETAILS OF TIMBER HEADER

Remove timber header when concrete pavement is placed.

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

DATE PREPARED  
10/12/2023

ROUTE STATE

DISTRICT SHEET NO.

COUNTY

JOB NO.

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL

JEFFERSON CITY, MO 65102


1-888-ASK-MODOT (1-888-273-6636)

MODOT

Standard Drawing Guidance (do not show on plans):

See Structural Project Manager or Liaison for preference on revising details as follows to specify staged construction.

① Show & call out any required staged construction joints.



② Show any required construction joints and show and call out any mechanical bar splices.




③ When mechanical bar splices are required due to staged construction, add the following after the indicated note:  
(Estimated \_\_\_ splices per slab)


Input the estimated number of required mechanical bar splices including those in the sleeper slab.

④ See Notes K1.11 and K1.12 in EPG 751.50 for wording of notes when semi-deep abutments are used.

⑤ If the end of a wing wall extends beyond the end of the bridge approach slab, it will be necessary to revise the length of the sleeper slab shown and to redirect the perforated drain pipe adjacent to the sleeper slab to go under the sleeper slab and then turn to daylight. This should be nonperforated drain pipe at this point.




SECTION A-A




SECTION BETWEEN  
BARRIER AND CURB

ALTERNATE DETAILS FOR TYPE B BARRIER (SBC)




PART PLAN SHOWING REINFORCEMENT






SECTION B-B

With the approval of the engineer, the contractor may crown the bottom of the approach slab to match the crown of the roadway surface.



SECTION C-C



SECTION BETWEEN CURB AND BARRIER

General Notes:

All concrete for the bridge approach slab and sleeper slab shall be in accordance with Sec 503 ( $f'c = 4,000$  psi).

The reinforcing steel in the bridge approach slab and the sleeper slab shall be epoxy coated Grade 60 with  $f_y = 60,000$  psi.

Drain pipe may be either 6" diameter corrugated metallic-coated pipe underdrain, 4" diameter corrugated polyvinyl chloride (PVC) drain pipe, or 4" diameter corrugated polyethylene (PE) drain pipe.

Minimum clearance to reinforcing steel shall be 1 1/2", unless otherwise shown.

The reinforcing steel in the bridge approach slab and the sleeper slab shall be continuous. The transverse reinforcing steel may be made continuous by providing a minimum lap splice of 29 inches for #5 bars and 44 inches for #6 bars, or by mechanical bar splice.

Mechanical bar splices shall be in accordance with Sec 710.

All joint filler shall be in accordance with Sec 1057 for preformed fiber expansion joint filler except as noted.

The contractor shall pour and satisfactorily finish the bridge slab before placing the bridge approach slab.


Longitudinal construction joints in approach slab and sleeper slab shall be aligned with longitudinal construction joints in bridge slab.

For concrete approach pavement details, see roadway plans.

See Missouri Standard Plan 609.00 for details of Type A curb.

Payment for furnishing all materials, labor and excavation necessary to construct the approach slab, including the timber header, sleeper slab, underdrain, Type 5 aggregate base, joint filler and all other appurtenances and incidental work as shown on this sheet, complete in place, will be considered completely covered by the contract unit price for Bridge Approach Slab (Major) per square yard.

\* Seal joint between vertical face of approach slab and wing with sealant in accordance with Sec 717 for silicone joint sealant for saw cut and formed joints.



SECTION D-D

PART ELEVATION

DETAILS OF TIMBER HEADER

Remove timber header when concrete pavement is placed.

BRIDGE APPROACH SLAB (MAJOR)

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

DATE PREPARED  
10/12/2023

ROUTE STATE  
MO

DISTRICT SHEET NO.  
4

COUNTY

JOB NO.

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE

DATE


DATE

DATE

Standard Drawing Guidance (do not show on plans):

See Structural Project Manager or Liaison for preference on revising details as follows to specify staged construction.

① Show & call out any required staged construction joints.



② Show any required construction joints and show and call out any mechanical bar splices.





③ When mechanical bar splices are required due to staged construction, add the following after the indicated note:  
(Estimated \_\_\_ splices per slab)

Input the estimated number of required mechanical bar splices including those in the sleeper slab.


④ See Notes K1.11 and K1.12 in EPG 751.50 for wording of notes when semi-deep abutments are used.

⑤ If the end of a wing wall extends beyond the end of the bridge approach slab, it will be necessary to revise the length of the sleeper slab shown and to redirect the perforated drain pipe adjacent to the sleeper slab to go under the sleeper slab and then turn to daylight. This should be nonperforated drain pipe at this point.




ALTERNATE DETAILS FOR TYPE B BARRIER (SBC)






PART PLAN SHOWING REINFORCEMENT




SECTION B-B

With the approval of the engineer, the contractor may crown the bottom of the approach slab to match the crown of the roadway surface.




SECTION C-C

BRIDGE APPROACH SLAB (MAJOR)



UNDERSEAL ACCESS HOLE DETAIL

(If required)



CONSTRUCTION JOINT DETAIL

General Notes:

All concrete for the bridge approach slab and sleeper slab shall be in accordance with Sec 503 ( $f'c = 4,000$  psi).

The reinforcing steel in the bridge approach slab and the sleeper slab shall be epoxy coated Grade 60 with  $f_y = 60,000$  psi.

Drain pipe may be either 6" diameter corrugated metallic-coated pipe underdrain, 4" diameter corrugated polyvinyl chloride (PVC) drain pipe, or 4" diameter corrugated polyethylene (PE) drain pipe.

Minimum clearance to reinforcing steel shall be 1 1/2", unless otherwise shown.

The reinforcing steel in the bridge approach slab and the sleeper slab shall be continuous. The transverse reinforcing steel may be made continuous by providing a minimum lap splice of 29 inches for #5 bars and 44 inches for #6 bars, or by mechanical bar splice.

Mechanical bar splices shall be in accordance with Sec 710.

All joint filler shall be in accordance with Sec 1057 for preformed fiber expansion joint filler except as noted.

The contractor shall pour and satisfactorily finish the bridge slab before placing the bridge approach slab.


Longitudinal construction joints in approach slab and sleeper slab shall be aligned with longitudinal construction joints in bridge slab.

For concrete approach pavement details, see roadway plans.


See Missouri Standard Plan 609.00 for details of Type A curb.

Payment for furnishing all materials, labor and excavation necessary to construct the approach slab, including the timber header, sleeper slab, underdrain, Type 5 aggregate base, joint filler and all other appurtenances and incidental work as shown on this sheet, complete in place, will be considered completely covered by the contract unit price for Bridge Approach Slab (Major) per square yard.

\* Seal joint between vertical face of approach slab and wing with sealant in accordance with Sec 717 for silicone joint sealant for saw cut and formed joints.



SECTION BETWEEN CURB AND BARRIER



SECTION D-D

PART ELEVATION

DETAILS OF TIMBER HEADER

Remove timber header when concrete pavement is placed.

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

DATE PREPARED  
10/12/2023

ROUTE STATE

DISTRICT SHEET NO.

COUNTY

JOB NO.

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL

JEFFERSON CITY, MO 65102


1-888-ASK-MODOT (1-888-273-6636)

MODOT

Standard Drawing Guidance (do not show on plans):

See Structural Project Manager or Liaison for preference on revising details as follows to specify staged construction.

① Show & call out any required staged construction joints.



② Show any required construction joints and show and call out any mechanical bar splices.




③ When mechanical bar splices are required due to staged construction, add the following after the indicated note:  
(Estimated \_\_\_ splices per slab)


Input the estimated number of required mechanical bar splices including those in the sleeper slab.

④ See Notes K1.11 and K1.12 in EPG 751.50 for wording of notes when semi-deep abutments are used.

⑤ If the end of a wing wall extends beyond the end of the bridge approach slab, it will be necessary to revise the length of the sleeper slab shown and to redirect the perforated drain pipe adjacent to the sleeper slab to go under the sleeper slab and then turn to daylight. This should be nonperforated drain pipe at this point.




SECTION A-A




SECTION BETWEEN  
BARRIER AND CURB


ALTERNATE DETAILS FOR TYPE B BARRIER (SBC)



PART PLAN SHOWING REINFORCEMENT




SECTION A-A




SECTION B-B

With the approval of the engineer, the contractor may crown the bottom of the approach slab to match the crown of the roadway surface.




SECTION C-C



UNDERSEAL ACCESS HOLE DETAIL

(If required)



CONSTRUCTION JOINT DETAIL

General Notes:

All concrete for the bridge approach slab and sleeper slab shall be in accordance with Sec 503 ( $f'c = 4,000$  psi).

The reinforcing steel in the bridge approach slab and the sleeper slab shall be epoxy coated Grade 60 with  $f_y = 60,000$  psi.

Drain pipe may be either 6" diameter corrugated metallic-coated pipe underdrain, 4" diameter corrugated polyvinyl chloride (PVC) drain pipe, or 4" diameter corrugated polyethylene (PE) drain pipe.

Minimum clearance to reinforcing steel shall be 1 1/2", unless otherwise shown.

The reinforcing steel in the bridge approach slab and the sleeper slab shall be continuous. The transverse reinforcing steel may be made continuous by providing a minimum lap splice of 29 inches for #5 bars and 44 inches for #6 bars, or by mechanical bar splice.

Mechanical bar splices shall be in accordance with Sec 710.

All joint filler shall be in accordance with Sec 1057 for preformed fiber expansion joint filler except as noted.

The contractor shall pour and satisfactorily finish the bridge slab before placing the bridge approach slab.


Longitudinal construction joints in approach slab and sleeper slab shall be aligned with longitudinal construction joints in bridge slab.

For concrete approach pavement details, see roadway plans.


See Missouri Standard Plan 609.00 for details of Type A curb.

Payment for furnishing all materials, labor and excavation necessary to construct the approach slab, including the timber header, sleeper slab, underdrain, Type 5 aggregate base, joint filler and all other appurtenances and incidental work as shown on this sheet, complete in place, will be considered completely covered by the contract unit price for Bridge Approach Slab (Major) per square yard.

\* Seal joint between vertical face of approach slab and wing with sealant in accordance with Sec 717 for silicone joint sealant for saw cut and formed joints.



SECTION BETWEEN CURB AND BARRIER



SECTION D-D

PART ELEVATION

DETAILS OF TIMBER HEADER

Remove timber header when concrete pavement is placed.

BRIDGE APPROACH SLAB (MAJOR)

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

DATE PREPARED  
10/12/2023

ROUTE STATE

DISTRICT SHEET NO.

COUNTY

JOB NO.

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL

JEFFERSON CITY, MO 65102


1-888-ASK-MODOT (1-888-273-6636)

MODOT

Standard Drawing Guidance (do not show on plans):

See Structural Project Manager or Liaison for preference on revising details as follows to specify staged construction.

① Show & call out any required staged construction joints.



② Show any required construction joints and show and call out any mechanical bar splices.





③ When mechanical bar splices are required due to staged construction, add the following after the indicated note:  
(Estimated \_\_\_ splices per slab)



Input the estimated number of required mechanical bar splices including those in the sleeper slab.

④ See Notes K1.11 and K1.12 in EPG 751.50 for wording of notes when semi-deep abutments are used.




⑤ If the end of a wing wall extends beyond the end of the bridge approach slab, it will be necessary to revise the length of the sleeper slab shown and to redirect the perforated drain pipe adjacent to the sleeper slab to go under the sleeper slab and then turn to daylight. This should be nonperforated drain pipe at this point.






ALTERNATE DETAILS FOR TYPE B BARRIER (SBC)



With the approval of the engineer, the contractor may crown the bottom of the approach slab to match the crown of the roadway surface.



DETAILS OF TIMBER HEADER  
Remove timber header when concrete pavement is placed.  
OPTIONAL CONCRETE SLAB



**Notes For Concrete Slab Only:**  
All concrete for the bridge approach slab shall be in accordance with Sec 503 ( $f'c = 4,000$  psi).  
The reinforcing steel in the bridge approach slab shall be epoxy coated Grade 60 with  $f_y = 60,000$  psi.  
Longitudinal construction joints in bridge approach slab shall be aligned with longitudinal construction joints in bridge slab.  
Minimum clearance to reinforcing steel shall be 1 1/2", unless otherwise shown.  
The reinforcing steel in the bridge approach slab shall be continuous. The transverse reinforcing steel may be made continuous by providing a minimum lap splice of 23 inches for #4 bars, or by mechanical bar splice.

③ Mechanical bar splices shall be in accordance with Sec 710.

All joint filler shall be in accordance with Sec 1057 for preformed fiber expansion joint filler except as noted.

Payment for furnishing all materials, labor and excavation necessary to construct the concrete bridge approach slab, including the timber header, underdrain, Type 5 aggregate base, joint filler, and all other appurtenances and incidental work as shown on this sheet, complete in place, will be considered completely covered by the contract unit price for Bridge Approach Slab (Minor) per square yard.




See Missouri Standard Plan 609.00 for details of Type A curb.

Drain pipe may be either 6" diameter corrugated metallic-coated pipe underdrain, 4" diameter corrugated polyvinyl chloride (PVC) drain pipe, or 4" diameter corrugated polyethylene (PE) drain pipe.


\* Seal joint between vertical face of approach slab and wing with sealant in accordance with Sec 717 for silicone joint sealant for saw cut and formed joints.

**General Notes:**  
Contractor shall have the option to construct either slab except as noted.  
④ The contractor shall pour and satisfactorily finish the bridge slab before placing the bridge approach slab.  
MoDOT Construction personnel will indicate the bridge approach slab used for this structure:  
☐ Concrete Bridge Approach Slab  
☐ Asphalt Bridge Approach Slab

**Notes For Asphalt Slab Only:**  
Payment for furnishing all materials, labor and excavation necessary to construct the asphalt bridge approach slab, including tack, curb, and Type 5 aggregate base within the pay limits shown, complete in place, will be considered completely covered by the contract unit price for Bridge Approach Slab (Minor) per square yard.  
Application of tack is required between lifts per Sec 403.



OPTIONAL ASPHALT SLAB (NOT ALLOWED WITH CONCRETE PAVEMENT)



See Missouri Standard Plan 609.00 for details of Type S curb.

**BRIDGE APPROACH SLAB (MINOR)**  
Integral end bents shown, non-integral end bent similar.

Standard Drawing Guidance (do not show on plans):

Asphalt approach slab should not be used for rehabilitation projects unless a vertical drain system is installed or is in place at end bent fill face.

Roadway drainage should be addressed by the core team & the consensus decision noted on the Bridge Memorandum. For roadway drainage options for Bridge Approach Slab (Minor), see EPG 503 Bridge Approach Slab.

See Project Manager or Liaison for preference on revising details as follows to specify staged construction.

① Show & call out any required staged construction joints.

② Show any required construction joints and show and call out any mechanical bar splices.

Staged Const. Joint

Mechanical Bar Splice (Typ.)

③ When mechanical bar splices are required due to staged construction, add the following after note:

(Estimated \_\_\_ splices per slab)

Input estimated number of required mechanical bar splices.

④ See Notes K1.11 & K1.12 in EPG 751.50 for wording of notes when semi-deep abutments are used.

⑤ If the end of a wing wall extends beyond the end of the bridge approach slab, it will be necessary to redirect the perforated drain pipe at the end of the bridge approach slab to turn to daylight. This should be nonperforated drain pipe at this point.

If either slab option is not required, either delete or cross out the option not used and delete or modify the first general note.

All wing lengths should have the curbs extended beyond their ends as shown to assist with directing bridge end drainage away from bridge ends. The standard drawing will work for most bridges with average wing lengths. For long wings, adjustments to the length of curbs may be necessary when the length of wings would prevent extending a full 5'-6" of curb length from the end of the wing to the end of the bridge approach slab. It may be necessary to extend the curb beyond the end of the bridge approach slab integral with concrete pavement or adjacent to asphalt pavement. Work any adjustments to the curb lengths with the details as shown on Standard Plan 609.40 & modify those details as necessary by either a note or detail.

SECTION A-A  
CONCRETE OPTION

This cross-section diagram shows the concrete bridge approach slab. From left to right, it includes: a 3/4" joint filler, a transition from roadway crown to bridge crown, #5 bars at 12" centers, #4 bars at 18" centers, #4 bars at 12" centers, #6 bars at 8" centers, a barrier, and the end of the wing. A note indicates that the transition from roadway crown to bridge crown is as necessary.

SECTION C-C  
ASPHALT OPTION

This cross-section diagram shows the asphalt bridge approach slab. It includes a transition from roadway crown to bridge crown, bituminous pavement (referencing roadway plans), a barrier, and the end of the wing. A note indicates that the transition from roadway crown to bridge crown is as necessary.

SECTION BETWEEN  
BARRIER AND CURB  
CONCRETE OPTION





This detail shows the connection between the barrier and the curb. It features a 1" chamfer on the barrier, a 4" Type A curb, a 1/4" joint filler, and a 3/4" joint filler. A note specifies that the transition chamfer to zero at Type A curb for gutter line to match. The gutter line of Type A curb aligns with the chamfer at the transition end of barrier. The width of the curb is 13" and the joint filler is 3/4".

4" TYPE S CURB  
ASPHALT OPTION

This detail shows the connection between the barrier and the curb for the asphalt option. It features a 13" curb and a 4" curb. A note indicates that the barrier and curb align at this point.

ALTERNATE DETAILS FOR TYPE B BARRIER (SBC)





General Notes (Posttensioned Slab):

Contractor shall verify all dimensions in field before ordering new material.

Concrete for the sleeper slab shall be in accordance with Sec 503 ( $f'c = 4,000$  psi).

Reinforcing steel in the sleeper slab shall be epoxy coated Grade 60 with  $f_y = 60,000$  psi.

Tie rod plates shall be ASTM A709 Grade 36.

Sleeves, nuts and 1 inch diameter tie rods shall be A307.

All tie rods, plates, sleeves, and nuts shall be galvanized in accordance with AASHTO M 232 (ASTM A153), Class C.

Minimum clearance to reinforcing steel shall be 1 1/2 inch,  
unless otherwise shown.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

All joint filler shall be in accordance with Sec 1057 for preformed fiber expansion joint filler, except as noted.

Drain pipe may be either 6 inch diameter corrugated metallic-coated pipe underdrain, 4 inch diameter corrugated polyvinyl chloride (PVC) drain pipe, or 4 inch diameter corrugated polyethylene (PE) drain pipe.

Resin Anchor System: An epoxy coated #6 Grade 60 reinforcing bar 17 inches long shall be substituted for the 3/4-inch diameter threaded rod.

When moving pretensioned beams, the roadway (top) face shall be kept face-up at all times. Beams shall be supported within 12 inches of the ends only.

Use non-shrink grout for filling the keyways.

For approach pavement details, see roadway plans. 8

Payment for furnishing all materials, labor and excavation necessary to construct the prestressed approach slab, including the sleeper slab, underdrain, asphaltic wearing surface, joint filler and all other appurtenances and incidental work as shown on this sheet, complete in place, will be considered completely covered by the contract unit price for Prestressed Bridge Approach Slab per square yard.

\* Contractor may adjust dimensions based on actual field measurements with approval of the engineer.

### Placement and Partial Width Posttensioning Instructions:

Top of aggregate base shall be made flush with top of bridge approach notch and top of sleeper slab, and uniformly graded at all points in between.

Place first exterior beam \*\*\*

Place adjacent interior beam \*\*\*

Place partial width tie rods through both beams and connect to hex sleeve.

Tighten all tie rods in the beam to about one-half of the specified tension before proceeding with the final tensioning. Begin with most centered tie rod in span.

Fill keyway with grout. See "Longitudinal Joint Between Pretensioned Beams". (Fill tie rod openings.)

Tie rod nuts shall be tightened to provide a final tension of one-half that specified for ASTM F3125 Grade A325 bolts in Section 712.7.3 of the Missouri Standard Specifications.

Place the next adjacent beam and partial width tie rod and connect to hex sleeve, following same sequence, until last exterior beam is placed and tightened.

Grout outside tie rod openings.

\*\*\* Apply Silicone Joint Sealant to the entire beam end at bent and trowel uniformly for complete seal just before placing the beam.


Access Hole Notes:

12 Voids Under Completed Prestressed Concrete Approach Slabs:  
Prior to acceptance of the work, all underseal access holes shall be opened by the the contractor to permit investigation by the engineer. Any voids or cavities found shall be filled by the contractor using an approved method. Care shall be taken during pumping operations to avoid raising the approach slab either individual beams or as a whole.

### Filling Holes:


At the completion of the investigation or underseal pumping, the holes shall be filled with sand to within one inch of the top and the remainder filled with joint sealing material.

No direct payment will be made for investigating void conditions under the completed slab or for filling any voids found for prestressed bridge approach slabs.



DATE PREPARED					
10/12/2023					
ROUTE		STATE			
		MO			
DISTRICT		SHEET NO.			
		8			
COUNTY					
JOB NO.					
CONTRACT ID.					
PROJECT NO.					
BRIDGE NO.					
DESCRIPTION					
DATE					

MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

 **MoDOT**

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

USE ONLY WITH  
APPROVAL OF  
ASSISTANT STATE  
BRIDGE ENGINEER

APP08\_precast1      Guidance


Standard Drawing Guidance (do not show on plans):

Turn off Bridge-Guidance level to hide all guidance.


Prestressed bridge approach slab is to be used for approach slab replacement only.

Roadway drainage should be addressed by the core team and the consensus noted on the Bridge Memorandum and the Standard Drawing. For roadway drainage options for Prestressed Bridge Approach Slab, see EPG 503 Bridge Approach Slab.


- ① Replace "Skew" with actual skew angle.
- ② Top of approach notch must be flat or uniformly sloped (no crown) and sleeper slab must be parallel in elevation to top of approach notch.
- ③ Identify asphalt overlay and thickness. Coordinate with district if better to make a roadway item and then note accordingly and revise pay item note.
- ④ Waterproof membrane is required when slab is overlaid with asphalt. Omit "Special Provisions" as needed.
- ⑤ Timber Header will not normally be needed, since prestressed beams will be used for replacements only. Use only if requested by District RE to protect ends of beams during construction.
- ⑥ Request field measurements between wings at end of slab and end of wings before dimensioning width of approach slab and determining beam widths to be used.
- ⑦ The 20'-0" slab dimension can be changed to 25'-0", the title can then be changed from (20 FEET) to (25 FEET).
- ⑧ Modify or remove based on actual conditions of the job.
- ⑨ Fill with asphalt or seal.
- ⑩ Number of tie rods: Ideally, install 3 tie rods at midpoint and quater points; one will have to go through wing wall; drill hole in wing, install, grout and seal. Realistically, install 2 tie rods as shown. (Only 2 tie rods were used successfully with favorable results in the correlated research.)
- ⑪ For "Placement and Full Width Posttensioning Instructions:", see Development Section. Partial width posttensioning is preferred.
- ⑪a Tie rods shall be placed along skew since shifting the beams longitudinally relative to each other during the tightening operation is prevented due to the anchorage of the beams to the end bent and the development of friction at the beam/aggregate interface.
- ⑫ Unlike conventional bridge approach slabs, prestressed concrete bridge approach slabs still require formed access holes for required investigation as specified prior to 2018 Standard Specifications.




USE ONLY WITH  
APPROVAL OF  
ASSISTANT STATE  
BRIDGE ENGINEER



### PLAN OF PRETENSIONED BEAM SHOWING REINFORCEMENT




SECTION THRU PRETENSIONED BEAM - 6 FEET




DETAIL B

(Both sides of interior beams and  
inside of exterior beams)




SECTION THRU PRETENSIONED BEAM - 8 FEET



SECTION B-B

Place 2"Ø conduit on top of bottom strands.



SECTION A-A

DETAIL A

Bill of Reinforcing Steel - Each Beam				
No.	Size & Mark	Actual Length	Shape	Bending Diagram
x' - x" Beam				
x 42	#6-H1 #5-H2	19'-8" x' - x"	20 20	
4	#5-U100	x' - x"	21	
4	#4-U101	x' - x"	21	
42	#5-U102	x' - x"	7	
x' - x" Beam				
x 42	#6-H1 #5-H2	19'-8" x' - x"	20 20	
4	#5-U100	x' - x"	21	
4	#4-U101	x' - x"	21	
42	#5-U102	x' - x"	7	

All dimensions are out to out.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

Actual lengths are measured along centerline of bar to the nearest inch.

Minimum clearance to reinforcing steel shall be 1 1/2" unless otherwise shown.

All reinforcement shall be epoxy coated Grade 60 with  $f_y = 60,000$ .

General Notes (Pretensioned Beams):

Concrete for pretensioned beams shall be Class A-1 with  $f'c = 6,000$  psi,  $f'ci = 3,500$  psi.

(+) indicates pretensioning strand.

Initial prestressing force = 31 kips/strand.

Pretensioning tendons shall be uncoated seven-wire low-relaxation strands for prestressed concrete in accordance with AASHTO M 203 Grade 270, with nominal diameter of strand = 1/2", nominal area = 0.153 sq. in. and minimum ultimate strength = 46.31 kips (270 ksi). Larger strands may be used with the same spacing and initial tension.

The method and sequence of releasing the strands shall be shown on the shop drawings.

Prestressing strands at ends of beams shall be trimmed to within 1/8" of concrete. Ends of beams shall be given 2 coats of an approved bituminous paint.

Lifting devices may be cast in beams. The device shall be shown on the shop drawings and approved by the engineer.

The top surface of all beams shall receive a smooth finish.

All holes in beams shall be cast. Drilling is not allowed.

Keyway surface shall be cleaned to remove form oil or other bond breaking material prior to shipment of the prestressed concrete approach slab. Cleaning shall be done by sandblasting the keyway areas between top of the beam and the bottom edge of the key.

Three 2 3/4-inch diameter (clear opening) underseal access holes shall be cast into each beam near the centerline of beam, clearing pretensioning strands and 2-inch diameter conduit by at least 1 1/2 inches. Shift reinforcement as needed to clear access holes by 1 1/2 inches minimum. Drilling is not allowed.

\* Contractor may adjust dimensions based on actual field measurements with approval of the engineer.

APP09\_precast2

Guidance

Standard Drawing Guidance (do not show on plans):

Turn off level "Bridge-Guidance" to hide.

- 1


Replace "Skew" with actual skew angle.
- 2

Use "smooth finish" if slab is to be overlaid with membrane and asphalt. When slab is to be overlaid with concrete wearing surface, use "surface finish in accordance with Sec 1029.6.16."
- 3

Standard beam widths are 6' and 8', and should be used wherever possible. The 8' beam is the fabricator's preferred width. However, beam widths may be reduced up to 6" to get them to fit with 1/2" clearance to wing wall. Use same strands and reinforcing steel and adjust spacing.
- 3a

A beam width that is less than the standard beam widths should be shown with adjusted spacing.
- 4

Calculate dimension using guidelines shown here (8'-0" Max.):



- 5




For squared structures, use Shape 10.
- 6

The 20'-0" slab dimension can be changed to 25'-0", the title can be changed from (20 FEET) to (25 FEET) and the "Bill of Reinforcing Steel" dimensions shall be changed accordingly.
- 7

Number of tie rods: Ideally, install 3 tie rods at midpoint and quarter points; one will have to go through wing wall; drill hole in wing, install, grout and seal. Realistically, install 2 tie rods as shown. (Only 2 tie rods were used successfully with favorable results in the correlated research.)
- 8

For 25-foot prestressed bridge approach slab, use four access holes at spacings of 3'-0" - 6'-0" - 6'-0" - 6'-0" - 4'-0".

USE ONLY WITH  
APPROVAL OF  
ASSISTANT STATE  
BRIDGE ENGINEER



Use a minimum lap of 3'-1" for #5 horizontal barrier bars.

The cross-sectional area above the slab is 2.27 square feet.

(2) To top of bar

(3) The R1 bar may be separated into two bars as shown, at the contractor's option, only when slip forming is not used. (All dimensions are out to out.)

(4) The R3 bar and #5 bottom transverse slab bar in cantilever (prestressed panels only) combination may be furnished as one bar as shown, at the contractor's option.

General Notes:

\* Slip-formed option only.

Conventional forming or slip forming may be used. Saw cut joints may be used with conventional forming.

Top of barrier shall be built parallel to grade with barrier joints (except at end bents) normal to grade.

All exposed edges of barrier shall have either a 1/2-inch radius or a 3/8-inch bevel, unless otherwise noted.

Payment for all concrete and reinforcement, complete in place, will be considered completely covered by the contract unit price for Type B Barrier per linear foot.

Concrete in the barrier shall be Class B-1.

Measurement of barrier is to the nearest linear foot for each structure, measured along the outside top of slab from end of wing to end of wing. ①


Concrete traffic barrier delineators shall be placed on top of the barrier as shown on Missouri Standard Plan 617.10 and in accordance with Sec 617. Delineators on bridges with two-lane, two-way traffic shall have retroreflective sheeting on both sides. Concrete traffic barrier delineators will be considered completely covered by the contract unit price for Type B Barrier.

Joint sealant and backer rods shall be in accordance with Sec 717 for silicone joint sealant for saw cut and formed joints.

For slip-formed option, both sides of barrier shall have a vertically broomed finish and the top shall have a transversely broomed finish.

② Plastic waterstop shall not be used with saw cut joints.

DATE PREPARED	
10/12/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	000
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	

[illegible]MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

BAC01\_elev      Guidance & Alternate Details

Standard Drawing Guidance (do not show on plans):

- In the available space, draw the elevation of the left barrier showing:
- Span ranges.
  - All horizontal #5-R bars in each span with all specified by bar marks.
  - First & last vertical #5-R bars dimensioned with total number in barrier.
  - All joints (as joint-filler joints) and centerlines with one centerline labeled as:

        @ 1/4" Joint (Barrier only) (Typ.)

- If slip forming is allowed then add the following two items:
- All #5-C bars in each span with all specified by bar marks (include asterisk)
  - All fiberglass bars with bars at one location labeled as:

        #4 Textured Fiberglass Bars (Typ.) \*

Adjust longitudinal dimensions note under elevation title as necessary.



If right barrier differs from left (typical with curved bridges), show both Elevation of Left Barrier and Elevation of Right Barrier. The longitudinal dimensions note can be relocated as the first note under the General Notes.

Dimensions are based on a 2.0%-sloped deck. Modify accordingly the outside dimensions in R-Bar Permissible Alternate Shape and Section A-A, and the 2.27 sq. ft. area in Section A-A for superelevated decks.

If conduit is required, indicate left or right or both barriers in a note.


- ① For barrier ending at end of slab:  
Exclude "(except at end bents)"  
Revise measurement to "end of slab to end of slab".
- ② Plastic waterstop detail and notes are required for all grade separations except over railroads and county roads. Remove if not required.
- ③ List C bars in the Bill of Reinforcing Steel and note that bars are for the slip-formed option only.  
  
Refer to EPG 751.12.1.2.1 for lengths of C bars.
- ④ Subtract 1/8" for a 3/16"-per-foot sloped deck.
- ⑤ Based on 8½" slab. Adjust for different slab thickness.
- ⑥ Remove for CIP slab.

EXAMPLE (SINGLE SPAN)



PART PLAN SHOWING  
JOINT LOCATION


Left Advance



PART PLAN SHOWING  
JOINT LOCATION


Right Advance

(Skewed bridges only)



SECTION THRU  
SAW CUT JOINT

(Use when conduit is required)




WATERSTOP DETAIL

Plastic waterstop shall be placed in all formed joints, except structures with superelevation, use on lower joints only.

Cost of plastic waterstop, complete in place, will be considered completely covered by the contract unit price for Type B Barrier.






(Use for grade separations)





PART ELEVATION OF BARRIER

ALTERNATE  
DETAIL FOR  
SINGLE SPAN








DETAILS OF GUARD RAIL ATTACHMENT




General Notes:

Reinforcing Steel:  
Concrete traffic barrier delineators shall be placed on top of the barrier as shown on Missouri Standard Plan 617.10 and in accordance with Sec 617. Delineators on bridges with two-lane, two-way traffic shall have retroreflective sheeting on both sides. Concrete traffic barrier delineators will be considered completely covered by the contract unit price for Type B Barrier.  
Minimum clearance to reinforcing steel shall be 1 1/2" except as shown for bars embedded into end bent.  
Use a minimum lap of 2'-7" between K9 and K10 or K13 bars.

TYPE B BARRIER AT END BENTS  
(Left barrier shown, right barrier similar)



Standard Drawing Guidance:  
(do not show on plans)  
① For skews greater than 3 degrees, use standard drawing BAC4a, which substitutes a K12 bar for the end K3 bar.  
② Dimensions are based on a 2.0% sloped deck. Subtract 1/8" for a 3/16" per foot sloped deck.





K1-K2 BAR PERMISSIBLE ALTERNATE SHAPE  
(K3 or K4 thru K8 bars not shown for clarity)  
The K1-K2 bar combination may be furnished as one bar as shown, at the contractor's option.  
All dimensions are out to out.


Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions. Sheet No. of

DATE PREPARED		10/12/2023	
ROUTE		STATE	
DISTRICT		MO	
		SHEET NO.	
		2	
COUNTY			
JOB NO.			
CONTRACT ID.			
PROJECT NO.			
BRIDGE NO.			
DESCRIPTION			
DATE			




DATE PREPARED 10/12/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 3
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	





Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.






Sheet No. of

DATE PREPARED 10/12/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 4
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
 105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	



DATE PREPARED 10/12/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 5
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
 105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	

ELEVATION OF BARRIER  
(Left barrier shown, right barrier similar)  
Longitudinal dimensions are horizontal.



- General Notes:**  
Conventional forming shall be used, and saw cut joints may be used.
- ① Top of barrier shall be built parallel to grade with barrier curb joints (except at end bents) normal to grade.
- All exposed edges of barrier shall have either a 1/2-inch radius or a 3/8-inch bevel, unless otherwise noted.
- Payment for all concrete and reinforcement, complete in place, will be considered completely covered by the contract unit price for Type B Barrier per liner foot.
- Concrete in the barrier shall be Class B-1.
- Measurement of barrier is to the nearest linear foot for each structure, measured along the outside top of slab from end of wing to end of wing.
- ② Concrete traffic barrier delineators shall be placed on top of the barrier as shown on Missouri Standard Plan 617.10 and in accordance with Sec 617. Delineators on bridges with two-lane, two-way traffic shall have retroreflective sheeting on both sides. Concrete traffic barrier delineators will be considered completely covered by the contract unit price for Type B Barrier.
- Joint sealant and backer rods shall be in accordance with Sec 717 for silicone joint sealant for saw cut and formed joints.
- ② Plastic waterstop shall not be used with saw cut joints.
- Coil inserts shall have a concrete ultimate pullout strength of not less than 36,000 pounds in 5,000 psi concrete and an ultimate tensile strength of not less than 36,000 pounds.
- Threaded coil rods shall have an ultimate capacity of 36,000 pounds. All coil inserts and threaded coil rods shall be galvanized in accordance with AASHTO M 232 (ASTM A153), Class C.
- Payment for furnishing and installing coil inserts and threaded coil rods will be considered completely covered by the contract unit price for Type B Barrier.


Detailed  
Checked

DATE PREPARED 10/12/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 6
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
MDOT 105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	









### K1-K2 BAR PERMISSIBLE ALTERNATE SHAPE

(K3 or K4 thru K8 bars not shown for clarity)

The K1-K2 bar combination may be furnished as one bar as shown, at the contractor's option.

All dimensions are out to out.


[illegible]

BAC11\_end\_si      Guidance & Alternate Details




Standard Drawing Guidance: (do not show on plans)

For skews greater than 3 degrees, use alternate details above, which substitutes a K3 bar for the end K2 bar. For skews greater than 41 degrees, two K3 bars are required.


① Dimensions are based on a 2.0% sloped deck. Subtract 1/8" for a 3/16" per foot sloped deck.





ALTERNATE DETAILS FOR SKEWED BRIDGES REQUIRING K3 BARS



\* Spaced with #5-K4 bars with bottom leg at same elevation as the bottom leg of K4 bars.  
\*\* Fit bar to follow transition face of barrier.  
\*\*\* To top of bar




Notes: Use a minimum lap of 3'-1" between K9 and R6 bars.  
Concrete traffic barrier delineators shall be placed on top of the barrier as shown on Missouri Standard Plan 617.10 and in accordance with Sec 617. Delineators on bridges with two-lane, two-way traffic shall have retroreflective sheeting on both sides. Concrete traffic barrier delineators will be considered completely covered by the contract unit price for Type B Barrier.



The top two bars shall be kept with position close to those shown in Sections A-A thru F-F  
The K1-K2 bar combination may be furnished as one bar as shown, at the contractor's option.  
All dimensions are out to out.

TYPE B BARRIER AT END BENTS  
(Left barrier shown, right barrier similar)

DATE PREPARED 10/12/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 8
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	

# BAC14\_end

## Guidance

Add Standard Note H9.1a, or H9.1b or H10.7.1 depending upon the use of guardrail or barrier system.

Use the following formulas for determining bar dimensions. These formulas work for all cross slopes.

K3 BARS

$$B = \text{SLAB (t)} + \text{W.S. (t)} + 10\frac{1}{2}"$$

$$E = \text{SLAB (t)} + \text{W.S. (t)} - \frac{3}{4}"$$

K4 BARS

$$C = \text{SLAB (t)} + \text{W.S. (t)} + 10"$$

K5, K6, K7 & K8 BARS

$$E = \text{SLAB (t)} + \text{W.S. (t)} + \frac{1}{2}"$$

R3 BARS

$$B = \text{SLAB (t)} + \text{W.S. (t)} + 9\frac{1}{4}"$$

R4 BARS

$$E = \text{SLAB (t)} + \text{W.S. (t)} - \frac{3}{4}"$$



Standard Drawing Guidance (do not show on plans):

- In the available space, draw the elevation of the left barrier showing:
- Span ranges.
  - All horizontal #5-R bars in each span with all specified by bar marks.
  - First & last vertical #5-R bars dimensioned with total number in barrier.
  - All joints (as joint-filler joints) and centerlines with one centerline labeled as:

⌀ 1/4" Joint (Barrier only) (Typ.)

If slip forming is allowed then add the following two items:

- All #5-C bars in each span with all specified by bar marks (include asterisk)
- All fiberglass bars with bars at one location labeled as:

#4 Textured Fiberglass Bars (Typ.) \*

Adjust longitudinal dimensions note under elevation title as necessary.

If right barrier differs from left (typical with curved bridges), show both Elevation of Left Barrier and Elevation of Right Barrier. The longitudinal dimensions note can be relocated as the first note under the General Notes.

Dimensions are based on a 2.0%-sloped deck. Modify accordingly the outside dimensions in R-Bar Permissible Alternate Shape and Section A-A, and the 3.52 sq. ft. area in Section A-A for superelevated decks.

If conduit is required, indicate left or right or both barriers in a note.

① For barrier ending at end of slab:

Exclude "(except at end bents)" in first note.

Revise measurement to "end of slab to end of slab" in second note.

② Plastic waterstop detail and notes are required for all grade separations except over railroads and county roads. Remove if not required.

③ List C bars in the Bill of Reinforcing Steel and note that bars are for the slip-formed option only.

Refer to EPG 751.12.1.2.1 for lengths of C bars.

④ Subtract 1/8" for a 3/16"-per-foot sloped deck.


⑤ Based on 8 1/2" slab. Adjust for different slab thickness.

⑥ Remove for CIP slab.


### ELEVATION OF BARRIER

(Left barrier shown, right barrier similar)


Longitudinal dimensions are horizontal.




SECTION THRU  
SAW CUT JOINT



PART ELEVATION  
AT FORMED JOINT




SECTION B-B



PART ELEVATION OF BARRIER

(1) Four feet long, centered on joint, slip-formed option only




SECTION A-A

Use a minimum lap of 3'-1" for #5 horizontal barrier bars.

The cross-sectional area above the slab is 3.52 square feet.


(2) To top of bar



R-BAR PERMISSIBLE ALTERNATE SHAPE

(3) The R1 bar may be separated into two bars as shown, at the contractor's option, only when slip forming is not used. (All dimensions are out to out.)

(4) The R2 bar and #5 bottom transverse slab bar in cantilever (prestressed panels only) combination may be furnished as one bar as shown, at the contractor's option.



⑥

### General Notes:

\* Slip-formed option only.

Conventional forming or slip forming may be used. Saw cut joints may be used with conventional forming.

① Top of barrier shall be built parallel to grade and barrier joints (except at end bents) normal to grade.

All exposed edges of barrier shall have either a 1/2-inch radius or a 3/8-inch bevel, unless otherwise noted.

Payment for all concrete and reinforcement, complete in place, will be considered completely covered by the contract unit price for Type D Barrier per linear foot.

Concrete in barrier shall be Class B-1.

Measurement of barrier is to the nearest linear foot for each structure, measured along the outside top of slab from end of wing to end of wing.

① Concrete traffic barrier delineators shall be placed on top of the barrier as shown on Missouri Standard Plan 617.10 and in accordance with Sec 617. Delineators on bridges with two-lane, two-way traffic shall have retroreflective sheeting on both sides. Concrete traffic barrier delineators will be considered completely covered by the contract unit price for Type D Barrier.

Joint sealant and backer rods shall be in accordance with Sec 717 for silicone joint sealant for saw cut and formed joints.

For slip-formed option, both sides of barrier shall have a vertically broomed finish and the top shall have a transversely broomed finish.

② Plastic waterstop shall not be used with saw cut joints.

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

### TYPE D BARRIER

Sheet No. of

DESCRIPTION

DATE


MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION








105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)




EXAMPLE - REDECK



EXAMPLE - NEW BRIDGE









BAR02\_D\_end\_i      Guidance & Alternate Details


Standard Drawing Guidance: (do not show on plans)


For skews greater than 3 degrees, use alternate details, which substitute a K3 bar for the end K2 bar. For skews greater than 41 degrees, two K3 bars are required.

① Dimensions are based on a 2.0% sloped deck. Subtract 1/8" for a 3/16" per foot sloped deck.




Alternate Details for Skewed Bridges Requiring K3 Bars



DATE PREPARED		10/13/2023	
ROUTE		STATE	
DISTRICT		MO	
		SHEET NO.	
		2	
COUNTY			
JOB NO.			
CONTRACT ID.			
PROJECT NO.			
BRIDGE NO.			
DESCRIPTION			
DATE			
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION			
<div><div>105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)</div></div>			

BAR03\_D\_end\_si

## Guidance & Alternate Details



## ALTERNATE DETAILS FOR SKEWED BRIDGES REQUIRING K3 BARS

Standard Drawing Guidance: (do not show on plans)

For skews greater than 3 degrees, use alternate details above, which substitutes a K3 bar for the end K2 bar. For skews greater than 41 degrees, two K3 bars are required.

① Dimensions are based on a 2.0% sloped deck. Subtract 1/8" for a 3/16" per foot sloped deck.




Note: This drawing is not to scale. Follow dimensions.

Sheet No.      of

[illegible]





Detailed  
Checked


Note: This drawing is not to scale. Follow dimensions. Sheet No. of

- (1) 5-#5-K1 @ 4" cts.
- (2) 2 spaces @ 4"
- (3) 5-#5-K4 & K5
- (4) 3-#5-K6 & K7
- (5) 2-#5-K13 @ 4 1/2" cts., each face
- (6) 3 spaces @ 3 1/8"
- (7) Spaced as shown, each face
- (8) 2-#5-K13 (Roadway face)
- (9) To top of bar

**General Notes:**  
Concrete traffic barrier delineators shall be placed on top of the barrier as shown on Missouri Standard Plan 617.10 and in accordance with Sec 617. Delineators on bridges with two-lane, two-way traffic shall have retroreflective sheeting on both sides. Concrete traffic barrier delineators will be considered completely covered by the contract unit price for Type D Barrier.

**Reinforcing Steel:**  
Minimum clearance to reinforcing steel shall be 1 1/2".  
Use a minimum lap of 3'-1" between horizontal K bars and R bars.



Standard Drawing Guidance: (Do not show on plans)  
① Show part of existing end bent.



**K10-K11 BAR PERMISSIBLE ALTERNATE SHAPE**  
(Other K bars not shown for clarity)  
The K10-K11 bar combination may be furnished as one bar as shown, at the contractor's option.  
All dimensions are out to out.



EXAMPLE ELEVATION




WATERSTOP DETAIL

Plastic waterstop shall be placed in all formed joints, except structures with superelevation, use on lower joints only.



Cost of plastic waterstop, complete in place, will be considered completely covered by the contract unit price for Type H Barrier.

(Use for grade separation)




SECTION THRU SAW CUT JOINT

(Use when conduit is required)



PART PLAN SHOWING JOINT LOCATION



(For skewed structures only)



PART ELEVATION OF BARRIER

(1) Four feet long, centered on joint, slip-formed option only

ALTERNATE DETAIL FOR SINGLE SPAN



**General Notes:**

Concrete traffic barrier delineators shall be placed on top of the barrier as shown on Missouri Standard Plan 617.10 and in accordance with Sec 617. Delineators on bridges with two-lane, two-way traffic shall have retroreflective sheeting on both sides. Concrete traffic barrier delineators will be considered completely covered by the contract unit price for Type H Barrier.

**Reinforcing Steel:**


Minimum clearance to reinforcing steel shall be 1 1/2" except as shown for bars embedded into end bent.

**TYPE H BARRIER AT END BENTS**

(Left barrier shown, right barrier similar)

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of



**PERMISSIBLE ALTERNATE SHAPES**

(Other K bars not shown for clarity)

The K4-K5 and K4-K6 bar combination may be furnished as one bar as shown, at the contractor's option.

All dimensions are out to out.

DATE PREPARED		10/13/2023
ROUTE	STATE	MO
DISTRICT	SHEET NO.	6
COUNTY		
JOB NO.		
CONTRACT ID.		
PROJECT NO.		
BRIDGE NO.		
DESCRIPTION		
DATE		

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

**MoDOT**


105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

Standard Drawing Guidance: (do not show on plans)

For skews greater than 3 degrees, use alternate details above, which substitutes a K3 bar for the end K2 bar. For skews greater than 41 degrees, two K3 bars are required.

① Dimensions are based on a 2.0% sloped deck. Subtract 1/8" for a 3/16" per foot sloped deck.

② Based on 8 1/2" slab. Adjust for different slab thickness.




PART ELEVATION

- (1) 5-#5-K1 @ 4" cts.


(2) 2 Spaces @ 4"
- (3) 5-#5-K4 and 5-#5-K5, spaced with K1

(4) 3 Spaces @ 3 13/16"
- (5) Spaced as shown, each face


(6) To top of bar




PART PLAN



SECTION F-F






SECTION G-G

[illegible]









Standard Drawing Guidance: (Do not show on plans)

① Show part of existing end bent.

**General Notes:**

Concrete traffic barrier delineators shall be placed on top of the barrier as shown on Missouri Standard Plan 617.10 and in accordance with Sec 617. Delineators on bridges with two-lane, two-way traffic shall have retroreflective sheeting on both sides. Concrete traffic barrier delineators will be considered completely covered by the contract unit price for Type H Barrier.


**Reinforcing Steel:**

Minimum clearance to reinforcing steel shall be 1 1/2".

Use a minimum lap of 3'-1" between K7 bars and R bars.

**TYPE H BARRIER AT END BENTS**

(Left barrier shown, right barrier similar)



**PERMISSIBLE ALTERNATE SHAPES**

(Other K bars not shown for clarity)

The K4-K5 and K4-K6 bar combination may be furnished as one bar as shown, at the contractor's option.

All dimensions are out to out.

Standard Drawing Guidance (do not show on plans):

- In the available space, draw the elevation of the left barrier showing:
- Span ranges.
  - All horizontal #5-R bars in each span with all specified by bar marks.
  - First & last vertical #5-R bars dimensioned with total number in barrier.
  - All joints (as joint-filler joints) and centerlines with one centerline labeled as:

② ¼" Joint (Barrier only) (Typ.)

- If slip forming is allowed then add the following two items:
- All #5-C bars in each span with all specified by bar marks (include asterisk)
  - All fiberglass bars with bars at one location labeled as:

#4 Textured Fiberglass Bars (Typ.) \*







Adjust longitudinal dimensions note under elevation title as necessary.

List C bars in the Bill of Reinforcing Steel and note that bars are for the slip-formed option only.

Length of C1 bars is 12'-0".

Do not include #5 bars for resin anchors in the bar bill.

ELEVATION OF BARRIER  
Longitudinal dimensions are horizontal.



General Notes:

\* Slip-formed option only.

Conventional forming or slip forming may be used. Saw cut joints may be used with conventional forming.

Top of barrier shall be built parallel to grade with barrier joints normal to grade.

All exposed edges of barrier shall have either a 1/2-inch radius or a 3/8-inch bevel, unless otherwise noted.

Payment for all concrete and reinforcement, complete in place, will be completely covered by the contract unit price for Type C Barrier per linear foot.

Concrete in the barrier shall be Class B-1.

Measurement of barrier is to the nearest linear foot, measured along the top of slab at centerline median from end of bridge approach slab to end of bridge approach slab.

Concrete traffic barrier delineators shall be placed on top of the barrier as shown on Missouri Standard Plan 617.10 and in accordance with Sec 617. Delineators shall have retroreflective sheeting on both sides. Concrete traffic barrier delineators will be considered completely covered by the contract unit price for Type C Barrier.

Joint sealant and backer rods shall be in accordance with Sec 717 for silicone joint sealant for saw cut and formed joints.

For slip-formed option, both sides of barrier shall have a vertically broomed finish and the top shall have a transversely broomed finish.

The contractor shall use one of the qualified resin anchor systems in accordance with 1039.

Cost of furnishing and installing the resin anchor system, complete in place, will be considered completely covered by the contract unit price for Type C Barrier.

The minimum embedment depth in concrete with f'c = 4,000 psi for the resin anchor system shall be that required to meet the minimum ultimate pullout strength in accordance with Sec 1039 but shall not be less than 5 inches.

An epoxy coated #5 Grade 60 reinforcing bar shall be substituted for the 5/8-inch diameter threaded rod.


Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.


TYPE C BARRIER

Sheet No. of



BAR11\_C\_elev      Alternate Details




EXAMPLE ELEVATION



(Use when conduit is required)





EXAMPLE  
ELEVATION

BAR11\_C\_elev Effective: Apr. 2020 Supersedes: Aug. 2018 (MBAC03)

Standard Drawing Guidance (do not show on plans):

In the available space, draw the elevation of the left barrier showing:

- Span ranges.
- All horizontal #5-R bars in each span with all specified by bar marks.
- First & last vertical #5-R bars dimensioned with total number in barrier.
- All joints (as joint-filler joints) and centerlines with one centerline labeled as:

    ℄ ¼" Joint (Barrier only) (Typ.)

If slip forming is allowed then add the following two items:

- All #5-C bars in each span with all specified by bar marks (include asterisk)
- All fiberglass bars with bars at one location labeled as:

    #4 Textured Fiberglass Bars (Typ.) \*

Adjust longitudinal dimensions note under elevation title as necessary.







List C bars in the Bill of Reinforcing Steel and note that bars are for the slip-formed option only.

Length of C1 bars is 12'-0".

Do not include #5 bars for resin anchors in the bar bill.

ELEVATION OF BARRIER




Longitudinal dimensions are horizontal.



TYPE C BARRIER


General Notes:

- \* Slip-formed option only.
- Conventional forming or slip forming may be used. Saw cut joints may be used with conventional forming.
- Top of barrier shall be built parallel to grade with barrier joints normal to grade.
- All exposed edges of barrier shall have either a 1/2-inch radius or a 3/8-inch bevel, unless otherwise noted.
- Payment for all concrete and reinforcement, complete in place, will be completely covered by the contract unit price for Type C Barrier per linear foot.
- Concrete in the barrier shall be Class B-1.
- Measurement of barrier is to the nearest linear foot, measured along the top of slab at centerline median from end of bridge approach slab to end of bridge approach slab.
- Concrete traffic barrier delineators shall be placed on top of the barrier as shown on Missouri Standard Plan 617.10 and in accordance with Sec 617. Delineators shall have retroreflective sheeting on both sides. Concrete traffic barrier delineators will be considered completely covered by the contract unit price for Type C Barrier.
- Joint sealant and backer rods shall be in accordance with Sec 717 for silicone joint sealant for saw cut and formed joints.
- For slip-formed option, both sides of barrier shall have a vertically broomed finish and the top shall have a transversely broomed finish.
- The contractor shall use one of the qualified resin anchor systems in accordance with 1039.
- Cost of furnishing and installing the resin anchor system, complete in place, will be considered completely covered by the contract unit price for Type C Barrier.
- The minimum embedment depth in concrete with f'c = 4,000 psi for the resin anchor system shall be that required to meet the minimum ultimate pullout strength in accordance with Sec 1039 but shall not be less than 5".
- An epoxy coated #5 Grade 60 reinforcing bar shall be substituted for the 5/8"Ø threaded rod.






## BILL OF REINFORCING STEEL

[illegible]

STIRRUP HOOK DIMENSIONS				
GRADES 40 - 50 - 60 KSI				
BAR SIZE	D (IN.)	90° HOOK	135° HOOK	APPROX. H
		HOOK A OR G	HOOK A OR G	
#4	2"	4 1/2"	4 1/2"	3"
#5	2 1/2"	6"	5 1/2"	3 3/4"
#6	4 1/2"	12"	8"	4 1/2"



NOTE: UNLESS OTHERWISE NOTED, DIAMETER "D" IS THE SAME FOR ALL BENDS AND HOOKS ON A BAR.



END HOOK DIMENSIONS					
BAR SIZE	D. (IN.)	ALL GRADES			
		180° HOOKS		90° HOOKS	
		A	J	A	J
#3	2 1/4"	5"	3"	6"	
#4	3"	6"	4"	8"	
#5	3 3/4"	7"	5"	10"	
#6	4 1/2"	8"	6"	12"	
#7	5 1/4"	2'-3"	7"	14"	
#8	6"	11"	8"	16"	
#9	9 1/2"	15"	11 3/4"	19"	
#10	10 3/4"	17"	13 1/4"	22"	
#11	12"	19"	14 3/4"	2'-0"	
#14	18 1/4"	2'-3"	21 3/4"	2'-7"	

**NOTE:**  
ALL STANDARD HOOKS AND BENDS OTHER THAN 180 DEGREE ARE TO BE  
BENT WITH SAME PROCEDURE AS FOR 90 DEGREE STANDARD HOOKS.  
HOOKS AND BENDS SHALL BE IN ACCORDANCE WITH THE PROCEDURES AS  
SHOWN ON THIS SHEET.  
E = EPOXY COATED REINFORCEMENT.  
S = STIRRUP.  
X = BAR IS INCLUDED IN SUBSTRUCTURE QUANTITIES.  
V = BAR DIMENSIONS VARY IN EQUAL INCREMENTS BETWEEN DIMENSIONS  
SHOWN ON THIS LINE AND THE FOLLOWING LINE.  
NO. EA. = NUMBER OF BARS OF EACH LENGTH.  
NOMINAL LENGTHS ARE BASED ON OUT TO OUT DIMENSIONS SHOWN IN  
BENDING DIAGRAMS AND ARE LISTED FOR FABRICATORS USE. (NEAREST INCH)  
ACTUAL LENGTHS ARE MEASURED ALONG CENTERLINE FOR BAR TO THE NEAREST INCH.  
PAYWEIGHTS ARE BASED ON ACTUAL LENGTHS.  
FOUR ANGLE OR CHANNEL SPACERS ARE REQUIRED FOR EACH COLUMN  
SPIRAL. SPACERS ARE TO BE PLACED ON INSIDE OF SPIRALS. LENGTH  
AND WEIGHT OF COLUMN SPIRALS DO NOT INCLUDE SPLICES OR SPACERS.  
REINFORCING STEEL (GRADE 60) FY = 60,000 PSI.

## BILL OF REINFORCING STEEL

[illegible]

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

"THIS MEDIA SHOULD  
NOT BE CONSIDERED  
A CERTIFIED  
DOCUMENT."

DATE PREPARED	
4/30/2020	
ROUTE	STATE
*	MO
DISTRICT	SHEET NO.
BR	*
COUNTY	
JOB NO.	
*	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	


DESCRIPTION

DATE \_\_\_\_\_

MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

Standard Drawing  
Guidance (do not show  
on plans):


Add these non-standard shapes to drawing when required. Follow Barbill instructions for obtaining correct weight & length.



Use Shape 12 to model half of desired shape while doubling number required.

Modify Barbill Output:

- Half No. Req'd
- Revise shape to 50
- Double dimension C
- Revise nominal length as  $2B+C+2A$
- Double actual length



Use Shape 27.

Modify Barbill Output:  
- Revise shape to 50

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.






[illegible][illegible]


SPlice LENGTH		MAX BAR LENGTH	
BAR SIZE	NON-EPOXY	BAR SIZE	NON-EPOXY
#4	21 IN.	#4	60 FT.
#5	26 IN.	#5	60 FT.
#6	31 IN.	#6	60 FT.
#7	39 IN.	#7	60 FT.
#8	51 IN.	#8	60 FT.
#9	65 IN.	#9	60 FT.
#10	82 IN.	#10	60 FT.
#11	101 IN.	#11	60 FT.

NOTE:  
THE BAR LIST IS BASED ON THE MISSOURI  
STANDARD PLANS.  
THIS BAR LIST IS FOR QUANTITY  
ESTIMATION PURPOSE ONLY AND SHALL BE  
VERIFIED OR MODIFIED BY THE CONTRACTOR.



BAR SIZE	D (IN.)	90° HOOK	135° HOOK	
		HOOK A OR G	HOOK A OR G	APPROX. H
#4	2"	4 1/2"	4 1/2"	3"
#5	2 1/2"	6"	5 1/2"	3 3/4"
#6	4 1/2"	12"	8"	4 1/2"

NOTE: UNLESS OTHERWISE NOTED, DIAMETER "D" IS THE SAME FOR ALL BENDS AND HOOKS ON A BAR.










END HOOK DIMENSIONS				
BAR SIZE	D (IN.)	GRADE 60		
		180° HOOKS		90° HOOKS
		A OR G	J	A OR G
#4	3"	6"	4"	8"
#5	3 3/4"	7"	5"	10"
#6	4 1/2"	8"	6"	12"
#7	5 1/4"	10"	7"	14"
#8	6"	11"	8"	16"
#9	9 1/2"	15"	11 3/4"	19"
#10	10 3/4"	17"	13 1/4"	22"
#11	12"	19"	14 3/4"	24"

NOTE:  
 ALL STANDARD HOOKS AND BENDS OTHER THAN 180 DEGREE ARE TO BE BENT WITH SAME  
 PROCEDURE AS FOR 90 DEGREE STANDARD HOOKS.  
 HOOKS AND BENDS SHALL BE IN ACCORDANCE WITH THE PROCEDURES AS SHOWN ON THIS SHEET.  
 FB = BARS MAY BE BENT IN FIELD TO FIT.  
 E = EPOXY COATED REINFORCEMENT.  
 S = SPORE.  
 V = BAR DIMENSIONS VARY IN EQUAL INCREMENTS BETWEEN DIMENSIONS SHOWN ON THIS LINE  
 AND THE FOLLOWING LINE. A BLANK SPACE ON THE SECOND LINE REPRESENTS THE SAME BAR DIMENSION AS THAT  
 ON THE FIRST LINE. CONTRAST THE DIMENSIONAL CAPABILITY TO ADD A SPlice LENGTH TO A BAR  
 LENGTH WHICH EXCEEDS ITS MAXIMUM ALLOWABLE LENGTH.  
 DIMENSIONS ARE GIVEN IN INCHES. NUMBER OF BARS PER LENGTH.  
 NOMINAL LENGTHS ARE BASED ON OUT TO OUT DIMENSIONS SHOWN IN BENDING DIAGRAMS AND ARE LISTED  
 IN INCHES. ACTUAL LENGTHS ARE MEASURED ALONG CENTERLINE BAR TO THE NEAREST INCH.  
 PAYMENTS ARE BASED ON ACTUAL LENGTHS.  
 REINFORCING STEEL (GRADE 60) FY = 60,000 PSI.

Detailed  
Checked

Sheet No.      of

## U.I.P. &amp; REHABILITATE EXISTING (x', x') X SPANS



No Wearing Surface

Guidance: (Do not show on plans.)

Substitute alternate Plan for skewed structures.

Modify details as needed to suit your structure.

Use with BEM01-2 (Bill of Reinforcing Steel).

Estimated Quantities	
Item	Total
Barrier End Modification each	4

General Notes:

Design Specifications:  
2002 AASHTO LFD (17th Ed.) Standard Specifications

Design Unit Stresses:  
Class B-1 Concrete  $f'_c = 4,000$  psi  
Reinforcing Steel (Grade 60)  $f_y = 60,000$  psi

**Reinforcing Steel:**  
Minimum clearance to reinforcing steel shall be 1 1/2",  
unless otherwise shown.

Miscellaneous:  
One lane of traffic shall remain open during construction. See roadway plans for traffic control.

All exposed edges of barrier shall have either a 1/2-inch radius or a 3/8-inch bevel, unless otherwise shown.

Outline of existing work is indicated by light dashed lines. Heavy lines indicate new work.

Contractor shall verify all dimensions in field before ordering new material.

All reinforcement in barrier end modification shall be epoxy coated.

Bars bonded in existing concrete not removed shall be cleanly stripped and embedded into new concrete where possible. If length is available, existing bars shall extend into new concrete at least 40 diameters for plain bars and 30 diameters for deformed bars, unless otherwise noted.

The area exposed by the removal of concrete and not covered with new concrete shall be coated with a qualified special mortar in accordance with Sec 704.

Cost of removing existing barrier concrete, and cost of furnishing and installing new concrete, new reinforcing steel, and any other work incidental to the barrier end modification, complete in place, will be considered completely covered by the contract unit price for Barrier End Modification.

REPAIRS TO BRIDGE:  
ROUTE OVER


ROUTE \_ FROM ROUTE \_ TO ROUTE \_  
ABOUT \_ MILES \_ OF ROUTE \_  
BEGINNING STATION x+x.x± (MATCH EXISTING)

DATE PREPARED	
10/13/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	000
COUNTY	

COUNTY
JOB NO.
CONTRACT ID.

PROJECT NO.
BRIDGE NO.

[illegible]MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION




Skewed Plan









PLAN (3)

Skewed Plan



Standard Drawing Guidance:  
(Do not show on plans)

See Technician Info/TipsAndHelp/  
AttachBoringPDFsToBridgePlans  
on Development Section Sharepoint page for  
instructions for attaching PDFs as rasters.

For one 11x17 Geotechnical Data sheet, snap  
to top left corner of left guidance box and  
snap anywhere for other corner, filling  
as much of the available space as possible.  
Delete boxes or turn off Constructions level.

"THIS MEDIA SHOULD  
NOT BE CONSIDERED  
A CERTIFIED  
DOCUMENT."

DATE PREPARED  
4/1/2021

ROUTE  
\*

DISTRICT  
BR

STATE  
MO

SHEET NO.  
\*

COUNTY  
\*

JOB NO.  
\*


CONTRACT ID.

PROJECT NO.

BRIDGE NO.  
BOR01

DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION




105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

2( 'x ') CONCRETE BOX CULVERT


SEC/SUR \* TWP \* RGE \*



Construction joint key not shown for clarity, see standard plans for details.

If any part of the barrel is exposed, the roadway fill shall be warped to provide 12 inches minimum cover. (Roadway Item)

If unsuitable material is encountered, excavation of unsuitable material and furnishing and placing of granular backfill shall be in accordance with Sec 206.



PLAN OF LAYOUT DIMENSIONS

Var.

Equation

Dim.

Var.

Equation

Dim.

Var.

Equation

Dim.

S

- - -

x

TI

- - -

x

F

2S + 2TX + TI

x

HT

- - -

x

A

- - -

x

G

2V

x

TS

- - -

x

B

- - -

x

V

HT + TS - 12"

x

BS

- - -

x

C

- - -

x

W

2A + B + C + 2E

x

TX

- - -

x

E

G + 23"

x

TW

Max{3'-4" or (BS + 12")}

x

Hydrologic Data

Drainage Area = \_\_\_ mi<sup>2</sup>

Design Flood Frequency = \_\_\_ years

Design Flood Discharge = \_\_\_ cfs

Design Flood (D.F.) Elevation = \_\_\_\_\_

Base Flood (100-year)

Base Flood Elevation = \_\_\_\_\_

Base Flood Discharge = \_\_\_ cfs

Estimated Backwater = \_\_ ft

Outlet Velocity = \_\_ ft/s

Roadway Overtopping

Overtopping Flood Discharge = \_\_\_ cfs

Overtopping Flood Frequency = \_\_\_ years

\_\_\_\_\_ Flood Elevation = \_\_\_\_\_

Elevations

Upstream (Elev. 1) =

Downstream (Elev. 2) =

Pr. Gr. at Tie Sta. =

Dimensions are based on end units. Fill heights are measured from the top of top slab to the top of earth fill or roadway.

Estimated Quantities

Class 4 Excavation

cu. yard

x

Final

Removal of Bridges

lump sum

1

Class B-1 Concrete (Culverts-Bridge)

cu. yard

x

Reinforcing Steel (Culverts-Bridge)

pound

x

Fill Heights

C Rdwy at C Culvert = ft

Design (All units) = ft

General Notes:

Design Specifications:  
2010 AASHTO LRFD Bridge Design Specifications and 2010 Interim Revisions

Design Loading:  
Vehicular = HL-93 minus lane load, Earth = 120 lb/cf  
Equivalent Fluid Pressure = 30 lb/cf (min.), 60 lb/cf (max.)

Design Unit Stresses:  
Class B-1 Concrete (Box Culvert) f'c = 4,000 psi  
Reinforcing Steel (Grade 60) fy = 60,000 psi

Standard Plans:  
703.37, 703.40, 703.46, 703.47

Miscellaneous:  
MoDOT Construction personnel will indicate the type of box culvert constructed:  
☐ Precast Concrete Box used  
☐ Cast-in-Place Concrete Box used

When alternate precast concrete box sections are used, the minimum distance from inside face of headwalls to precast sections measured along the shortest wall shall be 3 feet. Reinforcement and dimensions for wings and headwalls shall be in accordance with Missouri Standard Plans.

Channel bottom shall be graded within the right of way for transition of channel bed to culvert openings. Channel banks shall be tapered to match culvert openings. (Roadway Item)

Traffic Handling:  
Structure to be closed during construction. Traffic to be maintained on during construction. See roadway plans for traffic control.

B.M.

CULVERT-BRIDGE: ROUTE \* OVER \*  
ROUTE \* FROM \* TO \*  
ABOUT \* MILES \* OF \*  
TIE STA. \_\_\_\_\_

DATE PREPARED 10/13/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 1
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
MoDOT 105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	

Designed  
Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. 1 of



Pipes With Same Diameter

XX" Pipe Inlet Data		
Station	Offset	F.L. Elev.
xx+xx.xx	xx.xx' XX	xxx.xx
xx+xx.xx	xx.xx' XX	xxx.xx
xx+xx.xx	xx.xx' XX	xxx.xx

Inlets Sized for Elevation A-A  
(Pipe Diameter/Culvert HT)

0.1	0.2	0.3	0.4	0.5
0.6	0.7	0.8	0.9	

Ex: Use 0.5 detail for 36" pipe into a 6' tall culvert.

Pipes With Different Diameters

Pipe Inlet Data			
Station	Offset	Dia.	F.L. Elev.
xx+xx.xx	xx.xx' XX	xx"	xxx.xx
xx+xx.xx	xx.xx' XX	xx"	xxx.xx
xx+xx.xx	xx.xx' XX	xx"	xxx.xx

Supplemental Pipe Inlet Details ④

Supplemental Reinforcement Table (Nonstandard culverts with only one design fill height) ⑤

Top Slab Reinforcement										Bottom Slab Reinforcement						Wall Reinforcement					
A1 Bars		J3 Bars		H1 Bars		H2 Bars		A2 Bars		J4 Bars		H3 Bars		B1 Bars	B2 Bars						
Sz.	Spa.	Sz.	Spa.	C1	K2	Sz.	Spa.	C5	Sz.	Spa.	C6	Sz.	Spa.	C4	K3	Sz.	Spa.	C7	Sz.	Spa.	G1
x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x

Substitute table for tables shown on Standard Plan 703.47

- Standard Drawing Guidance  
(Do not show on plans. Turn off the Bridge Construction Level to hide)
- Some details have been grouped together to allow easy substitution with alternate details. To edit grouped details, select them and press <Ctrl> U.
- ① Ahead station is shown for streams flowing left to right. Arrow must be flipped for streams that flow right to left.

② Modify Estimated Quantities as required. Don't leave blank rows but leave space between Estimated Quantities and General Notes for at least one pay item to be added during construction. See Alternate Details for culvert extensions, or if five items are required.

③ Add any required transverse joints proportionally spaced along the barrel. Label units and add actual lengths of units along the barrel.

④ Insert STD 703.60 when pipe inlets are required. Add pipe inlets to Plan of Layout Dimensions at appropriate locations and to Elevation A-A if visible from elevation. Add inlet data using notes where space allows, or use tables.

⑤ For nonstandard culverts with only one design fill height, add supplemental reinforcement table.


⑥ No need to revise General Elevation A-A for dual roadways. In Fill Heights table add a lane designation after  $\varnothing$  Rdwy and insert another row for the other lane.

- \*\*\* VARIABLE DESIGN FILL HEIGHTS \*\*\*
- a) Select and delete the details grouped with the Fill Heights table. Select and move the alternate grouped details to drawing.

b) Place "See Member Thickness table" in the Equation column and place "Varies" in the Dim. column. If Dimension F varies, place "Varies" in the Dim. column.

c) Remove blank rows. End units may have different design fill heights but both units need to have the same member thicknesses.

d) This portion of table required when design fill height exceeds limits of the standard plans or when culvert cell height or span is not standard. If only a portion of the units are nonstandard, fill out entire table using the values from the standard table where applicable. Omit if not required.



If any part of the barrel is exposed, the roadway fill shall be warped to provide 12 inches minimum cover. (Roadway Item)

Construction joint key not shown for clarity, see standard plans for details.

If unsuitable material is encountered, excavation of unsuitable material and furnishing and placing of granular backfill shall be in accordance with Sec 206.

BXC01\_dbl\_sq\_str      Guidance & Alternate Details (2 of 2)

Corresponds to the border of the standard drawing for ease in moving alternate details (Snap to corner)

Alternate Details for Multiple Design Fill Heights (a)



Fill Heights		
℄ Rdwy at ℄ Culvert =		ft
Design (Units 1 & ) =		ft
Design (Units & ) =		ft
Design (Units & ) =		ft

Dimensions are based on end units, except AA is based on Unit . Fill heights are measured from the top of top slab to the top of earth fill or roadway.

Estimated Quantities			Final
Class 4 Excavation	cu. yard	x	
Temporary Shoring	lump sum	1	
Partial Removal of Culvert-Bridge Concrete	lump sum	1	
Class B-1 Concrete (Culverts-Bridge)	cu. yard	x	
Reinforcing Steel (Culverts-Bridge)	pound	x	

2

Alternate Estimated Quantities for Culvert Extensions or when Five Items are Required



Remove if not applicable.

Unit No.	Unit Length	Member Thickness					Top Slab Reinforcement										Bottom Slab Reinforcement							Wall Reinforcement					
							A1 Bars		J3 Bars		H1 Bars		H2 Bars		A2 Bars		J4 Bars		H3 Bars		B1 Bars		B2 Bars						
		TS	BS	TX	T1	F	Sz.	Spa.	Sz.	Spa.	C1	K2	Sz.	Spa.	C5	Sz.	Spa.	C6	Sz.	Spa.	Sz.	Spa.	C4	K3	Sz.	Spa.	C7	Sz.	Spa.
x	x	x	x	x	x	' - "	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x
x	x	x	x	x	x	' - "	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x
x	x	x	x	x	x	' - "	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x

Substitute table for tables shown on Standard Plan 703.47



Pipes With Same Diameter

XX" Pipe Inlet Data		
Station	Offset	F.L. Elev.
xx+xx.xx	xx.xx' XX	xxx.xx
xx+xx.xx	xx.xx' XX	xxx.xx
xx+xx.xx	xx.xx' XX	xxx.xx

Inlets Sized for Elevation A-A  
(Pipe Diameter/Culvert HT)

0.1	0.2	0.3	0.4	0.5
0.6	0.7	0.8	0.9	

Ex: Use 0.5 detail for 36" pipe into a 6' tall culvert.

Pipes With Different Diameters

Pipe Inlet Data			
Station	Offset	Dia.	F.L. Elev.
xx+xx.xx	xx.xx' XX	xx"	xxx.xx
xx+xx.xx	xx.xx' XX	xx"	xxx.xx
xx+xx.xx	xx.xx' XX	xx"	xxx.xx

Supplemental Reinforcement Table (Nonstandard culverts with only one design fill height) ⑤

Top Slab Reinforcement										Bottom Slab Reinforcement						Wall Reinforcement							
A1 Bars		J3 Bars				H1 Bars		H2 Bars		A2 Bars		J4 Bars		H3 Bars		B1 Bars	B2 Bars						
Sz.	Spa.	Sz.	Spa.	C1	K2	Sz.	Spa.	C5	Sz.	Spa.	C6	Sz.	Spa.	C4	K3	Sz.	Spa.	C7	Sz.	Spa.	Sz.	Spa.	G1
x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x

Substitute table for tables shown on Standard Plan 703.47

Standard Drawing Guidance  
(Do not show on plans. Turn off the Bridge Construction level to hide)

Some details have been grouped together to allow easy substitution with alternate details. To edit grouped details, select them and press <Ctrl> U.

- ① Ahead station is shown for streams flowing left to right. Arrow must be flipped for streams that flow right to left.
- ② Modify Estimated Quantities as required. Don't leave blank rows but leave space between Estimated Quantities and General Notes for at least one pay item to be added during construction. See Alternate Details for culvert extensions, or if five items are required.
- ③ Add any required transverse joints proportionally spaced along the barrel. Label units and add actual lengths of the units along the barrel.
- ④ Insert STD 703.60 when pipe inlets are required. Add pipe inlets to Plan of Layout Dimensions at appropriate locations and to Elevation A-A if visible from elevation. Add inlet data using notes where space allows, or use tables.
- ⑤ For nonstandard culverts with only one design fill height, add supplemental reinforcement table.
- ⑥ No need to revise General Elevation A-A for dual roadways. In Fill Heights table add a lane designation after Ⓞ Rdwy and insert another row for the other lane.

\*\*\* VARIABLE DESIGN FILL HEIGHTS \*\*\*

- Ⓐ Select and delete the details grouped with the Fill Heights table. Select and move the alternate grouped details to drawing.
- Ⓑ Place "See Member Thickness table" in the Equation column and place "Varies" in the Dim. column. If Dimension F varies, place "Varies" in the Dim. column.
- Ⓒ Remove blank rows. End units may have different design fill heights but both units need to have the same member thicknesses.
- Ⓓ This portion of table required when design fill height exceeds limits of the standard plans or when culvert cell height or span is not standard. If only a portion of the units are nonstandard, fill out entire table using the values from the standard table where applicable. Omit if not required.

Alternate Plan of Transverse Joints

1 2 3 4 Unit No.  
Ⓞ Trans. Jt. (Typ.)  
Ⓞ Culvert

1 2 3 4 5 6 Unit No.  
Ⓞ Trans. Jt. (Typ.)  
Ⓞ Culvert

1 2 3 4 5 Unit No.  
Ⓞ Trans. Jt. (Typ.)  
Ⓞ Culvert

1 2 3 4 5 6 7 Unit No.  
Ⓞ Trans. Jt. (Typ.)  
Ⓞ Culvert

1 2 3 4 5 6 7 8 Unit No.  
Ⓞ Trans. Jt. (Typ.)  
Ⓞ Culvert

1 2 3 4 5 6 7 8 9 Unit No.  
Ⓞ Trans. Jt. (Typ.)  
Ⓞ Culvert


1 2 3 4 5 6 7 8 9 10 Unit No.  
Ⓞ Trans. Jt. (Typ.)  
Ⓞ Culvert

If unsuitable material is encountered, excavation of unsuitable material and furnishing and placing of granular backfill shall be in accordance with Sec 206.


## Guidance and Alternate Details (2 of 2)

Corresponds to the border of the standard drawing for ease in moving alternate details (Snap to corner)

### —Alternate Details for Multiple Design Fill Heights (a)



## PLAN OF LAYOUT DIMENSIONS



### PLAN OF TRANSVERSE JOINTS AND STAGE CONSTRUCTION

Remove if not applicable.

Fill Heights		
℄ Rdwy at ℄ Culvert =		ft
Design (Units 1 & ) =		ft
Design (Units & ) =		ft
Design (Units & ) =		ft

Dimensions are based on end units, except AA is based on Unit . Fill heights are measured from the top of top slab to the top of earth fill or roadway.

Estimated Quantities			Final
Class 4 Excavation	cu. yard	x	
Temporary Shoring	lump sum	1	
Partial Removal of Culvert-Bridge Concrete	lump sum	1	
Class B-1 Concrete (Culverts-Bridge)	cu. yard	x	
Reinforcing Steel (Culverts-Bridge)	pound	x	


### — Alternate Estimated Quantities for Culvert Extensions or when Five Items are Required

[illegible]

Substitute table for tables shown on Standard Plan 703.47

2( 'x ') CONCRETE BOX CULVERT



SEC/SUR \* TWP \* RGE \*



Construction joint key not shown for clarity, see standard plans for details.

If any part of the barrel is exposed, the roadway fill shall be warped to provide 12 inches minimum cover. (Roadway Item)

If unsuitable material is encountered, excavation of unsuitable material and furnishing and placing of granular backfill shall be in accordance with Sec 206.



PLAN OF LAYOUT DIMENSIONS

LOCATION SKETCH

Layout Dimensions								
Var.	Equation	Dim.	Var.	Equation	Dim.	Var.	Equation	Dim.
S	- - -	x	F	2S + 2TX + TI	x	W	2A + B + C + 2E	x
HT	- - -	x	G	2V	x	X	3" + TX(tan Z)	x
TS	- - -	x	H	(A + C + E)(tan Z)	x	Z	Skew Angle	x
BS	- - -	x	I	3" (cos Z)	x	BB	(A + B)(sec Z)	x
TX	- - -	x	J	(A + B + E)(tan Z)	x	CC	(A + C)(sec Z)	x
TI	- - -	x	K	(S + TI/2)(sec Z)	x	EE	E(sec Z)	x
A	- - -	x	L	2EE + BB + CC	x	HH	20" (sec Z)	x
B	- - -	x	O	I + YY	x	QQ	TX(cos Z)	x
C	- - -	x	T	G(sec Z)	x	YY	TX(sin Z)	x
E	G + O + 20"	x	V	HT + TS - 12"	x	TW	Max{3'-4" or (BS + 12")}	x

Hydrologic Data	
Drainage Area =	___ mi <sup>2</sup>
Design Flood Frequency =	___ years
Design Flood Discharge =	___ cfs
Design Flood (D.F.) Elevation =	_____
Base Flood (100-year)	
Base Flood Elevation =	_____
Base Flood Discharge =	___ cfs
Estimated Backwater =	__ ft
Outlet Velocity =	__ ft/s
Roadway Overtopping	
Overtopping Flood Discharge =	___ cfs
Overtopping Flood Frequency =	___ years
Flood Elevation =	_____

Elevations	
Upstream (Elev. 1) =	
Downstream (Elev. 2) =	
Pr. Gr. at Tie Sta. =	

Fill Heights	
℄ Rdwy at ℄ Culvert =	ft
Design (All units) =	ft

Dimensions are based on end units. Fill heights are measured from the top of top slab to the top of earth fill or roadway.

Estimated Quantities			Final
Class 4 Excavation	cu. yard	x	
Removal of Bridges	lump sum	1	
Class B-1 Concrete (Culverts-Bridge)	cu. yard	x	
Reinforcing Steel (Culverts-Bridge)	pound	x	

General Notes:

Design Specifications:  
2010 AASHTO LRFD Bridge Design Specifications and 2010 Interim Revisions

Design Loading:  
Vehicular = HL-93 minus lane load, Earth = 120 lb/cf  
Equivalent Fluid Pressure = 30 lb/cf (min.), 60 lb/cf (max.)

Design Unit Stresses:  
Class B-1 Concrete (Box Culvert) f'c = 4,000 psi  
Reinforcing Steel (Grade 60) fy = 60,000 psi

Standard Plans:  
703.37, 703.44, 703.46, 703.47

Miscellaneous:  
MoDOT Construction personnel will indicate the type of box culvert constructed:  
☐ Precast Concrete Box used  
☐ Cast-in-Place Concrete Box used

When alternate precast concrete box sections are used, the minimum distance from inside face of headwalls to precast sections measured along the shortest wall shall be 3 feet. Reinforcement and dimensions for wings and headwalls shall be in accordance with Missouri Standard Plans.

Channel bottom shall be graded within the right of way for transition of channel bed to culvert openings. Channel banks shall be tapered to match culvert openings. (Roadway Item)

Traffic Handling:  
Structure to be closed during construction. Traffic to be maintained on during construction. See roadway plans for traffic control.

B.M.

CULVERT-BRIDGE: ROUTE \* OVER \*

ROUTE \* FROM \* TO \*  
ABOUT \* MILES \* OF \*  
TIE STA. \_\_\_\_\_

Designed  
Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. 1 of

DATE PREPARED 10/13/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 3
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
MoDOT 105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	



Pipes With Same Diameter

XX" Pipe Inlet Data		
Station	Offset	F.L. Elev.
xx+xx.xx	xx.xx' XX	xxx.xx
xx+xx.xx	xx.xx' XX	xxx.xx
xx+xx.xx	xx.xx' XX	xxx.xx

Inlets Sized for Elevation A-A  
(Pipe Diameter/Culvert HT)

0.1	0.2	0.3	0.4	0.5
0.6	0.7	0.8	0.9	

Ex: Use 0.5 detail for 36" pipe into a 6' tall culvert.

Pipes With Different Diameters

Pipe Inlet Data			
Station	Offset	Dia.	F.L. Elev.
xx+xx.xx	xx.xx' XX	xx"	xxx.xx
xx+xx.xx	xx.xx' XX	xx"	xxx.xx
xx+xx.xx	xx.xx' XX	xx"	xxx.xx

Supplemental Pipe Inlet Details

4

Supplemental Reinforcement Table (Nonstandard culverts with only one design fill height)

5

Top Slab Reinforcement								Bottom Slab Reinforcement								Wall Reinforcement									
A1 Bars		J3 Bars				H1 Bars		H2 Bars		A2 Bars		J4 Bars				H3 Bars		B1 Bars		B2 Bars					
Sz.	Spa.	Sz.	Spa.	C1	K2	Sz.	Spa.	C5	Sz.	Spa.	C6	Sz.	Spa.	Sz.	Spa.	C4	K3	Sz.	Spa.	C7	Sz.	Spa.	Sz.	Spa.	G1
x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x


Substitute table for tables shown on Standard Plan 703.47

Standard Drawing Guidance  
(Do not show on plans. Turn off the Bridge Construction level to hide)

Some details have been grouped together to allow easy substitution with alternate details. To edit grouped details, select them and press <Ctrl> U.

- 1
- Ahead station is shown for streams flowing left to right. Arrow must be flipped for streams that flow right to left.
- 2
- Modify Estimated Quantities as required. Don't leave blank rows but leave space between Estimated Quantities and General Notes for at least one pay item to be added during construction. See Alternate Details for culvert extensions, or if five items are required.
- 3
- Add any required transverse joints proportionally spaced along barrel. Label units and add actual lengths of units along the barrel.
- 4
- Insert STD 703.60 when pipe inlets are required. Add pipe inlets to Plan of Layout Dimensions at appropriate locations and to Elevation A-A if visible from elevation. Add inlet data using notes where space allows, or use tables.
- 5
- For nonstandard culverts with only one design fill height, add supplemental reinforcement table.
- 6
- No need to revise General Elevation A-A for dual roadways. In Fill Heights table add a lane designation after C Rdwy and insert another row for the other lane.

- \*\*\* VARIABLE DESIGN FILL HEIGHTS \*\*\*
- a
- Select and delete the details grouped with the Fill Heights table. Select and move the alternate grouped details to drawing.
- b
- Place "See Member Thickness table" in the Equation column and place "Varies" in the Dim. column. If Dimension F varies, place "Varies" in the Dim. column.
- c
- Remove blank rows. End units may have different design fill heights but both units need to have the same member thicknesses.
- d
- This portion of table required when design fill height exceeds limits of the standard plans or when culvert cell height or span is not standard. If only a portion of the units are nonstandard, fill out entire table using the values from the standard table where applicable. Omit if not required.





If any part of the barrel is exposed, the roadway fill shall be warped to provide 12 inches minimum cover. (Roadway Item)

Construction joint key not shown for clarity, see standard plans for details.


If unsuitable material is encountered, excavation of unsuitable material and furnishing and placing of granular backfill shall be in accordance with Sec 206.

BXC03\_dbl\_ra\_str      Guidance & Alternate Details (2 of 2)

Corresponds to the border of the standard drawing for ease in moving alternate details (Snap to corner)



Alternate Details for Multiple Design Fill Heights (a)



PLAN OF TRANSVERSE JOINTS AND STAGE CONSTRUCTION

Remove if not applicable.

Fill Heights			
C Rdwy at C Culvert	=		ft
Design (Units 1 & )	=		ft
Design (Units & )	=		ft
Design (Units & )	=		ft

Dimensions are based on end units, except AA is based on Unit . Fill heights are measured from the top of top slab to the top of earth fill or roadway.

Estimated Quantities			Final
Class 4 Excavation	cu. yard	x	
Temporary Shoring	lump sum	1	
Partial Removal of Culvert-Bridge Concrete	lump sum	1	
Class B-1 Concrete (Culverts-Bridge)	cu. yard	x	
Reinforcing Steel (Culverts-Bridge)	pound	x	

2


Alternate Estimated Quantities for Culvert Extensions or when Five Items are Required

Unit No.	Unit Length	Member Thickness					Top Slab Reinforcement										Bottom Slab Reinforcement							Wall Reinforcement		
							A1 Bars		J3 Bars				H1 Bars		H2 Bars		A2 Bars		J4 Bars			H3 Bars		B1 Bars	B2 Bars	
		Sz.	Spa.	Sz.	Spa.	C1	K2	Sz.	Spa.	C5	Sz.	Spa.	C6	Sz.	Spa.	Sz.	Spa.	C4	K3	Sz.	Spa.	C7	Sz.	Spa.	Sz.	Spa.
x	x	x	x	x	x	' -	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x
x	x	x	x	x	x	' -	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x
x	x	x	x	x	x	' -	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x

Substitute table for tables shown on Standard Plan 703.47

2( 'x ' ) CONCRETE BOX CULVERT

SEC/SUR \* TWP \* RGE \*





Construction joint key not shown for clarity, see standard plans for details.

GENERAL ELEVATION A-A

If any part of the barrel is exposed, the roadway fill shall be warped to provide 12 inches minimum cover. (Roadway Item)

If unsuitable material is encountered, excavation of unsuitable material and furnishing and placing of granular backfill shall be in accordance with Sec 206.



PLAN OF LAYOUT DIMENSIONS

Layout Dimensions								
Var.	Equation	Dim.	Var.	Equation	Dim.	Var.	Equation	Dim.
S	- - -	x	C	- - -	x	Q	$TX(\cos 20^\circ)$	x
HT	- - -	x	D	$R + M + N + 20"$	x	R	$P(\cos 20^\circ)$	x
TS	- - -	x	E	$G + 23"$	x	U	$(R + M)(\tan 20^\circ)$	x
BS	- - -	x	F	$2S + 2TX + TI$	x	V	$HT + TS - 12"$	x
TX	- - -	x	G	$2V$	x	W	$2A + B + C + D + E$	x
TI	- - -	x	M	$N(\cos 20^\circ)$	x	Y	$TX(\sin 20^\circ)$	x
A	- - -	x	N	$3" + TX(\tan 10^\circ)$	x	KK	$S + TI/2 + U$	x
B	- - -	x	P	$2V(\sec 20^\circ)$	x	TW	$\text{Max}\{3'-4" \text{ or } (BS + 12")\}$	x

Hydrologic Data	
Drainage Area =	___ mi <sup>2</sup>
Design Flood Frequency =	___ years
Design Flood Discharge =	___ cfs
Design Flood (D.F.) Elevation =	_____
Base Flood (100-year)	
Base Flood Elevation =	_____
Base Flood Discharge =	___ cfs
Estimated Backwater =	__ ft
Outlet Velocity =	__ ft/s
Roadway Overtopping	
Overtopping Flood Discharge =	___ cfs
Overtopping Flood Frequency =	___ years
_____ Flood Elevation =	_____

Elevations	
Upstream (Elev. 1) =	
Downstream (Elev. 2) =	
Pr. Gr. at Tie Sta. =	

Fill Heights	
_____ Rdwy at Culvert =	ft
Design (All units) =	ft

Dimensions are based on end units.

Fill heights are measured from the top of top slab to the top of earth roadway.

Estimated Quantities			Final
Class 4 Excavation	cu. yard	x	
Removal of Bridges	lump sum	1	
Class B-1 Concrete (Culverts-Bridge)	cu. yard	x	
Reinforcing Steel (Culverts-Bridge)	pound	x	

General Notes:

Design Specifications:  
2010 AASHTO LRFD Bridge Design Specifications and 2010 Interim Revisions

Design Loading:  
Vehicular = HL-93 minus lane load, Earth = 120 lb/cf  
Equivalent Fluid Pressure = 30 lb/cf (min.), 60 lb/cf (max.)

Design Unit Stresses:  
Class B-1 Concrete (Box Culvert) f'c = 4,000 psi  
Reinforcing Steel (Grade 60) fy = 60,000 psi

Standard Plans:  
703.37, 703.41, 703.46, 703.47

Miscellaneous:  
MoDOT Construction personnel will indicate the type of box culvert constructed:  
☐ Precast Concrete Box used  
☐ Cast-in-Place Concrete Box used

When alternate precast concrete box sections are used, the minimum distance from inside face of headwalls to precast sections measured along the shortest wall shall be 3 feet. Reinforcement and dimensions for wings and headwalls shall be in accordance with Missouri Standard Plans.

Channel bottom shall be graded within the right of way for transition of channel bed to culvert openings. Channel banks shall be tapered to match culvert openings. (Roadway Item)

Traffic Handling:  
Structure to be closed during construction. Traffic to be maintained on \_\_\_\_\_ during construction. See roadway plans for traffic control.

LOCATION SKETCH

B.M.

CULVERT-BRIDGE: ROUTE \* OVER \*

ROUTE \* FROM \* TO \*

ABOUT \* MILES \* OF \*

TIE STA. \_\_\_\_\_

Designed  
Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. 1 of

DATE PREPARED  
10/13/2023

ROUTE STATE  
DISTRICT SHEET NO.  
4

COUNTY

JOB NO.

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

MoDOT

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

Pipes With Same Diameter

XX" Pipe Inlet Data		
Station	Offset	F.L. Elev.
xx+xx.xx	xx.xx' XX	xxx.xx
xx+xx.xx	xx.xx' XX	xxx.xx
xx+xx.xx	xx.xx' XX	xxx.xx

Inlets Sized for Elevation A-A  
(Pipe Diameter/Culvert HT)

Pipes With Different Diameters

Pipe Inlet Data			
Station	Offset	Dia.	F.L. Elev.
xx+xx.xx	xx.xx' XX	xx"	xxx.xx
xx+xx.xx	xx.xx' XX	xx"	xxx.xx
xx+xx.xx	xx.xx' XX	xx"	xxx.xx

Supplemental Pipe Inlet Details ④

Supplemental Reinforcement Table (Nonstandard culverts with only one design fill height) ⑤

Top Slab Reinforcement												Bottom Slab Reinforcement							Wall Reinforcement				
A1 Bars		J3 Bars				H1 Bars		H2 Bars		A2 Bars		J4 Bars			H3 Bars		B1 Bars	B2 Bars					
Sz.	Spa.	Sz.	Spa.	C1	K2	Sz.	Spa.	C5	Sz.	Spa.	C6	Sz.	Spa.	Sz.	Spa.	C4	K3	Sz.	Spa.	C7	Sz.	Spa.	G1
x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x

Substitute table for tables shown on Standard Plan 703.47


Standard Drawing Guidance  
(Do not show on plans. Turn off the Bridge Construction level to hide)

Some details have been grouped together to allow easy substitution with alternate details. To edit grouped details, select them and press <Ctrl> U.

- ① Ahead station is shown for streams flowing left to right. Arrow must be flipped for streams that flow right to left.
- ② Modify Estimated Quantities as required. Don't leave blank rows but leave space between Estimated Quantities and General Notes for at least one pay item to be added during construction. See Alternate Details for culvert extensions, or if five items are required.
- ③ Add any required transverse joints proportionally spaced along the barrel. Label units and add actual lengths of units along the barrel.
- ④ Insert STD 703.60 when pipe inlets are required. Add pipe inlets to Plan of Layout Dimensions at appropriate locations and to Elevation A-A if visible from elevation. Add inlet data using notes where space allows, or use tables.
- ⑤ For nonstandard culverts with only one design fill height, add supplemental reinforcement table.
- ⑥ No need to revise General Elevation A-A for dual roadways. In Fill Heights table add a lane designation after  $\text{C Rdwy}$  and insert another row for the other lane.

\*\*\* VARIABLE DESIGN FILL HEIGHTS \*\*\*

- a Select and delete the details grouped with the Fill Heights table. Select and move the alternate grouped details to drawing.
- b Place "See Member Thickness table" in the Equation column and place "Varies" in the Dim. column. If Dimension F varies, place "Varies" in the Dim. column.
- c Remove blank rows. End units may have different design fill heights but both units need to have the same member thicknesses.
- d This portion of table required when design fill height exceeds limits of the standard plans or when culvert cell height or span is not standard. If only a portion of the units are nonstandard, fill out entire table using the values from the standard table where applicable. Omit if not required.



If any part of the barrel is exposed, the roadway fill shall be warped to provide 12 inches minimum cover. (Roadway Item)




Construction joint key not shown for clarity, see standard plans for details.

If unsuitable material is encountered, excavation of unsuitable material and furnishing and placing of granular backfill shall be in accordance with Sec 206.

BXC04\_dbI\_sq\_fla      Guidance & Alternate Details (2 of 2)

Corresponds to the border of the standard drawing for ease in moving alternate details (Snap to corner)

Alternate Details for Multiple Design Fill Heights (a)



Remove if not applicable.

Fill Heights			
C Rdwy at C Culvert =		ft	
Design (Units 1 & ) =		ft	
Design (Units & ) =		ft	
Design (Units & ) =		ft	

Dimensions are based on end units, except AA is based on Unit . Fill heights are measured from the top of top slab to the top of earth fill or roadway.


Estimated Quantities			Final
Class 4 Excavation	cu. yard	x	
Temporary Shoring	lump sum	1	
Partial Removal of Culvert-Bridge Concrete	lump sum	1	
Class B-1 Concrete (Culverts-Bridge)	cu. yard	x	
Reinforcing Steel (Culverts-Bridge)	pound	x	

2

Alternate Estimated Quantities for Culvert Extensions or when Five Items are Required

Unit No.	Unit Length	Member Thickness					Top Slab Reinforcement										Bottom Slab Reinforcement						Wall Reinforcement		
							A1 Bars		J3 Bars				H1 Bars		H2 Bars		A2 Bars		J4 Bars			H3 Bars		B1 Bars	B2 Bars
		Sz.	Spa.	Sz.	Spa.	C1	K2	Sz.	Spa.	C5	Sz.	Spa.	C6	Sz.	Spa.	C4	K3	Sz.	Spa.	C7	Sz.	Spa.	G1		
x	x	x	x	x	x	' - "	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x		
x	x	x	x	x	x	' - "	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x		
x	x	x	x	x	x	' - "	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x		

Substitute table for tables shown on Standard Plan 703.47



SEC/SUR \* TWP \* RGE \*

### Layout Dimensions

Var.	Equation	Dim.	Var.	Equation	Dim.	Var.	Equation	Dim.
S	- - -	x	K	$(S + TI/2)(\sec Z)$	x	BB	$(A + B)(\sec Z)$	x
HT	- - -	x	L	$AA + BB + CC + DD + EE$	x	CC	$(A + C)(\sec Z)$	x
TS	- - -	x	M	$N(\cos 20^\circ)$	x	DD	$R + M + N + 20"$	x
BS	- - -	x	N	$3" + TX(\tan 10^\circ)$	x	EE	$E(\sec Z)$	x
TX	- - -	x	O	$I + YY$	x	HH	$20"(\sec Z)$	x
TI	- - -	x	P	$2V[\sec(Z + 20^\circ)]$	x	II	$20"(\cos Z)$	x
A	- - -	x	Q	$TX(\cos 20^\circ)$	x	KK	$S + TI/2 + U$	x
B	- - -	x	R	$P(\cos 20^\circ)$	x	LL	$(AA + BB + DD)(\cos Z)$	x
C	- - -	x	T	$G(\sec Z)$	x	MM	$3"[\cos Z + \cos(Z - 20^\circ)]$	x
D	$II + MM + RR + TT$	x	U	$(R + M)(\tan 20^\circ)$	x	QQ	$TX(\cos Z)$	x
E	$G + O + 20"$	x	V	$HT + TS - 12"$	x	RR	$P[\cos(Z - 20^\circ)]$	x
F	$2S + 2TX + TI$	x	W	$2A + B + C + D + E + SS$	x	SS	$F(\sin Z)$	x
G	$2V$	x	X	$3" + TX(\tan Z)$	x	TT	$TX[\sin(20^\circ - Z)]$	x
H	$(A + C + E)(\tan Z)$	x	Y	$TX(\sin 20^\circ)$	x	YY	$TX(\sin Z)$	x
I	$3"(\cos Z)$	x	Z	Skew Angle	x	TW	$\text{Max}\{3'-4" \text{ or } (BS + 12")\}$	x
J	$(AA + BB + DD)(\sin Z)$	x	AA	$F(\tan Z)/2$	x			

### Hydrologic Data

Drainage Area = \_\_\_ mi<sup>2</sup>  
Design Flood Frequency = \_\_\_ years  
Design Flood Discharge = \_\_\_ cfs  
Design Flood (D.F.) Elevation = \_\_\_\_\_  
Base Flood (100-year)  
Base Flood Elevation = \_\_\_\_\_  
Base Flood Discharge = \_\_\_ cfs  
Estimated Backwater = \_\_ ft  
Outlet Velocity = \_\_ ft/s  
Roadway Overtopping  
Overtopping Flood Discharge = \_\_\_ cfs  
Overtopping Flood Frequency = \_\_\_ years  
\_\_\_\_\_ Flood Elevation = \_\_\_\_\_

### Elevations

Upstream (Elev. 1) = \_\_\_\_\_  
Downstream (Elev. 2) = \_\_\_\_\_  
Pr. Gr. at Tie Sta. = \_\_\_\_\_

### Fill Heights

\_\_\_\_\_ Rdwy at \_\_\_\_\_ Culvert = \_\_\_\_\_ ft  
Design (All units) = \_\_\_\_\_ ft

Dimensions are based on end units.  
Fill heights are measured from the top of top slab to the top of earth fill or roadway.

### Estimated Quantities

			Final
Class 4 Excavation	cu. yard	x	
Removal of Bridges	lump sum	1	
Class B-1 Concrete (Culverts-Bridge)	cu. yard	x	
Reinforcing Steel (Culverts-Bridge)	pound	x	

### General Notes:

**Design Specifications:**  
2010 AASHTO LRFD Bridge Design Specifications and 2010 Interim Revisions

**Design Loading:**  
Vehicular = HL-93 minus lane load, Earth = 120 lb/cf  
Equivalent Fluid Pressure = 30 lb/cf (min.), 60 lb/cf (max.)

**Design Unit Stresses:**  
Class B-1 Concrete (Box Culvert) f'c = 4,000 psi  
Reinforcing Steel (Grade 60) fy = 60,000 psi

**Standard Plans:**  
703.37, 703.43, 703.46, 703.47

**Miscellaneous:**  
MoDOT Construction personnel will indicate the type of box culvert constructed:  
☐ Precast Concrete Box used  
☐ Cast-in-Place Concrete Box used

When alternate precast concrete box sections are used, the minimum distance from inside face of headwalls to precast sections measured along the shortest wall shall be 3 feet. Reinforcement and dimensions for wings and headwalls shall be in accordance with Missouri Standard Plans.

Channel bottom shall be graded within the right of way for transition of channel bed to culvert openings. Channel banks shall be tapered to match culvert openings. (Roadway Item)

**Traffic Handling:**  
Structure to be closed during construction. Traffic to be maintained on \_\_\_\_\_ during construction. See roadway plans for traffic control.

B.M.

**CULVERT-BRIDGE: ROUTE \* OVER \***  
ROUTE \* FROM \* TO \*  
ABOUT \* MILES \* OF \*  
TIE STA. \_\_\_\_\_

DATE PREPARED  
10/13/2023

ROUTE STATE  
DISTRICT SHEET NO.  
5

COUNTY

JOB NO.

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

MoDOT

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)



Pipes With Same Diameter

XX" Pipe Inlet Data		
Station	Offset	F.L. Elev.
xx+xx.xx	xx.xx' XX	xxx.xx
xx+xx.xx	xx.xx' XX	xxx.xx
xx+xx.xx	xx.xx' XX	xxx.xx

Inlets Sized for Elevation A-A  
(Pipe Diameter/Culvert HT)

0.1	0.2	0.3	0.4	0.5
0.6	0.7	0.8	0.9	

Ex: Use 0.5 detail for 36" pipe into a 6' tall culvert.

Pipes With Different Diameters

Pipe Inlet Data			
Station	Offset	Dia.	F.L. Elev.
xx+xx.xx	xx.xx' XX	xx"	xxx.xx
xx+xx.xx	xx.xx' XX	xx"	xxx.xx
xx+xx.xx	xx.xx' XX	xx"	xxx.xx

Supplemental Reinforcement Table (Nonstandard culverts with only one design fill height)

Top Slab Reinforcement										Bottom Slab Reinforcement						Wall Reinforcement									
A1 Bars		J3 Bars				H1 Bars		H2 Bars		A2 Bars		J4 Bars		H3 Bars		B1 Bars	B2 Bars								
Sz.	Spa.	Sz.	Spa.	C1	K2	Sz.	Spa.	C5	Sz.	Spa.	C6	Sz.	Spa.	Sz.	Spa.	C4	K3	Sz.	Spa.	C7	Sz.	Spa.	Sz.	Spa.	G1
x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x

Substitute table for tables shown on Standard Plan 703.47

Standard Drawing Guidance  
(Do not show on plans. Turn off the Bridge Construction Level to hide)

Some details have been grouped together to allow easy substitution with alternate details. To edit grouped details, select them and press <Ctrl> U.

- 1 Ahead station is shown for streams flowing left to right. Arrow must be flipped for streams that flow right to left.

2 Modify Estimated Quantities as required. Don't leave blank rows but leave space between Estimated Quantities and General Notes for at least one pay item to be added during construction. See Alternate Details for culvert extensions, or if five items are required.

3 Add any required transverse joints proportionally spaced along the barrel. Label units and add actual lengths of units along the barrel.

4 Insert STD 703.60 when pipe inlets are required. Add pipe inlets to Plan of Layout Dimensions at appropriate locations and to Elevation A-A if visible from elevation. Add inlet data using notes where space allows, or use tables.

5 For nonstandard culverts with only one design fill height, add supplemental reinforcement table.

6 No need to revise General Elevation A-A for dual roadways. In Fill Heights table add a lane designation after C Rdwy and insert another row for the other lane.


7 For skews 20° or more, remove Detail C, remove TT from the equation for D and place "N/A" in the Dim. column for Dim. TT. Will first need to drop Detail C from group by selecting it, then pressing <Ctrl> U.
- \*\*\* VARIABLE DESIGN FILL HEIGHTS \*\*\*

a Select and delete the details grouped with the Fill Heights table. Select and move the alternate grouped details to drawing.

b Place "See Member Thickness table" in the Equation column and place "Varies" in the Dim. column. If Dimension F varies, place "Varies" in the Dim. column.

c Remove blank rows. End units may have different design fill heights but both units need to have the same member thicknesses.

d This portion of table required when design fill height exceeds limits of the standard plans or when culvert cell height or span is not standard. If only a portion of the units are nonstandard, fill out entire table using the values from the standard table where applicable. Omit if not required.




If unsuitable material is encountered, excavation of unsuitable material and furnishing and placing of granular backfill shall be in accordance with Sec 206.

## Guidance & Alternate Details (2 of 2)

Corresponds to the border of the standard drawing for ease in moving alternate details (Snap to corner)

### — Alternate Details for Multiple Design Fill Heights (a)



### PLAN OF TRANSVERSE JOINTS AND STAGE CONSTRUCTION

Remove if not applicable.—

Fill Heights		
℄ Rdwy at ℄ Culvert =		ft
Design (Units 1 & ) =		ft
Design (Units & ) =		ft
Design (Units & ) =		ft

Dimensions are based on end units, except AA is based on Unit . Fill heights are measured from the top of top slab to the top of earth fill or roadway.

Estimated Quantities			Final
Class 4 Excavation	cu. yard	x	
Temporary Shoring	lump sum	1	
Partial Removal of Culvert-Bridge Concrete	lump sum	1	
Class B-1 Concrete (Culverts-Bridge)	cu. yard	x	
Reinforcing Steel (Culverts-Bridge)	pound	x	

— Alternate Estimated Quantities for Culvert Extensions or when Five Items are Required

[illegible]

Substitute table for tables shown on Standard Plan 703.47



Pipes With Same Diameter

XX" Pipe Inlet Data		
Station	Offset	F.L. Elev.
xx+xx.xx	xx.xx' XX	xxx.xx
xx+xx.xx	xx.xx' XX	xxx.xx
xx+xx.xx	xx.xx' XX	xxx.xx

Inlets Sized for Elevation A-A  
(Pipe Diameter/Culvert HT)

0.1

0.2

0.3

0.4

0.5

0.6

0.7

0.8

0.9

Ex: Use 0.5 detail for 36" pipe into a 6' tall culvert.

Pipes With Different Diameters

Pipe Inlet Data			
Station	Offset	Dia.	F.L. Elev.
xx+xx.xx	xx.xx' XX	xx"	xxx.xx
xx+xx.xx	xx.xx' XX	xx"	xxx.xx
xx+xx.xx	xx.xx' XX	xx"	xxx.xx

Supplemental Pipe Inlet Details ④

Supplemental Reinforcement Table (Nonstandard culverts with only one design fill height) ⑤

Top Slab Reinforcement										Bottom Slab Reinforcement							Wall Reinforcement								
A1 Bars		J3 Bars				H1 Bars		H2 Bars		A2 Bars		J4 Bars			H3 Bars		B1 Bars	B2 Bars							
Sz.	Spa.	Sz.	Spa.	C1	K2	Sz.	Spa.	C5	Sz.	Spa.	C6	Sz.	Spa.	Sz.	Spa.	C4	K3	Sz.	Spa.	C7	Sz.	Spa.	Sz.	Spa.	G1
x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x

Substitute table for tables shown on Standard Plan 703.47

Standard Drawing Guidance  
(Do not show on plans. Turn off the Bridge Construction level to hide)


Some details have been grouped together to allow easy substitution with alternate details. To edit grouped details, select them and press <Ctrl> U.

- ① Ahead station is shown for streams flowing left to right. Arrow must be flipped for streams that flow right to left.
- ② Modify Estimated Quantities as required. Don't leave blank rows but leave space between Estimated Quantities and General Notes for at least one pay item to be added during construction. See Alternate Details for culvert extensions, or if five items are required.
- ③ Add any required transverse joints proportionally spaced along the barrel. Label units and add actual lengths of units along the barrel.
- ④ Insert STD 703.60 when pipe inlets are required. Add pipe inlets to Plan of Layout Dimensions at appropriate locations and to Elevation A-A if visible from elevation. Add inlet data using notes where space allows, or use tables.
- ⑤ For nonstandard culverts with only one design fill height, add supplemental reinforcement table.
- ⑥ No need to revise General Elevation A-A for dual roadways. In Fill Heights table add a lane designation after  $\text{\textcircled{C}}$  Rdwy and insert another row for the other lane.
- ⑦ For skews 20° or more, remove Detail C, remove TT from the equation for D and place "N/A" in the Dim. column for Dim. TT. Will first need to drop Detail C from group by selecting it, then pressing <Ctrl> U.

\*\*\* VARIABLE DESIGN FILL HEIGHTS \*\*\*

- ① Select and delete the details grouped with the Fill Heights table. Select and move the alternate grouped details to drawing.
- ② Place "See Member Thickness table" in the Equation column and place "Varies" in the Dim. column. If Dimension F varies, place "Varies" in the Dim. column.
- ③ Remove blank rows. End units may have different design fill heights but both units need to have the same member thicknesses.
- ④ This portion of table required when design fill height exceeds limits of the standard plans or when culvert cell height or span is not standard. If only a portion of the units are nonstandard, fill out entire table using the values from the standard table where applicable. Omit if not required.

Alternate Plan of Transverse Joints




If unsuitable material is encountered, excavation of unsuitable material and furnishing and placing of granular backfill shall be in accordance with Sec 206.

## Guidance & Alternate Details (2 of 2)

Corresponds to the border of the standard drawing for ease in moving alternate details (Snap to corner)

### — Alternate Details for Multiple Design Fill Heights (a)



### PLAN OF TRANSVERSE JOINTS AND STAGE CONSTRUCTION

Remove if not applicable.

Fill Heights		
℄ Rdwy at ℄ Culvert =		ft
Design (Units 1 & ) =		ft
Design (Units & ) =		ft
Design (Units & ) =		ft

Dimensions are based on end units, except AA is based on Unit . Fill heights are measured from the top of top slab to the top of earth fill or roadway.

Estimated Quantities			Final
Class 4 Excavation	cu. yard	x	
Temporary Shoring	lump sum	1	
Partial Removal of Culvert-Bridge Concrete	lump sum	1	
Class B-1 Concrete (Culverts-Bridge)	cu. yard	x	
Reinforcing Steel (Culverts-Bridge)	pound	x	

### — Alternate Estimated Quantities for Culvert Extensions or when Five Items are Required

LOCATION SKETCH


[illegible]

Substitute table for tables shown on Standard Plan 703.47



3 ( 'x ' ) CONCRETE BOX CULVERT

SEC/SUR \* TWP \* RGE \*



Construction joint key not shown for clarity, see standard plans for details.

If any part of the barrel is exposed, the roadway fill shall be warped to provide 12 inches minimum cover. (Roadway Item)

If unsuitable material is encountered, excavation of unsuitable material and furnishing and placing of granular backfill shall be in accordance with Sec 206.

GENERAL ELEVATION A-A

Layout Dimensions

Var.	Equation	Dim.	Var.	Equation	Dim.	Var.	Equation	Dim.
S	- - -	x	TI	- - -	x	F	3S + 2TX + 2TI	x
HT	- - -	x	A	- - -	x	G	2V	x
TS	- - -	x	B	- - -	x	V	HT + TS - 12"	x
BS	- - -	x	C	- - -	x	W	2A + B + C + 2E	x
TX	- - -	x	E	G + 23"	x	TW	Max{3'-4" or (BS + 12")}	x

Hydrologic Data

Drainage Area =	___ mi <sup>2</sup>
Design Flood Frequency =	___ years
Design Flood Discharge =	___ cfs
Design Flood (D.F.) Elevation =	_____
Base Flood (100-year)	
Base Flood Elevation =	_____
Base Flood Discharge =	___ cfs
Estimated Backwater =	__ ft
Outlet Velocity =	__ ft/s
Roadway Overtopping	
Overtopping Flood Discharge =	___ cfs
Overtopping Flood Frequency =	___ years
_____ Flood Elevation =	_____

Elevations

Upstream (Elev. 1) =	
Downstream (Elev. 2) =	
Pr. Gr. at Tie Sta. =	


Dimensions are based on end units.  
Fill heights are measured from the top of top slab to the top of earth fill or roadway.

Fill Heights

Cl Rdwy at Culvert =	ft
Design (All units) =	ft

Estimated Quantities

			Final
Class 4 Excavation	cu. yard	x	
Removal of Bridges	lump sum	1	
Class B-1 Concrete (Culverts-Bridge)	cu. yard	x	
Reinforcing Steel (Culverts-Bridge)	pound	x	



PLAN OF LAYOUT DIMENSIONS

LOCATION SKETCH

General Notes:

Design Specifications:  
2010 AASHTO LRFD Bridge Design Specifications and 2010 Interim Revisions

Design Loading:  
Vehicular = HL-93 minus lane load, Earth = 120 lb/cf  
Equivalent Fluid Pressure = 30 lb/cf (min.), 60 lb/cf (max.)

Design Unit Stresses:  
Class B-1 Concrete (Box Culvert) f'c = 4,000 psi  
Reinforcing Steel (Grade 60) fy = 60,000 psi

Standard Plans:  
703.37, 703.80, 703.86, 703.87

Miscellaneous:  
MoDOT Construction personnel will indicate the type of box culvert constructed:  
☐ Precast Concrete Box used  
☐ Cast-in-Place Concrete Box used

When alternate precast concrete box sections are used, the minimum distance from inside face of headwalls to precast sections measured along the shortest wall shall be 3 feet. Reinforcement and dimensions for wings and headwalls shall be in accordance with Missouri Standard Plans.

Channel bottom shall be graded within the right of way for transition of channel bed to culvert openings. Channel banks shall be tapered to match culvert openings. (Roadway Item)

Traffic Handling:  
Structure to be closed during construction. Traffic to be maintained on during construction. See roadway plans for traffic control.

B.M.

CULVERT-BRIDGE: ROUTE \* OVER \*

ROUTE \* FROM \* TO \*  
ABOUT \* MILES \* OF \*  
TIE STA. \_\_\_\_\_

Designed  
Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. 1 of

DATE PREPARED  
10/13/2023

ROUTE  
DISTRICT

STATE  
MO

SHEET NO.  
7

COUNTY

JOB NO.

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

MoDOT

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

If any part of the barrel is exposed, the roadway fill shall be warped to provide 12 inches minimum cover. (Roadway Item)

Construction joint key not shown for clarity, see standard plans for details.

If unsuitable material is encountered, excavation of unsuitable material and furnishing and placing of granular backfill shall be in accordance with Sec 206.

BXC07\_tri\_sq\_str

Guidance & Alternate Details (2 of 2)

Corresponds to the border of the standard drawing for ease in moving alternate details (Snap to corner)

Alternate Details for Multiple Design Fill Heights (a)


Fill Heights		
℄ Rdwy at ℄ Culvert =		ft
Design (Units 1 & ) =		ft
Design (Units & ) =		ft
Design (Units & ) =		ft

Dimensions are based on end units, except AA is based on Unit . Fill heights are measured from the top of top slab to the top of earth fill or roadway.


Estimated Quantities			Final
Class 4 Excavation	cu. yard	x	
Temporary Shoring	lump sum	1	
Partial Removal of Culvert-Bridge Concrete	lump sum	1	
Class B-1 Concrete (Culverts-Bridge)	cu. yard	x	
Reinforcing Steel (Culverts-Bridge)	pound	x	

2

Alternate Estimated Quantities for Culvert Extensions or when Five Items are Required



PLAN OF LAYOUT DIMENSIONS



PLAN OF TRANSVERSE JOINTS AND STAGE CONSTRUCTION

Remove if not applicable.

Unit No.	Unit Length	Member Thickness					Top Slab Reinforcement										Bottom Slab Reinforcement										Wall Reinforcement									
							A1 Bars				J3 Bars			H1 Bars			H2 Bars			A2 Bars		J4 Bars			H3 Bars			B1 Bars		B2 Bars						
		TS	BS	TX	TI	F	Sz.	Spa.	Sz.	Spa.	C1	K2	Sz.	Spa.	C5	Q8	Sz.	Spa.	C6	Q9	Sz.	Spa.	Sz.	Spa.	C4	K3	Sz.	Spa.	C7	Q10	Sz.	Spa.	Sz.	Spa.	G1	
x	x	x	x	x	x	' - "	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x
x	x	x	x	x	x	' - "	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x
x	x	x	x	x	x	' - "	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x


Substitute table for tables shown on Standard Plan 703.87





## 3 ( 'x ' ) CONCRETE BOX CULVERT

SEC/SUR \* TWP \* RGE \*



Construction joint key not shown for clarity, see standard plans for details.

If any part of the barrel is exposed, the roadway fill shall be warped to provide 12 inches minimum cover. (Roadway Item)

If unsuitable material is encountered, excavation of unsuitable material and furnishing and placing of granular backfill shall be in accordance with Sec 206.



Layout Dimensions								
Var.	Equation	Dim.	Var.	Equation	Dim.	Var.	Equation	Dim.
S	- - -	x	F	3S + 2TX + 2TI	x	W	2A + B + C + 2E	x
HT	- - -	x	G	2V	x	X	3" + TX(tan Z)	x
TS	- - -	x	H	(A + C + E)(tan Z)	x	Z	Skew Angle	x
BS	- - -	x	I	3"(cos Z)	x	BB	(A + B)(sec Z)	x
TX	- - -	x	J	(A + B + E)(tan Z)	x	CC	(A + C)(sec Z)	x
TI	- - -	x	K	(3S/2 + TI)(sec Z)	x	EE	E(sec Z)	x
A	- - -	x	L	2EE + BB + CC	x	HH	20"(sec Z)	x
B	- - -	x	O	I + YY	x	QQ	TX(cos Z)	x
C	- - -	x	T	G(sec Z)	x	YY	TX(sin Z)	x
E	G + O + 20"	x	V	HT + TS - 12"	x	TW	Max{3'-4" or (BS + 12")}	x

Hydrologic Data
Drainage Area = ___ mi <sup>2</sup>
Design Flood Frequency = ___ years
Design Flood Discharge = ___ cfs
Design Flood (D.F.) Elevation = _____
Base Flood (100-year)
Base Flood Elevation = _____
Base Flood Discharge = ___ cfs
Estimated Backwater = ___ ft
Outlet Velocity = __ ft/s
Roadway Overtopping
Overtopping Flood Discharge = ___ cfs
Overtopping Flood Frequency = ___ years
_____ Flood Elevation = _____

Elevations	
Upstream (Elev. 1) =	
Downstream (Elev. 2) =	
Pr. Gr. at Tie Sta. =	

6	Fill Heights
Ⓒ Rdwy at Ⓒ Culvert =	ft
Design (All units) =	ft

Estimated Quantities			Final
Class 4 Excavation	cu. yard	x	
Removal of Bridges	lump sum	1	
Class B-1 Concrete (Culverts-Bridge)	cu. yard	x	
Reinforcing Steel (Culverts-Bridge)	pound	x	



LOCATION SKETCH

General Notes:

**Design Specifications:**  
2010 AASHTO LRFD Bridge Design Specifications and 2010  
Interim Revisions

Design Loading:  
 Vehicular = HL-93 minus lane load, Earth = 120 lb/cf  
 Equivalent Fluid Pressure = 30 lb/cf (min.), 60 lb/cf (max.)

**Design Unit Stresses:**  
 Class B-1 Concrete (Box Culvert)  $f'_c = 4,000$  psi  
 Reinforcing Steel (Grade 60)  $f_y = 60,000$  psi

Standard Plans:

Miscellaneous:  
MoDOT Construction personnel will indicate the type of box culvert constructed:  
☐ Precast Concrete Box used  
☐ Cast-in-Place Concrete Box used

When alternate precast concrete box sections are used, the minimum distance from inside face of headwalls to precast sections measured along the shortest wall shall be 3 feet. Reinforcement and dimensions for wings and headwalls shall be in accordance with Missouri Standard Plans.

Channel bottom shall be graded within the right of way for transition of channel bed to culvert openings. Channel banks shall be tapered to match culvert openings. (Roadway Item)

**Traffic Handling:**  
Structure to be closed during construction. Traffic to be maintained on during construction. See roadway plans for traffic control.

B.M.

CULVERT-BRIDGE: ROUTE \* OVER \*

ROUTE \* FROM \* TO \*  
ABOUT \* MILES \* OF \*  
TIE STA. \_\_\_\_\_

Designed  
Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. 1 of

DATE PREPARED	
10/13/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	8

JOB NO.

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE \_\_\_\_\_

MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

Pipes With Same Diameter

XX" Pipe Inlet Data		
Station	Offset	F.L. Elev.
xx+xx.xx	xx.xx' XX	xxx.xx
xx+xx.xx	xx.xx' XX	xxx.xx
xx+xx.xx	xx.xx' XX	xxx.xx

Inlets Sized for Elevation A-A  
(Pipe Diameter/Culvert HT)

0.1	0.2	0.3	0.4	0.5
0.6	0.7	0.8	0.9	

Ex: Use 0.5 detail for 36" pipe into a 6' tall culvert.

Pipes With Different Diameters

Pipe Inlet Data			
Station	Offset	Dia.	F.L. Elev.
xx+xx.xx	xx.xx' XX	xx"	xxx.xx
xx+xx.xx	xx.xx' XX	xx"	xxx.xx
xx+xx.xx	xx.xx' XX	xx"	xxx.xx

Supplemental Pipe Inlet Details ④

Supplemental Reinforcement Table (Nonstandard culverts with only one design fill height) ⑤

Top Slab Reinforcement												Bottom Slab Reinforcement										Wall Reinforcement						
A1 Bars		J3 Bars				H1 Bars				H2 Bars				A2 Bars		J4 Bars				H3 Bars				B1 Bars		B2 Bars		
Sz.	Spa.	Sz.	Spa.	C1	K2	Sz.	Spa.	C5	Q8	Sz.	Spa.	C6	Q9	Sz.	Spa.	Sz.	Spa.	C4	K3	Sz.	Spa.	C7	Q10	Sz.	Spa.	Sz.	Spa.	G1
x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x
Substitute table for tables shown on Standard Plan 703.87																												

Standard Drawing Guidance  
(Do not show on plans. Turn off the Bridge Construction level to hide)


Some details have been grouped together to allow easy substitution with alternate details. To edit grouped details, select them and press <Ctrl> U.

- ① Ahead station is shown for streams flowing left to right. Arrow must be flipped for streams that flow right to left.
- ② Modify Estimated Quantities as required. Don't leave blank rows but leave space between Estimated Quantities and General Notes for at least one pay item to be added during construction. See Alternate Details for culvert extensions, or if five items are required.
- ③ Add any required transverse joints proportionally spaced along the barrel. Label units and add actual lengths of units along the barrel.
- ④ Insert STD 703.60 when pipe inlets are required. Add pipe inlets to Plan of Layout Dimensions at appropriate locations and to Elevation A-A if visible from elevation. Add Inlet data using notes where space allows, or use tables.
- ⑤ For nonstandard culverts with only one design fill height, add supplemental reinforcement table.
- ⑥ No need to revise General Elevation A-A for dual roadways. In Fill Heights table add a lane designation after  $\varnothing$  Rdwy and insert another row for the other lane.

\*\*\* VARIABLE DESIGN FILL HEIGHTS \*\*\*

- Ⓐ Select and delete the details grouped with the Fill Heights table. Select and move the alternate grouped details to drawing.
- Ⓑ Place "See Member Thickness table" in the Equation column and place "Varies" in the Dim. column. If Dimension F varies, place "Varies" in the Dim. column.
- Ⓒ Remove blank rows. End units may have different design fill heights but both units need to have the same member thicknesses.
- Ⓓ This portion of table required when design fill height exceeds limits of the standard plans or when culvert cell height or span is not standard. If only a portion of the units are nonstandard, fill out entire table using the values from the standard table where applicable. Omit if not required.

Alternate Plan of Transverse Joints




If unsuitable material is encountered, excavation of unsuitable material and furnishing and placing of granular backfill shall be in accordance with Sec 206.

BXC08\_tri\_la\_str


## Guidance & Alternate Details (2 of 2)

Corresponds to the border of the standard drawing for ease in moving alternate details (Snap to corner)

### —Alternate Details for Multiple Design Fill Heights (a)



### DETAIL A



### PLAN OF TRANSVERSE JOINTS AND STAGE CONSTRUCTION

Remove if not applicable.

Fill Heights		
℄ Rdwy at ℄ Culvert =		ft
Design (Units 1 & ) =		ft
Design (Units & ) =		ft
Design (Units & ) =		ft

Dimensions are based on end units, except AA is based on Unit . Fill heights are measured from the top of top slab to the top of earth fill or roadway.

Estimated Quantities			Final
Class 4 Excavation	cu. yard	x	
Temporary Shoring	lump sum	1	
Partial Removal of Culvert-Bridge Concrete	lump sum	1	
Class B-1 Concrete (Culverts-Bridge)	cu. yard	x	
Reinforcing Steel (Culverts-Bridge)	pound	x	

(


—Alternate Estimated Quantities for Culvert Extensions or when Five Items are Required

Unit No.	Unit Length	Member Thickness					Top Slab Reinforcement																Bottom Slab Reinforcement										Wall Reinforcement			
							A1 Bars				J3 Bars				H1 Bars				H2 Bars				A2 Bars				J4 Bars				H3 Bars				B1 Bars	
		TS	BS	TX	TI	F	Sz.	Spa.	Sz.	Spa.	C1	K2	Sz.	Spa.	C5	Q8	Sz.	Spa.	C6	Q9	Sz.	Spa.	Sz.	Spa.	C4	K3	Sz.	Spa.	C7	Q10	Sz.	Spa.	Sz.	Spa.	G	
x	x	x	x	x	x	' - "	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	
x	x	x	x	x	x	' - "	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	
x	x	x	x	x	x	' - "	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	

Substitute table for tables shown on Standard Plan 703.87

3( 'x ' ) CONCRETE BOX CULVERT



SEC/SUR \* TWP \* RGE \*



Construction joint key not shown for clarity, see standard plans for details.

If any part of the barrel is exposed, the roadway fill shall be warped to provide 12 inches minimum cover. (Roadway Item)

If unsuitable material is encountered, excavation of unsuitable material and furnishing and placing of granular backfill shall be in accordance with Sec 206.



Layout Dimensions								
Var.	Equation	Dim.	Var.	Equation	Dim.	Var.	Equation	Dim.
S	- - -	x	F	3S + 2TX + 2TI	x	W	2A + B + C + 2E	x
HT	- - -	x	G	2V	x	X	3" + TX(tan Z)	x
TS	- - -	x	H	(A + C + E)(tan Z)	x	Z	Skew Angle	x
BS	- - -	x	I	3"(cos Z)	x	BB	(A + B)(sec Z)	x
TX	- - -	x	J	(A + B + E)(tan Z)	x	CC	(A + C)(sec Z)	x
TI	- - -	x	K	(3S/2 + TI)(sec Z)	x	EE	E(sec Z)	x
A	- - -	x	L	2EE + BB + CC	x	HH	20"(sec Z)	x
B	- - -	x	O	I + YY	x	QQ	TX(cos Z)	x
C	- - -	x	T	G(sec Z)	x	YY	TX(sin Z)	x
E	G + O + 20"	x	V	HT + TS - 12"	x	TW	Max{3'-4" or (BS + 12")}	x

Hydrologic Data
Drainage Area = ___ mi <sup>2</sup>
Design Flood Frequency = ___ years
Design Flood Discharge = ___ cfs
Design Flood (D.F.) Elevation = _____
Base Flood (100-year)
Base Flood Elevation = _____
Base Flood Discharge = ___ cfs
Estimated Backwater = ___ ft
Outlet Velocity = __ ft/s
Roadway Overtopping
Overtopping Flood Discharge = ___ cfs
Overtopping Flood Frequency = ___ years
_____ Flood Elevation = _____

Elevations	
Upstream (Elev. 1) =	
Downstream (Elev. 2) =	
Pr. Gr. at Tie Sta. =	

6	Fill Heights
℄ Rdwy at ℄ Culvert =	ft
Design (All units) =	ft

Estimated Quantities			Final
Class 4 Excavation	cu. yard	x	
Removal of Bridges	lump sum	1	
Class B-1 Concrete (Culverts-Bridge)	cu. yard	x	
Reinforcing Steel (Culverts-Bridge)	pound	x	

General Notes:

Design Specifications:  
2010 AASHTO LRFD Bridge Design Specifications and 2010  
Interim Revisions

Design Loading:  
 Vehicular = HL-93 minus lane load, Earth = 120 lb/cf  
 Equivalent Fluid Pressure = 30 lb/cf (min.), 60 lb/cf (max.)

Design Unit Stresses:  
Class B-1 Concrete (Box Culvert)  $f'_c = 4,000$  psi  
Reinforcing Steel (Grade 60)  $f_y = 60,000$  psi

Standard Plans:  
703.37, 703.84, 703.86, 703.87 (4)

**Miscellaneous:**  
MoDOT Construction personnel will indicate the type of box culvert constructed:  
☐ Precast Concrete Box used  
☐ Cast-in-Place Concrete Box used

When alternate precast concrete box sections are used, the minimum distance from inside face of headwalls to precast sections measured along the shortest wall shall be 3 feet. Reinforcement and dimensions for wings and headwalls shall be in accordance with Missouri Standard Plans.

Channel bottom shall be graded within the right of way for transition of channel bed to culvert openings. Channel banks shall be tapered to match culvert openings. (Roadway Item)

**Traffic Handling:**  
Structure to be closed during construction. Traffic to be maintained on during construction. See roadway plans for traffic control.

B.M.

CULVERT-BRIDGE: ROUTE \* OVER \*

ROUTE \* FROM \* TO \*  
ABOUT \* MILES \* OF \*  
TIE STA. \_\_\_\_\_

Designed  
Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. 1 of

DATE PREPARED	
10/13/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	9

JOB NO.


CONTRACT ID.

PROJECT NO.

BRIDGE NO.

## DESCRIPTION

DATE \_\_\_\_\_

MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

Pipes With Same Diameter

XX" Pipe Inlet Data		
Station	Offset	F.L. Elev.
xx+xx.xx	xx.xx' XX	xxx.xx
xx+xx.xx	xx.xx' XX	xxx.xx
xx+xx.xx	xx.xx' XX	xxx.xx

Inlets Sized for Elevation A-A  
(Pipe Diameter/Culvert HT)

0.1

0.2

0.3

0.4

0.5

0.6

0.7

0.8

0.9

Ex: Use 0.5 detail for 36" pipe into a 6' tall culvert.

Pipes With Different Diameters

Pipe Inlet Data			
Station	Offset	Dia.	F.L. Elev.
xx+xx.xx	xx.xx' XX	xx"	xxx.xx
xx+xx.xx	xx.xx' XX	xx"	xxx.xx
xx+xx.xx	xx.xx' XX	xx"	xxx.xx

Supplemental Reinforcement Table (Nonstandard culverts with only one design fill height) ⑤

Top Slab Reinforcement											Bottom Slab Reinforcement										Wall Reinforcement							
A1 Bars		J3 Bars				H1 Bars				H2 Bars			A2 Bars		J4 Bars				H3 Bars				B1 Bars		B2 Bars			
Sz.	Spa.	Sz.	Spa.	C1	K2	Sz.	Spa.	C5	Q8	Sz.	Spa.	C6	Q9	Sz.	Spa.	Sz.	Spa.	C4	K3	Sz.	Spa.	C7	Q10	Sz.	Spa.	Sz.	Spa.	G1
x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x
Substitute table for tables shown on Standard Plan 703.87																												

Supplemental Pipe Inlet Details ④

Standard Drawing Guidance  
(Do not show on plans. Turn off the Bridge Construction Level to hide)


Some details have been grouped together to allow easy substitution with alternate details. To edit grouped details, select them and press <Ctrl> U.

- ① Ahead station is shown for streams flowing left to right. Arrow must be flipped for streams that flow right to left.
- ② Modify Estimated Quantities as required. Don't leave blank rows but leave space between Estimated Quantities and General Notes for at least one pay item to be added during construction. See Alternate Details for culvert extensions, or if five items are required.
- ③ Add any required transverse joints proportionally spaced along the barrel. Label units and add actual lengths of units along the barrel.
- ④ Insert STD 703.60 when pipe inlets are required. Add pipe inlets to Plan of Layout Dimensions at appropriate locations and to Elevation A-A if visible from elevation. Add inlet data using notes where space allows, or use tables.
- ⑤ For nonstandard culverts with only one design fill height, add supplemental reinforcement table.
- ⑥ No need to revise General Elevation A-A for dual roadways. In Fill Heights table add a lane designation after  $\text{C}$  Rdwy and insert another row for the other lane.

\*\*\* VARIABLE DESIGN FILL HEIGHTS \*\*\*

- a Select and delete the details grouped with the Fill Heights table. Select and move the alternate grouped details to drawing.
- b Place "See Member Thickness table" in the Equation column and place "Varies" in the Dim. column. If Dimension F varies, place "Varies" in the Dim. column.
- c Remove blank rows. End units may have different design fill heights but both units need to have the same member thicknesses.
- d This portion of table required when design fill height exceeds limits of the standard plans or when culvert cell height or span is not standard. If only a portion of the units are nonstandard, fill out entire table using the values from the standard table where applicable. Omit if not required.

Alternate Plan of Transverse Joints





If any part of the barrel is exposed, the roadway fill shall be warped to provide 12 inches minimum cover. (Roadway Item)



Construction joint key not shown for clarity, see standard plans for details.

If unsuitable material is encountered, excavation of unsuitable material and furnishing and placing of granular backfill shall be in accordance with Sec 206.


BXC09\_tri\_ra\_str

Guidance & Alternate Details (2 of 2)

Corresponds to the border of the standard drawing for ease in moving alternate details (Snap to corner)



Alternate Details for Multiple Design Fill Heights (a)



Remove if not applicable.

Fill Heights			
C Rdwy at C Culvert	=		ft
Design (Units 1 & )	=		ft
Design (Units & )	=		ft
Design (Units & )	=		ft

Dimensions are based on end units, except AA is based on Unit . Fill heights are measured from the top of top slab to the top of earth fill or roadway.

Estimated Quantities				Final
Class 4 Excavation	cu. yard	x		
Temporary Shoring	lump sum	1		
Partial Removal of Culvert-Bridge Concrete	lump sum	1		
Class B-1 Concrete (Culverts-Bridge)	cu. yard	x		
Reinforcing Steel (Culverts-Bridge)	pound	x		

(2)

Alternate Estimated Quantities for Culvert Extensions or when Five Items are Required


Unit No.	Unit Length	Member Thickness					Top Slab Reinforcement												Bottom Slab Reinforcement										Wall Reinforcement					
							A1 Bars				J3 Bars				H1 Bars				H2 Bars				A2 Bars		J4 Bars				H3 Bars				B1 Bars	
		TS	BS	TX	TI	F	Sz.	Spa.	Sz.	Spa.	C1	K2	Sz.	Spa.	C5	Q8	Sz.	Spa.	C6	Q9	Sz.	Spa.	Sz.	Spa.	C4	K3	Sz.	Spa.	C7	Q10	Sz.	Spa.	Sz.	Spa.
x	x	x	x	x	x	' -	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x
x	x	x	x	x	x	' -	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x
x	x	x	x	x	x	' -	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x

Substitute table for tables shown on Standard Plan 703.87



3( 'x ' ) CONCRETE BOX CULVERT



SEC/SUR \* TWP \* RGE \*



Construction joint key not shown for clarity, see standard plans for details.

If any part of the barrel is exposed, the roadway fill shall be warped to provide 12 inches minimum cover. (Roadway Item)

If unsuitable material is encountered, excavation of unsuitable material and furnishing and placing of granular backfill shall be in accordance with Sec 206.



Layout Dimensions								
Var.	Equation	Dim.	Var.	Equation	Dim.	Var.	Equation	Dim.
S	- - -	x	C	- - -	x	Q	$TX(\cos 20^\circ)$	x
HT	- - -	x	D	$R + M + N + 20"$	x	R	$P(\cos 20^\circ)$	x
TS	- - -	x	E	$G + 23"$	x	U	$(R + M)(\tan 20^\circ)$	x
BS	- - -	x	F	$3S + 2TX + 2TI$	x	V	$HT + TS - 12"$	x
TX	- - -	x	G	$2V$	x	W	$2A + B + C + D + E$	x
TI	- - -	x	M	$N(\cos 20^\circ)$	x	Y	$TX(\sin 20^\circ)$	x
A	- - -	x	N	$3" + TX(\tan 10^\circ)$	x	KK	$3S/2 + TI + U$	x
B	- - -	x	P	$2V(\sec 20^\circ)$	x	TW	$\text{Max}\{3' - 4" \text{ or } (BS + 12")\}$	x

Hydrologic Data
Drainage Area = ___ mi <sup>2</sup>
Design Flood Frequency = ___ years
Design Flood Discharge = ___ cfs
Design Flood (D.F.) Elevation = _____
Base Flood (100-year)
Base Flood Elevation = _____
Base Flood Discharge = ___ cfs
Estimated Backwater = ___ ft
Outlet Velocity = __ ft/s
Roadway Overtopping
Overtopping Flood Discharge = ___ cfs
Overtopping Flood Frequency = ___ years
Flood Elevation =

Elevations	
Upstream (Elev. 1) =	
Downstream (Elev. 2) =	
Pr. Gr. at Tie Sta. =	

6	Fill Heights
℄ Rdwy at ℄ Culvert =	ft
Design (All units) =	ft

Estimated Quantities			Final
Class 4 Excavation	cu. yard	x	
Removal of Bridges	lump sum	1	
Class B-1 Concrete (Culverts-Bridge)	cu. yard	x	
Reinforcing Steel (Culverts-Bridge)	pound	x	

General Notes:

Design Specifications:  
2010 AASHTO LRFD Bridge Design Specifications and 2010  
Interim Revisions

Design Loading:  
 Vehicular = HL-93 minus lane load, Earth = 120 lb/cf  
 Equivalent Fluid Pressure = 30 lb/cf (min.), 60 lb/cf (max.)

Design Unit Stresses:  
Class B-1 Concrete (Box Culvert)  $f'_c = 4,000$  psi  
Reinforcing Steel (Grade 60)  $f_y = 60,000$  psi

Standard Plans:  
703.37, 703.81, 703.86, 703.87 (4)

Miscellaneous:  
 MoDOT Construction personnel will indicate the type of box culvert constructed:  
☐ Precast Concrete Box used  
☐ Cast-in-Place Concrete Box used

When alternate precast concrete box sections are used, the minimum distance from inside face of headwalls to precast sections measured along the shortest wall shall be 3 feet. Reinforcement and dimensions for wings and headwalls shall be in accordance with Missouri Standard Plans.

Channel bottom shall be graded within the right of way for transition of channel bed to culvert openings. Channel banks shall be tapered to match culvert openings. (Roadway Item)

Traffic Handling:  
Structure to be closed during construction. Traffic to be  
 maintained on during construction. See roadway  
 plans for traffic control.

B.M.

CULVERT-BRIDGE: ROUTE \* OVER \*

ROUTE \* FROM \* TO \*  
ABOUT \* MILES \* OF \*  
TIE STA. \_\_\_\_\_

Designed  
Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. 1 of

DATE PREPARED	
10/13/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	10

JOB NO.
CONTRACT ID.
PROJECT NO.
BRIDGE NO.

DESCRIPTION

DATE \_\_\_\_\_

MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

103 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

Pipes With Same Diameter

XX" Pipe Inlet Data		
Station	Offset	F.L. Elev.
xx+xx.xx	xx.xx' XX	xxx.xx
xx+xx.xx	xx.xx' XX	xxx.xx
xx+xx.xx	xx.xx' XX	xxx.xx

Inlets Sized for Elevation A-A  
(Pipe Diameter/Culvert HT)

0.1	0.2	0.3	0.4	0.5
0.6	0.7	0.8	0.9	

Ex: Use 0.5 detail for 36" pipe into a 6' tall culvert.

Pipes With Different Diameters

Pipe Inlet Data			
Station	Offset	Dia.	F.L. Elev.
xx+xx.xx	xx.xx' XX	xx"	xxx.xx
xx+xx.xx	xx.xx' XX	xx"	xxx.xx
xx+xx.xx	xx.xx' XX	xx"	xxx.xx

Supplemental Pipe Inlet Details ④

Supplemental Reinforcement Table (Nonstandard culverts with only one design fill height) ⑤

Top Slab Reinforcement												Bottom Slab Reinforcement								Wall Reinforcement								
A1 Bars		J3 Bars				H1 Bars				H2 Bars				A2 Bars		J4 Bars				H3 Bars				B1 Bars		B2 Bars		
Sz.	Spa.	Sz.	Spa.	C1	K2	Sz.	Spa.	C5	Q8	Sz.	Spa.	C6	Q9	Sz.	Spa.	Sz.	Spa.	C4	K3	Sz.	Spa.	C7	Q10	Sz.	Spa.	Sz.	Spa.	G1
x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x


Substitute table for tables shown on Standard Plan 703.87

Standard Drawing Guidance  
(Do not show on plans. Turn off the Bridge Construction level to hide)

Some details have been grouped together to allow easy substitution with alternate details. To edit grouped details, select them and press <Ctrl> U.

- ① Ahead station is shown for streams flowing left to right. Arrow must be flipped for streams that flow right to left.
- ② Modify Estimated Quantities as required. Don't leave blank rows but leave space between Estimated Quantities and General Notes for at least one pay item to be added during construction. See Alternate Details for culvert extensions, or if five items are required.
- ③ Add any required transverse joints proportionally spaced along the barrel. Label units and add actual lengths of units along the barrel.
- ④ Insert STD 703.60 when pipe inlets are required. Add pipe inlets to Plan of Layout Dimensions at appropriate locations and to Elevation A-A if visible from elevation. Add inlet data using notes where space allows, or use tables.
- ⑤ For nonstandard culverts with only one design fill height, add supplemental reinforcement table.
- ⑥ No need to revise General Elevation A-A for dual roadways. In Fill Heights table add a lane designation after  $\text{C Rdwy}$  and insert another row for the other lane.

- \*\*\* VARIABLE DESIGN FILL HEIGHTS \*\*\*
- a) Select and delete the details grouped with the Fill Heights table. Select and move the alternate grouped details to drawing.
- b) Place "See Member Thickness table" in the Equation column and place "Varies" in the Dim. column. If Dimension F varies, place "Varies" in the Dim. column.
- c) Remove blank rows. End units may have different design fill heights but both units need to have the same member thicknesses.
- d) This portion of table required when design fill height exceeds limits of the standard plans or when culvert cell height or span is not standard. If only a portion of the units are nonstandard, fill out entire table using the values from the standard table where applicable. Omit if not required.




If any part of the barrel is exposed, the roadway fill shall be warped to provide 12 inches minimum cover. (Roadway Item)

Construction joint key not shown for clarity, see standard plans for details.

If unsuitable material is encountered, excavation of unsuitable material and furnishing and placing of granular backfill shall be in accordance with Sec 206.

BXC10\_tri\_sq\_fla      Guidance & Alternate Details (2 of 2)

Corresponds to the border of the standard drawing for ease in moving alternate details (Snap to corner)



Alternate Details for Multiple Design Fill Heights (a)


Fill Heights		
℄ Rdwy at ℄ Culvert =		ft
Design (Units 1 & ) =		ft
Design (Units & ) =		ft
Design (Units & ) =		ft

Dimensions are based on end units, except AA is based on Unit . Fill heights are measured from the top of top slab to the top of earth fill or roadway.

Estimated Quantities				Final
Class 4 Excavation	cu. yard	x		
Temporary Shoring	lump sum	1		
Partial Removal of Culvert-Bridge Concrete	lump sum	1		
Class B-1 Concrete (Culverts-Bridge)	cu. yard	x		
Reinforcing Steel (Culverts-Bridge)	pound	x		


(2)

Alternate Estimated Quantities for Culvert Extensions or when Five Items are Required



PLAN OF TRANSVERSE JOINTS AND STAGE CONSTRUCTION

Remove if not applicable.




PLAN OF LAYOUT DIMENSIONS

Unit No.	Unit Length	Member Thickness					Top Slab Reinforcement												Bottom Slab Reinforcement										Wall Reinforcement							
							A1 Bars				J3 Bars				H1 Bars				H2 Bars				A2 Bars		J4 Bars				H3 Bars				B1 Bars		B2 Bars	
		TS	BS	TX	TI	F	Sz.	Spa.	Sz.	Spa.	C1	K2	Sz.	Spa.	C5	Q8	Sz.	Spa.	C6	Q9	Sz.	Spa.	Sz.	Spa.	C4	K3	Sz.	Spa.	C7	Q10	Sz.	Spa.	Sz.	Spa.	G1	
x	x	x	x	x	x	' - "	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x
x	x	x	x	x	x	' - "	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x
x	x	x	x	x	x	' - "	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x

Substitute table for tables shown on Standard Plan 703.87

3 ( 'x ' ) CONCRETE BOX CULVERT


SEC/SUR \* TWP \* RGE \*



Construction joint key not shown for clarity, see standard plans for details.

If any part of the barrel is exposed, the roadway fill shall be warped to provide 12 inches minimum cover. (Roadway Item)

If unsuitable material is encountered, excavation of unsuitable material and furnishing and placing of granular backfill shall be in accordance with Sec 206.



PLAN OF LAYOUT DIMENSIONS

Note: This drawing is not to scale. Follow dimensions.

Layout Dimensions							
Var.	Equation	Dim.	Var.	Equation	Dim.	Var.	Equation
S	- - -	x	K	$(3S/2 + TI)(\sec Z)$	x	BB	$(A + B)(\sec Z)$
HT	- - -	x	L	$AA + BB + CC + DD + EE$	x	CC	$(A + C)(\sec Z)$
TS	- - -	x	M	$N(\cos 20^\circ)$	x	DD	$R + M + N + 20"$
BS	- - -	x	N	$3" + TX(\tan 10^\circ)$	x	EE	$E(\sec Z)$
TX	- - -	x	O	$I + YY$	x	HH	$20"(\sec Z)$
TI	- - -	x	P	$2V[\sec(Z + 20^\circ)]$	x	II	$20"(\cos Z)$
A	- - -	x	Q	$TX(\cos 20^\circ)$	x	KK	$3S/2 + TI + U$
B	- - -	x	R	$P(\cos 20^\circ)$	x	LL	$(AA + BB + DD)(\cos Z)$
C	- - -	x	T	$G(\sec Z)$	x	MM	$3"[\cos Z + \cos(Z - 20^\circ)]$
D	$II + MM + RR + TT$	x	U	$(R + M)(\tan 20^\circ)$	x	QQ	$TX(\cos Z)$
E	$G + O + 20"$	x	V	$HT + TS - 12"$	x	RR	$P[\cos(Z - 20^\circ)]$
F	$3S + 2TX + 2TI$	x	W	$2A + B + C + D + E + SS$	x	SS	$F(\sin Z)$
G	$2V$	x	X	$3" + TX(\tan Z)$	x	TT	$TX[\sin(20^\circ - Z)]$
H	$(A + C + E)(\tan Z)$	x	Y	$TX(\sin 20^\circ)$	x	YY	$TX(\sin Z)$
I	$3"(\cos Z)$	x	Z	Skew Angle	x	TW	$\text{Max}\{3'-4" \text{ or } (BS + 12")\}$
J	$(AA + BB + DD)(\sin Z)$	x	AA	$F(\tan Z)/2$	x		

Hydrologic Data
Drainage Area = ___ mi <sup>2</sup>
Design Flood Frequency = ___ years
Design Flood Discharge = ___ cfs
Design Flood (D.F.) Elevation = _____
Base Flood (100-year)
Base Flood Elevation = _____
Base Flood Discharge = ___ cfs
Estimated Backwater = __ ft
Outlet Velocity = __ ft/s
Roadway Overtopping
Overtopping Flood Discharge = ___ cfs
Overtopping Flood Frequency = ___ years
_____ Flood Elevation = _____

Elevations
Upstream (Elev. 1) = _____
Downstream (Elev. 2) = _____
Pr. Gr. at Tie Sta. = _____

Fill Heights
Culvert at Culvert = _____ ft
Design (All units) = _____ ft

Dimensions are based on end units. Fill heights are measured from the top of top slab to the top of earth fill or roadway.

Estimated Quantities			Final
Class 4 Excavation	cu. yard	x	
Removal of Bridges	lump sum	1	
Class B-1 Concrete (Culverts-Bridge)	cu. yard	x	
Reinforcing Steel (Culverts-Bridge)	pound	x	

General Notes:

Design Specifications: 2010 AASHTO LRFD Bridge Design Specifications and 2010 Interim Revisions

Design Loading: Vehicular = HL-93 minus lane load, Earth = 120 lb/cf Equivalent Fluid Pressure = 30 lb/cf (min.), 60 lb/cf (max.)

Design Unit Stresses: Class B-1 Concrete (Box Culvert) f'c = 4,000 psi Reinforcing Steel (Grade 60) fy = 60,000 psi

Standard Plans: 703.37, 703.83, 703.86, 703.87

Miscellaneous: MoDOT Construction personnel will indicate the type of box culvert constructed: ☐ Precast Concrete Box used ☐ Cast-in-Place Concrete Box used

When alternate precast concrete box sections are used, the minimum distance from inside face of headwalls to precast sections measured along the shortest wall shall be 3 feet. Reinforcement and dimensions for wings and headwalls shall be in accordance with Missouri Standard Plans.

Channel bottom shall be graded within the right of way for transition of channel bed to culvert openings. Channel banks shall be tapered to match culvert openings. (Roadway Item)

Traffic Handling: Structure to be closed during construction. Traffic to be maintained on during construction. See roadway plans for traffic control.

B.M.

CULVERT-BRIDGE: ROUTE \* OVER \*

ROUTE \* FROM \* TO \*  
ABOUT \* MILES \* OF \*  
TIE STA. \_\_\_\_\_

Designed  
Detailed  
Checked

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION



105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

Pipes With Same Diameter

XX" Pipe Inlet Data		
Station	Offset	F.L. Elev.
xx+xx.xx	xx.xx' XX	xxx.xx
xx+xx.xx	xx.xx' XX	xxx.xx
xx+xx.xx	xx.xx' XX	xxx.xx

Inlets Sized for Elevation A-A  
(Pipe Diameter/Culvert HT)

0.1	0.2	0.3	0.4	0.5
0.6	0.7	0.8	0.9	

Ex: Use 0.5 detail for 36" pipe into a 6' tall culvert.

Pipes With Different Diameters

Pipe Inlet Data			
Station	Offset	Dia.	F.L. Elev.
xx+xx.xx	xx.xx' XX	xx"	xxx.xx
xx+xx.xx	xx.xx' XX	xx"	xxx.xx
xx+xx.xx	xx.xx' XX	xx"	xxx.xx

Supplemental Pipe Inlet Details ④

Supplemental Reinforcement Table (Nonstandard culverts with only one design fill height) ⑤

Top Slab Reinforcement										Bottom Slab Reinforcement										Wall Reinforcement								
A1 Bars		J3 Bars				H1 Bars				H2 Bars		A2 Bars		J4 Bars				H3 Bars		B1 Bars	B2 Bars							
Sz.	Spa.	Sz.	Spa.	C1	K2	Sz.	Spa.	C5	Q8	Sz.	Spa.	C6	Q9	Sz.	Spa.	Sz.	Spa.	C4	K3	Sz.	Spa.	C7	Q10	Sz.	Spa.	Sz.	Spa.	G1
x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x

Substitute table for tables shown on Standard Plan 703.87


Standard Drawing Guidance  
(Do not show on plans. Turn off the Bridge Construction Level to hide)

Some details have been grouped together to allow easy substitution with alternate details. To edit grouped details, select them and press <Ctrl> U.

- ① Ahead station is shown for streams flowing left to right. Arrow must be flipped for streams that flow right to left.
- ② Modify Estimated Quantities as required. Don't leave blank rows but leave space between Estimated Quantities and General Notes for at least one pay item to be added during construction. See Alternate Details for culvert extensions, or if five items are required.
- ③ Add any required transverse joints proportionally spaced along the barrel. Label units and add actual lengths of units along the barrel.
- ④ Insert STD 703.60 when pipe inlets are required. Add pipe inlets to Plan of Layout Dimensions at appropriate locations and to Elevation A-A if visible from elevation. Add inlet data using notes where space allows, or use tables.
- ⑤ For nonstandard culverts with only one design fill height, add supplemental reinforcement table.
- ⑥ No need to revise General Elevation A-A for dual roadways. In Fill Heights table add a lane designation after  $\varnothing$  Rdwy and insert another row for the other lane.
- ⑦ For skews 20 degrees or more, remove Detail C, remove TT from equation for D and place "N/A" in the Dim. column of Dimension TT. Will first need to separate Detail C from Plan by selecting and pressing <Ctrl> U.

\*\*\* VARIABLE DESIGN FILL HEIGHTS \*\*\*

- a Select and delete the details grouped with the Fill Heights table. Select and move the alternate grouped details to drawing.
- b Place "See Member Thickness table" in the Equation column and place "Varies" in the Dim. column. If Dimension F varies, place "Varies" in the Dim. column.
- c Remove blank rows. End units may have different design fill heights but both units need to have the same member thicknesses.
- d This portion of table required when design fill height exceeds limits of the standard plans or when culvert cell height or span is not standard. If only a portion of the units are nonstandard, fill out entire table using the values from the standard table where applicable. Omit if not required.





If any part of the barrel is exposed, the roadway fill shall be warped to provide 12 inches minimum cover. (Roadway Item)

Construction joint key not shown for clarity, see standard plans for details.

If unsuitable material is encountered, excavation of unsuitable material and furnishing and placing of granular backfill shall be in accordance with Sec 206.

BXC11\_tri\_la fla      Guidance & Alternate Details (2 of 2)

Corresponds to the border of the standard drawing for ease in moving alternate details (Snap to corner)



Alternate Details for Multiple Design Fill Heights (a)


Fill Heights		
Centerline Rdwy at Centerline Culvert	=	ft
Design (Units 1 & )	=	ft
Design (Units & )	=	ft
Design (Units & )	=	ft

Dimensions are based on end units, except AA is based on Unit . Fill heights are measured from the top of top slab to the top of earth fill or roadway.

Estimated Quantities				Final
Class 4 Excavation	cu. yard	x		
Temporary Shoring	lump sum	1		
Partial Removal of Culvert-Bridge Concrete	lump sum	1		
Class B-1 Concrete (Culverts-Bridge)	cu. yard	x		
Reinforcing Steel (Culverts-Bridge)	pound	x		

(2)

Alternate Estimated Quantities for Culvert Extensions or when Five Items are Required




Remove if not applicable.

		c		d		LOCATION SKETCH																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											
Unit No.	Unit Length	Member Thickness					Top Slab Reinforcement												Bottom Slab Reinforcement										Wall Reinforcement																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
		TS	BS	TX	TI	F	A1 Bars		J3 Bars				H1 Bars				H2 Bars				A2 Bars		J4 Bars				H3 Bars				B1 Bars	B2 Bars																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	
		Sz.	Spa.	Sz.	Spa.	C1	K2	Sz.	Spa.	C5	Q8	Sz.	Spa.	C6	Q9	Sz.	Spa.	Sz.	Spa.	C4	K3	Sz.	Spa.	C7	Q10	Sz.	Spa.	Sz.	Spa.	G1																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																			
x	x	x	x	x	x	' - "	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x



### 3 ( ' x ' ) CONCRETE BOX CULVERT

SEC / SUR	*	TWP	*	RGE	*
-----------	---	-----	---	-----	---



Construction joint key not shown for clarity, see standard plans for details.

If any part of the barrel is exposed, the roadway fill shall be warped to provide 12 inches minimum cover. (Roadway Item)

If unsuitable material is encountered, excavation of unsuitable material and furnishing and placing of granular backfill shall be in accordance with Sec 206.

Layout Dimensions								
Var.	Equation	Dim.	Var.	Equation	Dim.	Var.	Equation	Dim.
S	- - -	x	K	$(3S/2 + T1)(\sec Z)$	x	BB	$(A + B)(\sec Z)$	x
HT	- - -	x	L	$AA + BB + CC + DD + EE$	x	CC	$(A + C)(\sec Z)$	x
TS	- - -	x	M	$N(\cos 20^\circ)$	x	DD	$R + M + N + 20"$	x
BS	- - -	x	N	$3" + TX(\tan 10^\circ)$	x	EE	$E(\sec Z)$	x
TX	- - -	x	O	$I + YY$	x	HH	$20"(\sec Z)$	x
TI	- - -	x	P	$2V[\sec(Z + 20^\circ)]$	x	II	$20"(\cos Z)$	x
A	- - -	x	Q	$TX(\cos 20^\circ)$	x	KK	$3S/2 + TI + U$	x
B	- - -	x	R	$P(\cos 20^\circ)$	x	LL	$(AA + BB + DD)(\cos Z)$	x
C	- - -	x	T	$G(\sec Z)$	x	MM	$3"[\cos Z + \cos(Z - 20^\circ)]$	x
D	$II + MM + RR + TT$	x	U	$(R + M)(\tan 20^\circ)$	x	QQ	$TX(\cos Z)$	x
E	$G + O + 20"$	x	V	$HT + TS - 12"$	x	RR	$P[\cos(Z - 20^\circ)]$	x
F	$3S + 2TX + 2TI$	x	W	$2A + B + C + D + E + SS$	x	SS	$F(\sin Z)$	x
G	$2V$	x	X	$3" + TX(\tan Z)$	x	TT	$TX[\sin(20^\circ - Z)]$	x
H	$(A + C + E)(\tan Z)$	x	Y	$TX(\sin 20^\circ)$	x	YY	$TX(\sin Z)$	x
I	$3"(\cos Z)$	x	Z	Skew Angle	x	TW	$\text{Max}\{3'-4" \text{ or } (BS + 12")\}$	x
J	$(AA + BB + DD)(\sin Z)$	x	AA	$F(\tan Z)/2$	x			

Hydrologic Data
Drainage Area = ___ mi <sup>2</sup>
Design Flood Frequency = ___ years
Design Flood Discharge = ___ cfs
Design Flood (D.F.) Elevation = _____
Base Flood (100-year)
Base Flood Elevation = _____
Base Flood Discharge = _____ cfs
Estimated Backwater = ___ ft
Outlet Velocity = __ ft/s
Roadway Overtopping
Overtopping Flood Discharge = ___ cfs
Overtopping Flood Frequency = ___ years
_____ Flood Elevation = _____

Elevations	
Upstream (Elev. 1) =	
Downstream (Elev. 2) =	
Pr. Gr. at Tie Sta. =	

6 Fill Heights  
 @ Rdwy at @ Culvert = ft  
 Design (All units) = ft

Dimensions are based on end units.  
Fill heights are measured from the top of top slab to the top of  
earth fill or roadway.

Estimated Quantities			Final
Class 4 Excavation	cu. yard	x	
Removal of Bridges	lump sum	1	
Class B-1 Concrete (Culverts-Bridge)	cu. yard	x	
Reinforcing Steel (Culverts-Bridge)	pound	x	

General Notes:

**Design Specifications:**  
2010 AASHTO LRFD Bridge Design Specifications and 2010  
Interim Revisions

Design Loading:  
 Vehicular = HL-93 minus lane load, Earth = 120 lb/cf  
 Equivalent Fluid Pressure = 30 lb/cf (min.), 60 lb/cf (max.)

**Design Unit Stresses:**  
Class B-1 Concrete (Box Culvert)  $f'_c = 4,000$  psi  
Reinforcing Steel (Grade 60)  $f_y = 60,000$  psi

Standard Plans:

Miscellaneous:  
MoDOT Construction personnel will indicate the type of box culvert constructed:  
☐ Precast Concrete Box used  
☐ Cast-in-Place Concrete Box used

When alternate precast concrete box sections are used, the minimum distance from inside face of headwalls to precast sections measured along the shortest wall shall be 3 feet. Reinforcement and dimensions for wings and headwalls shall be in accordance with Missouri Standard Plans.


Channel bottom shall be graded within the right of way for transition of channel bed to culvert openings. Channel banks shall be tapered to match culvert openings. (Roadway Item)

**Traffic Handling:**  
Structure to be closed during construction. Traffic to be maintained on during construction. See roadway plans for traffic control.

B.M.

CULVERT-BRIDGE: ROUTE \* OVER \*

ROUTE \* FROM \* TO \*  
ABOUT \* MILES \* OF \*  
TIE STA.



Designed  
Detailed  
Checked


Note: This drawing is not to scale. Follow dimensions.

Sheet No. 1 of

LOCATION SKETCH

## DESCRIPTION

DATE \_\_\_\_\_

MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)



Pipes With Same Diameter

XX" Pipe Inlet Data		
Station	Offset	F.L. Elev.
xx+xx.xx	xx.xx' XX	xxx.xx
xx+xx.xx	xx.xx' XX	xxx.xx
xx+xx.xx	xx.xx' XX	xxx.xx

Pipes With Different Diameters

Pipe Inlet Data			
Station	Offset	Dia.	F.L. Elev.
xx+xx.xx	xx.xx' XX	xx"	xxx.xx
xx+xx.xx	xx.xx' XX	xx"	xxx.xx
xx+xx.xx	xx.xx' XX	xx"	xxx.xx

Inlets Sized for Elevation A-A  
(Pipe Diameter/Culvert HT)

0.1	0.2	0.3	0.4	0.5
0.6	0.7	0.8	0.9	

Ex: Use 0.5 detail for 36" pipe into a 6' tall culvert.

Supplemental Pipe Inlet Details ④

Supplemental Reinforcement Table (Nonstandard culverts with only one design fill height) ⑤

Top Slab Reinforcement														Bottom Slab Reinforcement										Wall Reinforcement				
A1 Bars		J3 Bars				H1 Bars				H2 Bars				A2 Bars		J4 Bars				H3 Bars				B1 Bars		B2 Bars		
Sz.	Spa.	Sz.	Spa.	C1	K2	Sz.	Spa.	C5	Q8	Sz.	Spa.	C6	Q9	Sz.	Spa.	Sz.	Spa.	C4	K3	Sz.	Spa.	C7	Q10	Sz.	Spa.	Sz.	Spa.	G1
x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x

Substitute table for tables shown on Standard Plan 703.87


Standard Drawing Guidance  
(Do not show on plans. Turn off the Bridge Construction level to hide)

Some details have been grouped together to allow easy substitution with alternate details. To edit grouped details, select them and press <Ctrl> U.

- ① Ahead station is shown for streams flowing left to right. Arrow must be flipped for streams that flow right to left.
- ② Modify Estimated Quantities as required. Don't leave blank rows but leave space between Estimated Quantities and General Notes for at least one pay item to be added during construction. See Alternate Details for culvert extensions, or if five items are required.
- ③ Add any required transverse joints proportionally spaced along the barrel. Label units and add actual lengths of units along the barrel.
- ④ Insert STD 703.60 when pipe inlets are required. Add pipe inlets to Plan of Layout Dimensions at appropriate locations and to Elevation A-A if visible from elevation. Add inlet data using notes where space allows, or use tables.
- ⑤ For nonstandard culverts with only one design fill height, add supplemental reinforcement table.
- ⑥ No need to revise General Elevation A-A for dual roadways. In Fill Heights table add a lane designation after  $\varnothing$  Rdwy and insert another row for the other lane.
- ⑦ For skews 20 degrees or more, remove Detail C, remove TT from equation for D and place "N/A" in the Dim. column of Dimension TT. Will first need to separate Detail C from Plan by selecting and pressing <Ctrl> U.

\*\*\* VARIABLE DESIGN FILL HEIGHTS \*\*\*

- a Select and delete the details grouped with the Fill Heights table. Select and move the alternate grouped details to drawing.
- b Place "See Member Thickness table" in the Equation column and place "Varies" in the Dim. column. If Dimension F varies, place "Varies" in the Dim. column.
- c Remove blank rows. End units may have different design fill heights but both units need to have the same member thicknesses.
- d This portion of table required when design fill height exceeds limits of the standard plans or when culvert cell height or span is not standard. If only a portion of the units are nonstandard, fill out entire table using the values from the standard table where applicable. Omit if not required.




If any part of the barrel is exposed, the roadway fill shall be warped to provide 12 inches minimum cover. (Roadway Item)

Construction joint key not shown for clarity, see standard plans for details.

If unsuitable material is encountered, excavation of unsuitable material and furnishing and placing of granular backfill shall be in accordance with Sec 206.

BXC12\_tri\_ra\_flg      Guidance & Alternate Details (2 of 2)

Corresponds to the border of the standard drawing for ease in moving alternate details (Snap to corner)



Alternate Details for Multiple Design Fill Heights (a)


Fill Heights		
℄ Rdwy at ℄ Culvert =		ft
Design (Units 1 & ) =		ft
Design (Units & ) =		ft
Design (Units & ) =		ft

Dimensions are based on end units, except AA is based on Unit . Fill heights are measured from the top of top slab to the top of earth fill or roadway.

Estimated Quantities			Final
Class 4 Excavation	cu. yard	x	
Temporary Shoring	lump sum	1	
Partial Removal of Culvert-Bridge Concrete	lump sum	1	
Class B-1 Concrete (Culverts-Bridge)	cu. yard	x	
Reinforcing Steel (Culverts-Bridge)	pound	x	

(2)

Alternate Estimated Quantities for Culvert Extensions or Required




Remove if not applicable.


Unit No.	Unit Length	Member Thickness					Top Slab Reinforcement										Bottom Slab Reinforcement										Wall Reinforcement		
							A1 Bars				J3 Bars			H1 Bars			H2 Bars			A2 Bars	J4 Bars			H3 Bars			B1 Bars	B2 Bars	
		TS	BS	TX	TI	F	Sz. Spa.	Sz. Spa.	C1	K2	Sz. Spa.	C5	Q8	Sz. Spa.	C6	Q9	Sz. Spa.	Sz. Spa.	C4	K3	Sz. Spa.	C7	Q10	Sz. Spa.	Sz. Spa.	G1			
x	x	x	x	x	x	' - "	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x		
x	x	x	x	x	x	' - "	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x		
x	x	x	x	x	x	' - "	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x	x		

Substitute table for tables shown on Standard Plan 703.87







DETAIL B



PART SECTION AT RAIL POST



SECTION A-A



THRIE BEAM OPTION

Standard Drawing Guidance (do not show on plans):

- Designed for AASHTO LFD.
- Not designed for AASHTO LRFD.
- Not crash tested.
- Comparable to TL-2 (NCHRP 350) deck-mounted (top) post and rail system: Texas T101, Texas Type 6.

Unchecked LRFD analysis shows:

- 0' Fill  
Guardrail (W-Beam): Design Requirements for TL-2  
5'-0" post spacing max  
Single Rail  
Grade 50 post and plate

Thrie-Beam: Design Requirements for TL-2  
6'-9" post spacing max  
Single Rail  
Grade 50 post and Plate

- 2' Fill  
Guardrail (W-Beam): Design Requirements for TL-2  
4'-0" post spacing max  
Double Nested  
Grade 50 post and plate

Thrie-Beam: Design Requirements for TL-2  
6'-0" post spacing max  
Double Nested  
Grade 50 post and Plate

Use this detail when required to connect rail post to culvert slabs greater than 9" thick or where culvert walls interfere with bolting through slab.

This sheet shows details for connecting guardrail post to culvert slab only.

Work with districts on type of guardrail required.

General Notes:

Furnishing and installing posts and guardrail on culvert as shown on this sheet will be considered completely covered by the contract unit price for Bridge Guardrail (W-Beam), Bridge Guardrail (Thrie Beam), other items.

Furnishing and installing posts and guardrail on culvert shall be in accordance with Sec 606 except as shown.

Rail posts shall be seated on elastomeric pads having the same dimensions as the post base plate and 1/16" thickness. Such pads may be any elastomeric material, plain or fibered, having a hardness (Durometer) of 50 or above, as certified by the manufacturer. Additional pads or half pads may be used in shimming for alignment. Post heights shown will increase by the thickness of the pad.

Posts and base plates shall be fabricated from ASTM A709 Grade 36 steel and galvanized.

Fabrication of structural steel shall be in accordance with Sec 1080.

Holes for ASTM A307 bolts may be drilled into the culvert.


See slab sheet for rail post spacing.

See Missouri Standard Plans drawing 606.00 for details not shown.

DATE PREPARED 10/13/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 14
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
MDOT 105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	







SWEDGE ANCHOR  
BOLT DETAIL


**GENERAL NOTES:**  
Anchor bolts for Type C bearings shall be 1"Ø ASTM F1554 Grade 55 swedged bolts, with no heads or nuts and shall extend 10" into the concrete. Swedging shall be 1" less than the extension into the concrete. Anchor bolts shall be set in the drilling holes or in the anchor bolt wells and grouted prior to the erection of steel. The top of anchor bolts shall be set approximately 1/4" below the top of bearing.

Anchor bolts shall be coated with a minimum of two coats of inorganic zinc primer to provide a total dry thickness of 4 mils minimum, 6 mils maximum, or galvanized in accordance with Sec 1081.


Weight of the anchor bolts for bearings are included in the weight of the Fabricated Structural Steel.

⌚ Indicates machine finish surface.

Shop drawings are not required for the lead plates and the preformed fabric pads.




SIDE VIEW



END VIEW

**TYPE C BEARINGS**

(Estimated Weight      pounds)

DATE PREPARED 10/13/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 1
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-273-6636)	



GENERAL NOTES:


Anchor bolts for Type D bearings shall be  $\varnothing$  ASTM F1554 Grade 55 swedged bolts and shall extend into the concrete with ASTM A563 Grade A Heavy Hex nuts. Actual manufacturer's certified mill test reports (chemical and mechanical) shall be provided. Use ASTM F436 hardened washers for the fixed bearings and no heavy hex nuts or hardened washers for the expansion bearings. Swedging shall be 1" less than extension into the concrete.

Anchor bolts, hardened washers and heavy hex nuts shall be coated with a minimum of two coats of inorganic zinc primer to provide a total dry film thickness of 4 mils minimum, 6 mils maximum, or galvanized in accordance with Sec 1081.


Weight of the anchor bolts, hardened washers and heavy hex nuts for bearings are included in the weight of the Fabricated Structural Steel.

☞ Indicates machine finish surface.

Shop drawings are not required for the lead plates and the preformed fabric pads.



TYPE D BEARINGS  
(Estimated Weight      pounds)




SWEDGE ANCHOR BOLTS DETAILS

(1)  $\frac{1}{8}$ " for  $\frac{3}{4}$ "Ø thru  $1\frac{1}{4}$ "Ø anchor bolts

$\frac{1}{8}$ " to  $\frac{1}{4}$ " for  $1\frac{3}{8}$ "Ø thru  $2\frac{1}{2}$ "Ø anchor bolts




Note: This drawing is not to scale. Follow dimensions.

Sheet No.      of

DATE PREPARED 10/13/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 2
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	














Stopper plates and straps shall be provided to prevent loss of support due to creeping of PTFE bearings. Payment for fabricating and installing the stopper plates and straps will be considered completely covered by the contract unit price for Type N PTFE Bearing.

The bottom face of the 1/8" stainless steel plate that is welded to the sole plate shall be lubricated with a lubricant that is approved by the bearing manufacturer.



Standard Drawing Guidance:  
(do not show on plans.)

- ① Use note H3.29.1 with Grade 50W steel.  
Use note H3.29.2 when steel superstructure is galvanized.  
(H3.29 shown)
- ② Remove underlined portion when steel superstructure is galvanized.

GENERAL NOTES:

Design coefficient of friction equals 0.06.

Anchor bolts shall be Ø ASTM F1554 Grade 55 swedged bolts and shall extend into the concrete with ASTM A563 Grade A Heavy Hex nuts. Actual manufacturer's certified mill test reports (chemical and mechanical) shall be provided. Swedging shall be 1" less than extension into the concrete.

Anchor bolts shall be at the centerline of slotted hole at 60°F. Bearing position shall be adjusted  $R$  for each 10° fall or rise in temperature at installation.

② Anchor bolts and heavy hex nuts shall be coated with a minimum of two coats of inorganic zinc primer to provide a total dry film thickness of 4 mils minimum, 6 mils maximum, or galvanized in accordance with Sec 1081.

Neoprene Elastomeric Pads shall be 70 Durometer.

① Structural steel for sole plate shall be ASTM A709 Grade and shall be coated with a minimum of two coats of inorganic zinc primer to provide a total dry film thickness of 4 mils minimum, 6 mils maximum. The stainless steel plate shall be protected from any coating.



Type N PTFE Bearings shall be in accordance with Sec 716.

PTFE surface shall be fabricated as a single piece. Splicing will not be permitted.

PTFE SLIDING BEARINGS																		
BENT NO.	A	B	C	D	E	F	G	H	J	K	L	M	N	P	Q	R	NUMBER OF SHIM PLATES *	NUMBER REQUIRED
* The required shim plate shall be placed between layers of elastomer and molded together to form an integral unit.																	TOTAL BEARINGS	

## TYPE N PTFE BEARINGS





[illegible]



## SWEDGE ANCHOR BOLT DETAILS

(1)  $\frac{1}{8}$ " for  $\frac{3}{4}$ " $\varnothing$  thru  $1\frac{1}{4}$ " $\varnothing$  anchor bolts

$\frac{1}{8}$ " to  $\frac{1}{4}$ " for  $1\frac{3}{8}$ "Ø thru  $2\frac{1}{2}$ "Ø anchor bolts



Standard Drawing Guidance:  
(do not show on plans.)

- ① Use note H3.49.1 with Grade 50W steel.  
Use note H3.49.2 when steel superstructure is galvanized.  
(H3.49 shown)
- ② Remove underlined portion when steel superstructure is galvanized.

GENERAL NOTES:

Anchor bolts shall be Ø ASTM F1554 Grade 55 swedged bolts and shall extend into the concrete with ASTM A563 Grade A Heavy Hex nuts. Actual manufacturer's certified mill test reports (chemical and mechanical) shall be provided. Swedging shall be 1" less than extension into the concrete.

- ② Anchor bolts and heavy hex nuts shall be coated with a minimum of two coats of inorganic zinc primer to provide a total dry film thickness of 4 mils minimum, 6 mils maximum, or galvanized in accordance with Sec 1081.

Neoprene Elastomeric Pads shall be Durometer.


Structural steel for sole plate shall be ASTM A709 Grade and shall be coated with a minimum of two coats of inorganic zinc primer to provide a total dry film thickness of 4 mils minimum, 6 mils maximum.

- ① Laminated Neoprene Bearing Pad Assembly shall be in accordance with Sec 716.


FIXED BEARINGS															
BENT NO.	A	B	C	D	F	G	J	K	L	M	N	P	Q	NUMBER OF SHIM PLATES *	NUMBER REQUIRED
* The required shim plate shall be placed between layers of elastomer and molded together to form an integral unit.														TOTAL BEARINGS	

## LAMINATED NEOPRENE BEARING PAD ASSEMBLY

[illegible]



DETAIL FOR 3/4"Ø THRU  
2 1/2"Ø ANCHOR BOLTS







OPTIONAL DETAIL FOR 1 3/8"Ø  
THRU 2 1/2"Ø ANCHOR BOLTS

## SWEDGE ANCHOR BOLT DETAILS

(1)  $\frac{1}{8}$ " for  $\frac{3}{4}$ " $\varnothing$  thru  $1\frac{1}{4}$ " $\varnothing$  anchor bolts

$\frac{1}{8}$ " to  $\frac{1}{4}$ " for  $1\frac{3}{8}$ "Ø thru  $2\frac{1}{2}$ "Ø anchor bolts



EXPANSION BEARINGS																	
BENT NO.	A	B	C	D	E	F	G	J	K	L	M	N	P	Q	R	NUMBER OF SHIM PLATES *	NUMBER REQUIRED
* The required shim plate shall be placed between layers of elastomeric and molded together to form an integral unit.																TOTAL BEARINGS	

\* The required shim plate shall be placed between layers of elastomeric and molded together to form an integral unit.

GENERAL NOTES:

Anchor bolts shall be Ø ASTM F1554 Grade 55 swedged bolts and shall extend into the concrete with ASTM A563 Grade A Heavy Hex nuts. Actual manufacturer's certified mill test reports (chemical and mechanical) shall be provided. Swedging shall be 1" less than extension into the concrete.

Anchor bolt shall be at the centerline of slotted hole at 60°F. Bearing position shall be adjusted **R** for each 10° fall or rise in temperature at installation.

Anchor bolts and heavy hex nuts shall be coated with a minimum of two coats of inorganic zinc primer to provide a total dry film thickness of 4 mils minimum, 6 mils maximum, or galvanized in accordance with Sec 1081.

Neoprene Elastomeric Pads shall be Durometer.

Structural steel for sole plate shall be ASTM A709 Grade \_\_\_\_\_ and shall be coated with a minimum of two coats of inorganic zinc primer to provide a total dry film thickness of 4 mils minimum, 6 mils maximum.

Laminated Neoprene Bearing Pad Assembly shall be in accordance with Sec 716.

## LAMINATED NEOPRENE BEARING PAD ASSEMBLY


[illegible]











[illegible]

SECTION THRU SAW CUT JOINT






PART ELEVATION OF CURB BLOCKOUT





SECTION A-A

SECTION B-B



Cost of removing existing end posts will be considered completely covered by the contract unit price for Curb Blockout.







3'-0" Curb Blockout  
These details are meant to be used as a starting point only. Modify as needed.

- ① Taper front face as gradually as possible, while maintaining 6" minimum thickness of blockout at the end of the existing parapet. 2'-9" maximum taper length.
  - ② Holes may be shifted 12" closer to the end (8" instead of 20") to avoid attaching a rail post to the top of backwall. All other dimensions and reinforcement remain the same.
- Longitudinal R bars shall extend 2'-7" minimum into new end post.

Notes:  
Work this sheet with Sheet No. .  
For details of resin anchors, see Sheet No. .  
Resin anchors shall be shifted or bent in field to clear one-inch diameter holes by at least 1/2 inch.

## CURB BLOCKOUT AT END BENTS



## DETAILS OF END POST AND GUARD RAIL ATTACHMENT

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.


Sheet No. of

DATE PREPARED 10/13/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 2


COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	

DESCRIPTION	DATE


MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)
--	--



ELEVATION SHOWING REINFORCEMENT  
(Right End Post at End Bent No. similar)




PLAN SHOWING REINFORCEMENT  
LEFT END POST AT END BENT NO. 1




PART ELEVATION SHOWING END POST  
CONCRETE REMOVAL

Cost of removing existing end posts will be considered completely covered by the contract unit price for Curb Blockout.



SECTION A-A



SECTION B-B

## 2'-8" Curb Blockout

These details are meant to be used as a starting point only. Modify as needed.

- ① Taper front face as gradually as possible, while maintaining 6" minimum thickness of blockout at the end of the existing parapet. 2'-9" maximum taper length.
- ② Holes may be shifted 12" closer to the end (8" instead of 20") to avoid attaching a rail post to the top of backwall. All other dimensions and reinforcement remain the same.

Longitudinal R bars shall extend 2'-7" minimum into new end post.


Detach unused border reference file before PDF request.

Notes:


Work this sheet with Sheet No. \_.

For details of resin anchors, see Sheet No. \_.


Resin anchors shall be shifted or bent in field to clear one-inch diameter holes by at least 1/2 inch.




ELEVATION SHOWING REINFORCEMENT  
(Right End Post at End Bent No. 1 similar)



PLAN SHOWING REINFORCEMENT  
LEFT END POST AT END BENT NO.



PLAN




ELEVATION


DETAILS OF END POST AND  
GUARD RAIL ATTACHMENT

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

DATE PREPARED 10/13/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 3
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	



Notes:

Longitudinal dimensions are along grade and are taken at top outside edge of curb.

Top of curb blockout shall be built parallel to grade with curb blockout joints (except at end bents) normal to grade.

Concrete in the curb blockout shall be Class B-1.

All exposed edges of curb blockout shall have either a 1/2-inch radius or a 3/8-inch bevel, unless otherwise noted.

Payment for concrete, reinforcement, resin anchor systems and any other work incidental to the curb blockout, complete in place, will be considered completely covered by the contract unit price for Curb Blockout per linear foot.

Measurement of curb blockout is to the nearest linear foot for each structure, measured along the inside edge of curb from end of slab to end of slab.

Concrete traffic barrier delineators shall be placed on top of the curb blockout similarly as shown on Missouri Standard Plans 617.10 and in accordance with Sec 617. Delineators on bridges with two-lane, two-way traffic shall have retroreflective sheeting on both sides. Concrete traffic barrier delineators will be considered completely covered by the contract unit price for Curb Blockout.

**PLAN OF LEFT CURB BLOCKOUT**  
(Right curb blockout similar)

Cost of any concrete curb repair will be considered completely covered by the contract unit price for Curb Blockout.

The 1/4-inch joints may be either formed joints with joint filler or saw-cut joints.


Joint sealant and backer rods shall be in accordance with Sec 717 for Silicone Joint Sealant for Saw Cut and Formed Joints.

For details of optional saw-cut joint, see Sheet No. .

For additional details of end of blockout, see Sheet No. .

Work this sheet with Sheets No. & .

**CURB BLOCKOUT**



\* 4-#5-R bars (Each face) (Equally spaced)

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

DATE PREPARED		10/13/2023	
ROUTE		STATE	
		MO	
DISTRICT		SHEET NO.	
		4	
COUNTY			
JOB NO.			
CONTRACT ID.			
PROJECT NO.			
BRIDGE NO.			




CBO\_03-CurbRail-plan-free

Guidance & Alternate Details

These details are meant to be used as a starting point only. Modify as needed.

If slip-form option is not allowed, include saw-cut joint details, or allow joint filler only (with SPM approval).

Longitudinal R bars in front face shall lap 3'-1" minimum with horizontal R bars in end post.





SECTION A-A

\* 3-#5-R bars (Each face) (Equally spaced)

Change to 3-#5 R bars in Plan (top bar not bent in field) and remove line that indicates the sloped top. Use resin anchor System A for all. 6 R bars in end post at front face (top bar not bent in field).

ALTERNATE DETAILS FOR 2' -8" BLOCKOUT





Notes:

Longitudinal dimensions are along grade and are taken at top outside edge of curb.

Top of curb blockout shall be built parallel to grade with curb blockout joints (except at end bents) normal to grade.

Concrete in the curb blockout shall be Class B-1.

All exposed edges of curb blockout shall have either a 1/2-inch radius or a 3/8-inch bevel, unless otherwise noted.

Payment for concrete, reinforcement, resin anchor systems and any other work incidental to the curb blockout, complete in place, will be considered completely covered by the contract unit price for Curb Blockout per linear foot.

Measurement of curb blockout is to the nearest linear foot for each structure, measured along the inside edge of curb from end of slab to end of slab.

Concrete traffic barrier delineators shall be placed on top of the curb blockout similarly as shown on Missouri Standard Plans 617.10 and in accordance with Sec 617. Delineators on bridges with two-lane, two-way traffic shall have retroreflective sheeting on both sides. Concrete traffic barrier delineators will be considered completely covered by the contract unit price for Curb Blockout.

PLAN OF LEFT CURB BLOCKOUT  
(Right curb blockout similar)

Cost of any concrete curb repair will be considered completely covered by the contract unit price for Curb Blockout.


The 1/4-inch joints may be either formed joints with joint filler or saw-cut joints.

Joint sealant and backer rods shall be in accordance with Sec 717 for Silicone Joint Sealant for Saw Cut and Formed Joints.

For details of optional saw-cut joint, see Sheet No. .

For additional details of end of blockout, see Sheet No. .

Work this sheet with Sheets No. & .



PART ELEVATION  
AT FORMED JOINT


SECTION A-A

\* 4-#5-R bars (Each face) (Equally spaced)

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

DATE PREPARED		10/13/2023	
ROUTE		STATE	
DISTRICT		MO	
		SHEET NO.	
		5	
COUNTY			
JOB NO.			
CONTRACT ID.			
PROJECT NO.			
BRIDGE NO.			
DESCRIPTION			
DATE			
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION			
			
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)			

CBO\_04-CurbRail-plan-attached


Guidance & Alternate Details

These details are meant to be used as a starting point only. Modify as needed.

If slip-form option is not allowed, include saw-cut joint details, or allow joint filler only (with SPM approval).

Longitudinal R bars in front face shall lap 3'-1" minimum with horizontal R bars in end post.


Change to 3-#5 R bars in Plan and remove line that indicates the sloped top. Use resin anchor System A for all anchors in curb; Resin Anchor C becomes B. 6 R bars in end post at front face (top bar not bent in field).





SECTION A-A

\* 3-#5-R bars (Each face) (Equally spaced)


ALTERNATE DETAILS FOR 2' - 8" BLOCKOUT



FREE FROM EXISTING END POST (3'-0")




FREE STANDING



DETAILS OF RESIN ANCHORS

\* Manufacturer's recommended embedment length (5" min.)




TYPICAL SECTION THRU RAILING SHOWING CHANNEL REMOVAL

Cost of channel removal will be considered completely covered by the contract unit price for Curb Blockout.

Notes:

- Work this sheet with Sheets No. & .
- All curb blockout reinforcement shall be epoxy coated.
- The contractor shall use one of the qualified resin anchor systems in accordance with Sec 1039.
- The minimum embedment depth in concrete with f'c = 4,000 psi for the resin anchor system shall be that required to meet the minimum ultimate pullout strength in accordance with Sec 1039 but shall not be less than 5 inches.
- An epoxy coated #6 Grade 60 reinforcing bar shall be substituted for the 3/4-inch diameter threaded rod.
- Resin anchors shall be shifted or bent in field to clear one-inch diameter holes by at least 1/2 inch.



USE ONLY IF THERE IS AN EXPANSION GAP (ANY SIZE) BETWEEN THE END POST AND THE FIRST RAIL POST OFF THE BRIDGE

Detailed  
Checked

DATE PREPARED 10/13/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 6
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)

CBO\_05-CurbRail-details      Guidance & Alternate Details 1 of 2


Standard Drawing Guidance (Do not show on plans):

- ① May use 2'-8" if curb blockout is on a non-NHS route and sight distance or weight is an issue.
- ② Holes may be shifted 12" closer to the end (8" instead of 20") to avoid attaching a rail post to the top of backwall. All other dimensions and reinforcement remain the same.

Use this sheet with CBO\_03 or 04, & CBO\_05.

Longitudinal R bars in front face shall lap 3'-1" minimum with horizontal R bars in end post.


These details may not cover all situations, and are intended as a starting point only. Modify as necessary.




PART SECTION  
THRU END OF BLOCKOUT

PART ELEVATION SHOWING  
END OF BLOCKOUT


ATTACH TO EXISTING END POST (3'-0")



PART ELEVATION OF END OF BLOCKOUT  
SHOWING REINFORCEMENT




ELEVATION B-B




PART SECTION  
THRU END OF BLOCKOUT

PART ELEVATION SHOWING  
END OF BLOCKOUT




FREE FROM EXISTING END POST (2'-8") ①





PART ELEVATION OF END OF BLOCKOUT  
SHOWING REINFORCEMENT



ELEVATION B-B




ATTACH TO EXISTING END POST (2'-8") ①



### TYPICAL ELEVATION OF CURB BLOCKOUT AT SUPPORT LOCATIONS


Horizontal R bars and rail attachment holes not shown for clarity. C bars and textured fiberglass bars shall be used in addition to reinforcement shown for conventional forming.




SECTION A-A

Standard Drawing Guidance  
(Do not show on plans):


① Optional construction joint 1 1/2" (min.) past end of the 7-#5-R bars.



SECTION B-B



SECTION C-C



SECTION THRU  
SAW CUT JOINT

Notes:

\*\* When optional construction joint is used,  
#5-C1 bars may be shifted or omitted.

Work this sheet with Sheets No. \_ & \_.

Joint sealant and backer rods shall be in accordance with Sec 717 for silicone joint sealant for saw cut and formed joints.

For slip-formed option, both sides of the curb blockout shall have a vertically broomed finish and the top shall have a transversely broomed finish.

Cost of silicone joint sealant and backer rod, complete in place, will be considered completely covered by the contract unit price for Curb Blockout.

General notes shown for conventionally formed curb blockouts also apply to slip-formed curb blockouts.

Channel, posts and concrete end posts shall be removed if necessary for slip forming. Removal cost will be considered completely covered by the contract unit price for Curb Blockout.

\* Each side of joint location.

Note: C2 bars spaced with resin anchor systems in roadway face of 12" wide curb blockout.

### OPTIONAL SLIP-FORMED CURB BLOCKOUT

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No.      of

DATE PREPARED	
10/13/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	7

JOB NO.

CONTRACT ID.


PROJECT NO.

BRIDGE NO.


[illegible]MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)






SECTION B-B



SECTION C-C



SECTION THRU  
SAW CUT JOINT

Guidance: Remove top slopes from ends in Elevation for 2'-8" blackout.



Alternate details for 2'-8" blackout

Standard Drawing Guidance (do not show on plans):

Check that the 1 1/2"Ø holes for the diaphragms shown on the design plans will provide a minimum clearance of at least 1 1/2" to any prestressing strands. Diaphragm spacing may need to be adjusted.

For MoDOT Type 2 girder only, use shorter angle and plate 15 1/2" instead of 16" to account for depth tolerance of web. Revise bolt end clearances to 1 3/4".

Delete panels for CIP slab.



STEEL DIAPHRAGM NOTES:

\* In lieu of 2 1/2" outside diameter washers, contractor may substitute a 3/16" (Min. thickness) plate with four 15/16"Ø holes and one hardened washer per bolt.

\*\* Bolts shall be tightened to provide a tension of one-half that specified in Sec 712 for high strength bolt installation. ASTM F3125 Grade A325 Type 1 bolts may be substituted for and installed in accordance with the requirements for the specified ASTM A307 bolts.


All diaphragm materials including bolts, nuts, and washers shall be galvanized.

Fabricated structural steel shall be ASTM A709 Grade 36 except as noted.

Payment for furnishing and installing steel intermediate diaphragms will be considered completely covered by the contract unit price for Steel Intermediate Diaphragm for P/S Concrete Girders.

Shop drawings will not be required for steel intermediate diaphragms and angle connections.

For location of intermediate diaphragms, see Sheet No. .






DATE PREPARED 10/13/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 1
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DATE	DESCRIPTION
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
 <p>105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)</p>	

Standard Drawing Guidance (do not show on plans):

Check that the 1 1/2"Ø holes for the diaphragms shown on the design plans will provide a minimum clearance of at least 1 1/2" to any prestressing strands. Diaphragm spacing may need to be adjusted.

For MoDOT Type 2 girder only, use shorter angle and plate 15 1/2" instead of 16" to account for depth tolerance of web. Revise bolt end clearances to 1 3/4".

Delete panels for CIP slab.



STEEL DIAPHRAGM NOTES:

\* In lieu of 2 1/2" outside diameter washers, contractor may substitute a 3/16" (Min. thickness) plate with four 15/16" Ø holes and one hardened washer per bolt.

**\*\* Bolts shall be tightened to provide a tension of one-half that specified in Sec 712 for high strength bolt installation. ASTM F3125 Grade A325 Type 1 bolts may be substituted for and installed in accordance with the requirements for the specified ASTM A307 bolts.**

All diaphragm materials including bolts, nuts, and washers shall be galvanized.

Fabricated structural steel shall be ASTM A709 Grade 36 except as noted.

Payment for furnishing and installing steel intermediate diaphragms will be considered completely covered by the contract unit price for Steel Intermediate Diaphragm for P/S Concrete Girders.

Shop drawings will not be required for steel intermediate diaphragms and angle connections.

For location of intermediate diaphragms, see Sheet No. .



## STEEL INTERMEDIATE DIAPHRAGMS

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No.      of

DATE PREPARED	
10/13/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	2
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	





[illegible]MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

Standard Drawing Guidance (Do not show on plans):

Check that the 1 1/2"Ø holes for the diaphragms shown on the design plans will provide a minimum clearance of at least 1 1/2" to any prestressing strands. Diaphragm spacing may need to be adjusted.

Delete panels for CIP slab.



**STEEL DIAPHRAGM NOTES:**

\* In lieu of 2 1/2" outside diameter washers, contractor may substitute a 3/16" (Min. thickness) plate with four 15/16" Ø holes and one hardened washer per bolt.

\*\* Bolts shall be tightened to provide a tension of one-half that specified in Sec 712 for high strength bolt installation. ASTM F3125 Grade A325 Type 1 bolts may be substituted for and installed in accordance with the requirements for the specified ASTM A307 bolts.

All diaphragm materials including bolts, nuts, and washers shall be galvanized.


Fabricated structural steel shall be ASTM A709 Grade 36 except as noted.


Payment for furnishing and installing steel intermediate diaphragms will be considered completely covered by the contract unit price for Steel Intermediate Diaphragm for P/S Concrete Girders.

Shop drawings will not be required for steel intermediate diaphragms and angle connections.

For location of intermediate diaphragms, see Sheet No. .

STEEL INTERMEDIATE DIAPHRAGMS




DATE PREPARED		10/13/2023	
ROUTE		STATE	
		MO	
DISTRICT		SHEET NO.	
		3	
COUNTY			
JOB NO.			
CONTRACT ID.			
PROJECT NO.			
BRIDGE NO.			
DESCRIPTION			
DATE			
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION			
		105 WEST CAPITOL	
		JEFFERSON CITY, MO 65102	
		1-888-ASK-MODOT (1-888-275-6636)	





Standard Drawing Guidance (do not show on plans):

Check that the 1 1/2"Ø holes for the diaphragms shown on the design plans will provide a minimum clearance of at least 1 1/2" to any prestressing strands. Diaphragm spacing may need to be adjusted.

Delete panels for CIP slab.



## STEEL INTERMEDIATE DIAPHRAGMS



## STEEL DIAPHRAGM NOTES:

\* In lieu of 2 1/2" outside diameter washers, contractor may substitute a 3/16" (Min. thickness) plate with four 15/16" Ø holes and one hardened washer per bolt.

\*\* Bolts shall be tightened to provide a tension of one-half that specified in Sec 712 for high strength bolt installation. ASTM F3125 Grade A325 Type 1 bolts may be substituted for and installed in accordance with the requirements for the specified ASTM A307 bolts.


All diaphragm materials including bolts, nuts, and washers shall be galvanized.

Fabricated structural steel shall be ASTM A709 Grade 36 except as noted.

Payment for furnishing and installing steel intermediate diaphragms will be considered completely covered by the contract unit price for Steel Intermediate Diaphragm for P/S Concrete Girders.

Shop drawings will not be required for steel intermediate diaphragms and angle connections.




For location of intermediate diaphragms, see Sheet No. .

DATE PREPARED 10/13/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 5
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	DATE
<div>MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION</div> <div><div>105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)</div></div>	



Standard Drawing Guidance (do not show on plans):

Check that the 1 1/2"Ø holes for the diaphragms shown on the design plans will provide a minimum clearance of at least 1 1/2" to any prestressing strands. Diaphragm spacing may need to be adjusted.

```
Delete panels for CIP slab.
```



## STEEL INTERMEDIATE DIAPHRAGMS



STEEL DIAPHRAGM NOTES:

\* In lieu of 2 1/2" outside diameter washers, contractor may substitute a 3/16" (Min. thickness) plate with four 15/16" Ø holes and one hardened washer per bolt.

\*\* Bolts shall be tightened to provide a tension of one-half that specified in Sec 712 for high strength bolt installation. ASTM F3125 Grade A325 Type 1 bolts may be substituted for and installed in accordance with the requirements for the specified ASTM A307 bolts.

All diaphragm materials including bolts, nuts, and washers shall be galvanized.

Fabricated structural steel shall be ASTM A709 Grade 36 except as noted.

Payment for furnishing and installing steel intermediate diaphragms will be considered completely covered by the contract unit price for Steel Intermediate Diaphragm for P/S Concrete Girders.

Shop drawings will not be required for steel intermediate diaphragms and angle connections.

For location of intermediate diaphragms, see Sheet No. .

DATE PREPARED	
10/13/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	6

COUNTY
--------


JOB NO.
---------

CONTRACT ID.


PROJECT NO.

BRIDGE NO.
------------

--	--	--	--	--	--	--	--

[illegible]

MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.




Sheet No.      of



Standard Drawing Guidance (Do not show on plans):

Check that the 1 1/2"Ø holes for the diaphragms shown on the design plans will provide a minimum clearance of at least 1 1/2" to any prestressing strands. Diaphragm spacing may need to be adjusted.

Delete panels for CIP slab.



**STEEL DIAPHRAGM NOTES:**

\* In lieu of 2 1/2" outside diameter washers, contractor may substitute a 3/16" (Min. thickness) plate with four 15/16" Ø holes and one hardened washer per bolt.

\*\* Bolts shall be tightened to provide a tension of one-half that specified in Sec 712 for high strength bolt installation. ASTM F3125 Grade A325 Type 1 bolts may be substituted for and installed in accordance with the requirements for the specified ASTM A307 bolts.

All diaphragm materials including bolts, nuts, and washers shall be galvanized.

Fabricated structural steel shall be ASTM A709 Grade 36 except as noted.

Payment for furnishing and installing steel intermediate diaphragms will be considered completely covered by the contract unit price for Steel Intermediate Diaphragm for P/S Concrete Girders.

Shop drawings will not be required for steel intermediate diaphragms and angle connections.

For location of intermediate diaphragms, see Sheet No. .





Detailed  
Checked

DATE PREPARED 10/13/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 7
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

**MoDOT**

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)



## STEEL DIAPHRAGM NOTES:

\* In lieu of 2 1/2" outside diameter washers, contractor may substitute a 3/16" (Min. thickness) plate with four 15/16"Ø holes and one hardened washer per bolt.

\*\* Bolts shall be tightened to provide a tension of one-half that specified in Sec 712 for high strength bolt installation. ASTM F3125 Grade A325 Type 1 bolts may be substituted for and installed in accordance with the requirements for the specified ASTM A307 bolts.

All diaphragm materials including bolts, nuts, and washers shall be galvanized.

Fabricated structural steel shall be ASTM A709 Grade 36 except as noted.

Payment for furnishing and installing steel intermediate diaphragms will be considered completely covered by the contract unit price for Steel Intermediate Diaphragm for P/S Concrete Girders.

Shop drawings will not be required for steel intermediate diaphragms and angle connections.







For location of intermediate diaphragms, see Sheet No. .

Standard Drawing Guidance (Do not show on plans):

Check that the 1 1/2"Ø holes for the diaphragms shown on the design plans will provide a minimum clearance of at least 1 1/2" to any prestressing strands. Diaphragm spacing may need to be adjusted.

Delete panels for CIP slab.

DATE PREPARED					
10/13/2023					
ROUTE		STATE MO			
DISTRICT		SHEET NO. 8			
COUNTY					
JOB NO.					
CONTRACT ID.					
PROJECT NO.					
BRIDGE NO.					
DESCRIPTION					
DATE					



Standard Drawing Guidance (Do not show on plans):

Check that the 1 1/2"Ø holes for the diaphragms shown on the design plans will provide a minimum clearance of at least 1 1/2" to any prestressing strands. Diaphragm spacing may need to be adjusted.

① Use 2' - 4" for NU 78 girders

Delete panels for CIP slab.

STEEL DIAPHRAGM NOTES:

\* In lieu of 2 1/2" outside diameter washers, contractor may substitute a 3/16" (Min. thickness) plate with four 15/16" Ø holes and one hardened washer per bolt.

\*\* Bolts shall be tightened to provide a tension of one-half that specified in Sec 712 for high strength bolt installation. ASTM F3125 Grade A325 Type 1 bolts may be substituted for and installed in accordance with the requirements for the specified ASTM A307 bolts.

All diaphragm materials including bolts, nuts, and washers shall be galvanized.

Fabricated structural steel shall be ASTM A709 Grade 36 except as noted.


Payment for furnishing and installing steel intermediate diaphragms will be considered completely covered by the contract unit price for Steel Intermediate Diaphragm for P/S Concrete Girders.

Shop drawings will not be required for steel intermediate diaphragms and angle connections.


For location of intermediate diaphragms, see Sheet No. .

[illegible]


MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

The logo for the Missouri Department of Transportation (MoDOT) features a stylized outline of the state of Missouri. Inside the outline, the word "MoDOT" is written in a bold, sans-serif font. To the right of the state outline, there are three curved, overlapping lines that suggest a road or a highway.


105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)



PART SECTION SHOWING  
INTERMEDIATE DIAPHRAGMS




SECTION A-A



SECTION THRU INT. GIRDER  
AT DIAPHRAGM

SECTION THRU EXT. GIRDER  
AT DIAPHRAGM



SECTION B-B

SECTION C-C

Standard Drawing Guidance (Do not show on plans):

Check that the 1 1/2\"Ø holes for the diaphragms shown on the design plans will provide a minimum clearance of at least 1 1/2\" to any prestressing strands. Diaphragm spacing may need to be adjusted.

① Use 2'-4\" for NU 78 girders

Delete panels for CIP slab.

STEEL DIAPHRAGM NOTES:

- \* In lieu of 2 1/2\" outside diameter washers, contractor may substitute a 3/16\" (Min. thickness) plate with four 15/16\"Ø holes and one hardened washer per bolt.
- \*\* Bolts shall be tightened to provide a tension of one-half that specified in Sec 712 for high strength bolt installation. ASTM F3125 Grade A325 Type 1 bolts may be substituted for and installed in accordance with the requirements for the specified ASTM A307 bolts.
- All diaphragm materials including bolts, nuts, and washers shall be galvanized.
- Fabricated structural steel shall be ASTM A709 Grade 36 except as noted.
- Payment for furnishing and installing steel intermediate diaphragms will be considered completely covered by the contract unit price for Steel Intermediate Diaphragm for P/S Concrete Girders.
- Shop drawings will not be required for steel intermediate diaphragms and angle connections.
- For location of intermediate diaphragms, see Sheet No. .

STEEL INTERMEDIATE DIAPHRAGMS

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.


Sheet No. of

DATE PREPARED	
10/13/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	10
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	

MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION


**MoDOT**

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)



TYPICAL PART SECTION SHOWING  
END DIAPHRAGMS

(W21 thru W24) Omit this detail if End Diaphragms  
(slab haunched to bear) are not used.



TYPICAL PART SECTION SHOWING  
END DIAPHRAGMS

(W27 thru W40) Omit these details if End Diaphragms  
(slab haunched to bear) are not used.

DETAIL A

Standard Drawing Guidance (do not show on plans):


Angle size should be shown without inch (") marks on the plans.

Do not show fillet weld size unless by design and size of weld exceeds Sec 1080.

Show specialty welds information as given unless by design.

Delete panels for CIP slab.

① Modify if necessary in accordance with EPG 751.14.5.3.



TYPICAL PART SECTION SHOWING  
CROSS FRAMES AND  
INTERMEDIATE DIAPHRAGMS

Replace this detail with alternate details if  
flange connection angle is required by design.

STEEL DIAPHRAGMS

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.


Sheet No. of

DESCRIPTION	DATE


MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

**MoDOT**


105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)



TYPICAL PART SECTION SHOWING  
CROSS FRAMES AND  
INTERMEDIATE DIAPHRAGMS  
TOP FLANGE IN TENSION




TYPICAL PART SECTION SHOWING  
INTERMEDIATE DIAPHRAGMS  
BOTTOM FLANGE IN TENSION




DETAIL B

(Bottom flange shown,  
top flange similar.)



ELEVATION

SIDE VIEW







PLAN

DETAIL OF FLANGE CONNECTION ANGLE

Note: Bolts shall be 3/4-inch diameter  
ASTM F3125 Grade A325 Type 1 Type 3 that  
connect the 6 x 6 x 3/8 angle to the top  
flange and placed so the nut is on the  
inside of flange (toward the web).

Use these alternate details if  
Flange Connection Angle is  
required by design.

- ② Use Type 3 for weathering steel bolted connections and Type 1 for painted or galvanized steel connections.
- ③ Verify clearance for cross slope.



Standard Drawing Guidance (do not show on plans):

Angle size should be shown without inch (") marks on the plans.

Do not show fillet weld size unless by design and size of weld exceeds Sec 1080.

Show specialty welds information as given unless by design.

Delete panels for CIP slab.


① Modify if necessary in accordance with EPG 751.14.5.4.

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

STEEL DIAPHRAGMS





Sheet No. of




DATE PREPARED 10/13/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 12
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	



Use these alternate details if Flange Connection Angle is required by design.

- ② Use Type 3 for weathering steel bolted connections and Type 1 for painted or galvanized steel connections.
- ③ Verify clearance for cross-slope.





\* At the contractor's option, rectangular fill plates may be used in lieu of diamond fill plates as shown in Optional Detail B.

## STEEL DIAPHRAGMS

Standard Drawing Guidance (do not show on plans):

Angle size should be shown without inch (") marks on the plans.

Do not show fillet weld size unless by design and size of weld exceeds Sec 1080.


Show specialty welds information as given unless by design.

Delete panels for CIP slab.

① Modify if necessary in accordance with EPG 751.14.5.4.



DATE PREPARED	
10/13/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	13
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	

[illegible]MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION



Use these alternate details if  
Flange Connection Angle is  
required by design

② Use Type 3 for weathering steel bolted  
connections and Type 1 for painted or galvanized  
steel connections.






Standard Drawing Guidance (do not show on plans):

See EPG 751.14.5.9.1


Modify as required.

- ① Drip bars should be located between 5 feet from center of expansion device and 1 foot short of the end of the partial coating limit.

Details shown are for plate girder. For wide flange beam, change "Girder" to "Beam" (5 places).




DRIP BAR DETAIL NEAR EXPANSION DEVICE




SECTION A-A

Standard Drawing Guidance (do not show on plans):

Use this detail near expansion device to deflect water away from girder.



DRIP BAR DETAIL NEAR BENTS




SECTION B-B

Standard Drawing Guidance (do not show on plans):

Use this detail near bent, on outside of exterior girder only,  
to deflect water away from bent.

Note:  
Steel for drip bars shall be same grade as bottom flange.


NOTE:  
Steel for drip bars shall be same grade as bottom flange.

<div><div><div>MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION</div><div>105 WEST CAPITAL JEFFERSON CITY, MO 65102</div></div></div>		DATE	DESCRIPTION	DATE PREPARED					
				10/13/2023					
		<div><div>ROUTE</div><div>DISTRICT</div></div>		<div><div>STATE</div><div>SHEET NO.</div></div>					
		COUNTY							
		JOB NO.							
		CONTRACT ID.							
		PROJECT NO.							
		BRIDGE NO.							


Standard Drawing Guidance (do not show on plans):  
Modify as required.

Bolted drip angles should only be used when welded drip bars cannot be used.


① Drip angles should be located between 5 feet from center of expansion device and 1 foot less from the end of the partial coating limit.



SECTION A-A



SECTION B-B



DRIP ANGLES DETAIL


Standard Drawing Guidance (do not show on plans):  
Use this detail near expansion device.  
Use this detail as shown to deflect water from girder.

Note:


Drip angles shall be caulked with dark brown caulking against flange, web and fillet welds.

Drip angles shall be same grade as bottom flange.


Use 1/2-inch diameter ASTM F3125 Grade A325 Type 3 for bolted connection.



SECTION C-C




SECTION D-D









DRIP ANGLES DETAIL

Standard Drawing Guidance (do not show on plans):  
Use this detail near bent.  
Use this detail as shown to deflect water away from bent for exterior girder only.

DATE PREPARED		10/13/2023	
ROUTE		STATE	
DISTRICT		MO	
		SHEET NO.	
		2	
COUNTY			
JOB NO.			
CONTRACT ID.			
PROJECT NO.			
BRIDGE NO.			
DESCRIPTION			
DATE			
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION			
			
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-273-6636)			







\* At about 30'-0" centers with at least one splice gap between pull or end posts.

Standard Drawing Guidance (Do not show on plans.):

- ① 6" embedment typical, may be adjusted to accommodate a thinner slab thickness, but not less than 4" embedment.
- ② May conflict with any proposed expansion device in sidewalk, consult the structural project manager.

GENERAL NOTES:

Pedestrian guard fence (Chain link type) shall be in accordance with Sec 1043 except all fabric shall have the top and bottom edges knuckled.

All posts shall be vertical. Grout of 1/2" minimum thickness shall be placed under floor plates to provide for vertical alignment of posts.

Payment for furnishing, galvanizing and erecting the fence and frame complete with anchor bolts and washers will be considered completely covered by the contract unit price for (112 in.) Curved Top Pedestrian Fence (Structures) per linear foot.

Dimensions of pedestrian guard fence are measured horizontally.

The maximum spacing allowed between pull posts and end posts is 100 ft. Post brace and 1/2"Ø truss rod are required for panels adjacent to pull posts and end posts only.

Connect the lower end of the 1/2"Ø truss rod to the bottom of the pull posts and end posts to which the stretcher bar is attached.

(112 in.) Curved Top Pedestrian Fence (Structures)  
will be measured to the nearest linear foot for each  
structure measured along the bottom outside edge of  
the sidewalk barrier from \_\_\_\_\_ to \_\_\_\_\_.

Core wire size for wire fabric shall be 6 gage minimum.

DATE PREPARED	
10/16/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	1

COUNTY
--------

JOB NO.
CONTRACT ID.
PROJECT NO.
BRIDGE NO.

[illegible]

103 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)





Notes:

These details are a general representation of a Decorative Pedestrian Fence. The actual fence components and component positions may be different than what is shown.

Fence shall have a gloss black finish (Federal Standard #17038). See special provisions.

Base plate shall be ASTM A709, Grade 50.

All base plates, U bolts, hex nuts and washers shall be galvanized in accordance with ASTM A123 and Sec 1081.

Measurement of pedestrian fence will be made horizontally and to the nearest linear foot along centerline fence.

Payment for furnishing and erecting the fence complete in place will be considered completely covered by the contract unit price for (     in.) Decorative Pedestrian Fence (Structures).

All fence posts shall be vertical.

Mortar shall be placed under the post base plates in accordance with Sec 1066.

Decorative pedestrian fencing shall be in accordance with 2020-AASHTO LRFD Bridge Design Specifications, 9th Ed.

Shop drawings and structural calculations will not be required for the decorative pedestrian fences on the Bridge Pre-qualified Products List.

All materials used in fabrication and construction of the decorative pedestrian fencing shall be in accordance with the manufacturer's specifications, except as modified in the contract documents.

Decorative pedestrian fencing system shall be supplied by only one manufacturer. Decorative pedestrian fencing system shall include all components except the anchor bolts and hardware, and #4 bars welded to the anchor bolts. The assembly of the pickets to the rails and the rails to the posts shall be the same as the style mentioned for the manufacturer.

See Bridge Pre-qualified Products List (BPPL) for a list of approved manufacturers.


Substitution for the U-bolt cages will not be permitted.

For details of pedestrian curb, see Sheet No.     .

Standard Drawing Guidance:


(Do not show on plans.)

Note on plans that longitudinal dimensions of fence are horizontal.




TYPICAL PART ELEVATION

\* Optional rail. Need is based on design computations performed by the manufacturer and approved by MoDOT, or may be added for aesthetics.



PART PLAN SHOWING BASE PLATE




SECTION A-A

DECORATIVE PEDESTRIAN FENCE


FEN04 Alternate Details

On Type H Barrier



TYPICAL PART ELEVATION



\* Optional rail. Need is based on design computations performed by the manufacturer and approved by MoDOT, or may be added for aesthetics.



PART ELEVATION AT EXPANSION JOINT  
SHOWING EXPANSION PANEL

\* Optional rail. Need is based on design computations performed by the manufacturer and approved by MoDOT, or may be added for aesthetics.


\*\* Connection shall allow 4" movement.



TYPICAL DETAIL OF FENCE  
AT LIGHT STANDARDS

LIGHT STANDARDS

Include this detail when an expansion joint is used (on curb).




PART ELEVATION AT EXPANSION JOINT  
SHOWING EXPANSION PANEL


\* Optional rail. Need is based on design computations performed by the manufacturer and approved by MoDOT, or may be added for aesthetics.

\*\* Connection shall allow 4" movement.


Use this detail when an expansion joint is used.



SECTION A-A





PART PLAN SHOWING CONNECTION PLATE



ELEVATION C-C

Use where the top of barrier is less than 9 inches wide,  
or when the barrier is to be slip-formed.



GENERAL NOTES:

Finger plate shall be cut with a machine guided gas torch from one plate. The plate from which fingers are cut may be spliced before fingers are cut. The surface of cut shall be perpendicular to the surface of the plate. The cut shall not exceed 1/8" in width. The centerline of cut shall not deviate more than 1/16" from the position of centerline of cut shown. No splicing of finger plate or finger plate assembly will be allowed after fingers are cut. The expansion device shall be fabricated and installed to the crown and grade of the roadway.

Plan dimensions are based on installation at 60°F. The expansion gap and other dimensions shall be increased or decreased 1/8" for each 10° fall or rise in temperature at installation.








Material for the expansion device shall be ASTM A709 Grade 36 structural steel. Anchors for the expansion device shall be in accordance with Sec 1037.

Structural steel for the expansion device and barrier plate shall be coated with a minimum of two coats of inorganic zinc primer to provide a total dry film thickness of 4 mils minimum, 6 mils maximum, or galvanized in accordance with ASTM A123. Anchors need not be protected from overspray.

Payment for furnishing, coating or galvanizing and installing the structural steel for the expansion device will be considered completely covered by the contract unit price for Expansion Device (Finger Plate) per linear foot.

Longitudinal reinforcing steel shall be placed so that ends shall not be more than  $\pm 1"$  from the 3/4" vertical mounting plate at the expansion device.

Complete joint penetration welds utilized in the fabrication of the expansion device shall be nondestructively tested by an approved method.



FINGER PLATE EXPANSION DEVICE AT END BENT NO.


DATE PREPARED	
10/16/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	1
COUNTY	

JOB NO.
CONTRACT ID.
PROJECT NO.
BRIDGE NO.


[illegible]

STANDARD DRAWING GUIDANCE (do not show on plans):  
(For all finger plate drawings. Some notes may not apply to this sheet.)

- ① Not a guidance note. Do not replace.
- ② Gap between fingers, barrier recess gap and, for intermediate bents, gap in
- ③ For end bents:  $② + 1/2" / \cos(\text{skew})$
- ④ Gap adjustment for temperature: along bridge longitudinal axis
- ⑤ Transverse gap between fingers
- ⑥ Maximum gap between fingers normal to joint @ 60°F.
- ⑦ Finger length.
- ⑧ Transverse gap between fingers: not the same as ⑤ for skewed joints.
- ⑨ Plate length =  $(18" + ⑥) / \cos(\text{skew})$
- ⑩ Gap between girder or between girder and end bent.
- ⑪ Include details of slab projection beyond C W-beam under barrier on plan of slab detail sheet. Consider similarly projection beyond front face of angle under barrier at end bents.
- ⑫ Delete panel for CIP slab.




PART PLAN OF FINGER PLATE




PART PLAN OF DEVICE

SQ TYPE B BARRIER (SBC)





PART PLAN OF DEVICE  
LA TYPE B BARRIER (SBC)




PART PLAN OF DEVICE  
LA TYPE D BARRIER











SECTION THRU DEVICE

\* Dimensions along C Girder


Note:  
Concrete shall be forced under and around  
finger plate supporting hardware, anchors,  
angles and bars. Proper consolidation shall  
be achieved by localized internal vibration.




PART PLAN OF DEVICE




PART PLAN OF FINGER PLATE




SECTION A-A




SECTION B-B




PART ELEVATION  
AT END OF  
BARRIER PLATE




SECTION C-C



FINGER DETAIL



OPTIONAL FINGER DETAIL



ELEVATION OF BARRIER

GENERAL NOTES:

Finger plate shall be cut with a machine guided gas torch from one plate. The plate from which fingers are cut may be spliced before fingers are cut. The surface of cut shall be perpendicular to the surface of the plate. The cut shall not exceed 1/8" in width. The centerline of cut shall not deviate more than 1/16" from the position of centerline of cut shown. No splicing of finger plate or finger plate assembly will be allowed after fingers are cut. The expansion device shall be fabricated and installed to the crown and grade of the roadway.

Plan dimensions are based on installation at 60°F. The expansion gap and other dimensions shall be increased or decreased for each 10° fall or rise in temperature at installation.

Material for the expansion device shall be ASTM A709 Grade 36 structural steel. Anchors for the expansion device shall be in accordance with Sec 1037.

Structural steel for the expansion device and barrier plate shall be coated with a minimum of two coats of inorganic zinc primer to provide a total dry film thickness of 4 mils minimum, 6 mils maximum, or galvanized in accordance with ASTM A123. Anchors need not be protected from overspray.

Payment for furnishing, coating or galvanizing and installing the structural steel for the expansion device will be considered completely covered by the contract unit price for Expansion Device (Finger Plate) per linear foot.


Longitudinal reinforcing steel shall be placed so that ends shall not be more than ±1" from the 3/4" vertical mounting plate at the expansion device.

Complete joint penetration welds utilized in the fabrication of the expansion device shall be nondestructively tested by an approved method.


DATE PREPARED		10/16/2023	
ROUTE		STATE	
		MO	
DISTRICT		SHEET NO.	
		2	
COUNTY			
JOB NO.			
CONTRACT ID.			
PROJECT NO.			
BRIDGE NO.			
DESCRIPTION			
DATE			

STANDARD DRAWING GUIDANCE (do not show on plans):  
(For all finger plate drawings. Some notes may not apply to this sheet.)


- ① Not a guidance note. Do not replace.
- ② Gap between fingers, barrier recess gap and, for intermediate bents, gap in barrier.
- ③ For end bents: ② + 1/2"/cos(skew)
- ④ Gap adjustment for temperature: along bridge longitudinal axis
- ⑤ Transverse gap between fingers
- ⑥ Maximum gap between fingers normal to joint @ 60°F.
- ⑦ Finger length.
- ⑧ Transverse gap between fingers: not the same as ⑤ for skewed joints.
- ⑨ Plate length = (18"+ ⑥ )/cos(skew)
- ⑩ Gap between girder or between girder and end bent.
- ⑪ Include details of slab projection beyond C W-beam under barrier on plan of slab detail sheet. Consider similarly projection beyond front face of angle under barrier at end bents.
- ⑫ Delete panel for CIP slab.




PART PLAN OF FINGER PLATE  
LA




PART PLAN OF DEVICE  
LA TYPE B BARRIER (SBC)



PART PLAN OF DEVICE  
SQ TYPE B BARRIER (SBC)




PART PLAN OF DEVICE  
LA TYPE D BARRIER




PART PLAN OF DEVICE

## RA TYPE D BARRIER




PART PLAN OF DEVICE

## RA TYPE B BARRIER (SBC)




PART PLAN OF FINGER PLATE


RA




PART ELEVATION  
AT END OF BENT  
BARRIER PLATE




SECTION B - B



SECTION C-C












SECTION A-A



ELEVATION OF BARRIER

## TYPE B BARRIER (SBC) (ALL SKEWS)



**GENERAL NOTES:**

Finger plate shall be cut with a machine guided gas torch from one plate. The plate from which fingers are cut may be spliced before fingers are cut. The surface of cut shall be perpendicular to the surface of the plate. The cut shall not exceed 1/8" in width. The centerline of cut shall not deviate more than 1/16" from the position of centerline of cut shown. No splicing of finger plate or finger plate assembly will be allowed after fingers are cut. The expansion device shall be fabricated and installed to the crown and grade of the roadway.

Plan dimensions are based on installation at 60°F. The expansion gap and other dimensions shall be increased or decreased 1/16" for each 10° fall or rise in temperature at installation.

Material for the expansion device shall be ASTM A709 Grade 36 structural steel. Anchors for the expansion device shall be in accordance with Sec 1037.



Structural steel for the expansion device and barrier plate shall be coated with a minimum of two coats of inorganic zinc primer to provide a total dry film thickness of 4 mils minimum, 6 mils maximum, or galvanized in accordance with ASTM A123. Anchors need not be protected from overspray.

Payment for furnishing, coating or galvanizing and installing the structural steel for the expansion device will be considered completely covered by the contract unit price for Expansion Device (Finger Plate) per linear foot.

All holes shown for connections shall be subpunched 11/16-inch diameter (shop or field drill) and reamed to 13/16-inch diameter in field, except holes in members that will be used as templates and holes for the drainage trough may be drilled to 13/16-inch diameter in the shop. For multi-piece connections, only the holes in the template member may be drilled to 13/16-inch diameter in the shop.

Longitudinal reinforcing steel shall be placed so that ends shall not be more than ±1" from the web of W14 x 43 at the expansion device.

Complete joint penetration welds utilized in the fabrication of the expansion device shall be nondestructively tested by an approved method.







FINGER PLATE EXPANSION DEVICE AT END BENT NO. \_


FING03\_stl\_end      Guidance & Alternate Details (1 of 2)

STANDARD DRAWING GUIDANCE (do not show on plans):  
(For all finger plate drawings. Some notes may not apply to this sheet.)


- ① Not a guidance note. Do not replace.
- ② Gap between fingers, barrier recess gap and, for intermediate bents, gap in barrier.
- ③ For end bents: ② + 1/2"/cos(skew)
- ④ Gap adjustment for temperature: along bridge longitudinal axis
- ⑤ Transverse gap between fingers
- ⑥ Maximum gap between fingers normal to joint @ 60°F.
- ⑦ Finger length.
- ⑧ Transverse gap between fingers: not the same as ⑤ for skewed joints.
- ⑨ Plate length = (18"+ ⑥ )/cos(skew)
- ⑩ Gap between girder or between girder and end bent.
- ⑪ Include details of slab projection beyond C W-beam under barrier on plan of slab detail sheet. Consider similarly projection beyond front face of angle under barrier at end bents.
- ⑫ Delete panel for CIP slab.









PART PLAN OF DEVICE  
RA TYPE D BARRIER














PART PLAN OF FINGER PLATE  
RA



PART PLAN OF DEVICE  
RA TYPE B BARRIER (SBC)



TYPE B BARRIER (SBC) (ALL)



GENERAL NOTES:

Finger plate shall be cut with a machine guided gas torch from one plate. The plate from which fingers are cut may be spliced before fingers are cut. The surface of cut shall be perpendicular to the surface of the plate. The cut shall not exceed 1/8" in width. The centerline of cut shall not deviate more than 1/16" from the position of centerline of cut shown. No splicing of finger plate or finger plate assembly will be allowed after fingers are cut. The expansion device shall be fabricated and installed to the crown and grade of the roadway.

Plan dimensions are based on installation at 60°F. The expansion gap and other dimensions shall be increased or decreased 1/8" for each 10° fall or rise in temperature at installation.

Material for the expansion device shall be ASTM A709 Grade 36 structural steel. Anchors for the expansion device shall be in accordance with Sec 1037.

Structural steel for the expansion device and barrier plate shall be coated with a minimum of two coats of inorganic zinc primer to provide a total dry film thickness of 4 mils minimum, 6 mils maximum, or galvanized in accordance with ASTM A123. Anchors need not be protected from overspray.

Payment for furnishing, coating or galvanizing and installing the structural steel for the expansion device will be considered completely covered by the contract unit price for Expansion Device (Finger Plate) per linear foot.

All holes shown for connections shall be subpunched 11/16-inch diameter (shop or field drill) and reamed to 13/16-inch diameter in field, except holes in members that will be used as templates and holes for the drainage trough. may be drilled to 13/16-inch diameter in the shop. For multi-piece connections, only the holes in the template member may be drilled to 13/16-inch diameter in the shop.

Longitudinal reinforcing steel shall be placed so that ends shall not be more than  $\pm 1"$  from the web of W14 x 43 at the expansion device.

Complete joint penetration welds utilized in the fabrication of the expansion device shall be nondestructively tested by an approved method.

DATE PREPARED	
10/16/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	4
COUNTY	


1999, 2000, 2001, 2002, 2003, 2004, 2005, 2006, 2007, 2008, 2009, 2010, 2011, 2012, 2013, 2014, 2015, 2016, 2017, 2018, 2019, 2020, 2021, 2022, 2023, 2024, 2025, 2026, 2027, 2028, 2029, 2030, 2031, 2032, 2033, 2034, 2035, 2036, 2037, 2038, 2039, 2040, 2041, 2042, 2043, 2044, 2045, 2046, 2047, 2048, 2049, 2050, 2051, 2052, 2053, 2054, 2055, 2056, 2057, 2058, 2059, 2060, 2061, 2062, 2063, 2064, 2065, 2066, 2067, 2068, 2069, 2070, 2071, 2072, 2073, 2074, 2075, 2076, 2077, 2078, 2079, 2080, 2081, 2082, 2083, 2084, 2085, 2086, 2087, 2088, 2089, 2090, 2091, 2092, 2093, 2094, 2095, 2096, 2097, 2098, 2099, 2100, 2101, 2102, 2103, 2104, 2105, 2106, 2107, 2108, 2109, 2110, 2111, 2112, 2113, 2114, 2115, 2116, 2117, 2118, 2119, 2120, 2121, 2122, 2123, 2124, 2125, 2126, 2127, 2128, 2129, 2130, 2131, 2132, 2133, 2134, 2135, 2136, 2137, 2138, 2139, 2140, 2141, 2142, 2143, 2144, 2145, 2146, 2147, 2148, 2149, 2150, 2151, 2152, 2153, 2154, 2155, 2156, 2157, 2158, 2159, 2160, 2161, 2162, 2163, 2164, 2165, 2166, 2167, 2168, 2169, 2170, 2171, 2172, 2173, 2174, 2175, 2176, 2177, 2178, 2179, 2180, 2181, 2182, 2183, 2184, 2185, 2186, 2187, 2188, 2189, 2190, 2191, 2192, 2193, 2194, 2195, 2196, 2197, 2198, 2199, 2200, 2201, 2202, 2203, 2204, 2205, 2206, 2207, 2208, 2209, 2210, 2211, 2212, 2213, 2214, 2215, 2216, 2217, 2218, 2219, 2220, 2221, 2222, 2223, 2224, 2225, 2226, 2227, 2228, 2229, 2230, 2231, 2232, 2233, 2234, 2235, 2236, 2237, 2238, 2239, 2240, 2241, 2242, 2243, 2244, 2245, 2246, 2247, 2248, 2249, 2250, 2251, 2252, 2253, 2254, 2255, 2256, 2257, 2258, 2259, 2260, 2261, 2262, 2263, 2264, 2265, 2266, 2267, 2268, 2269, 2270, 2271, 2272, 2273, 2274, 2275, 2276, 2277, 2278, 2279, 2280, 2281, 2282, 2283, 2284, 2285, 2286, 2287, 2288, 2289, 2290, 2291, 2292, 2293, 2294, 2295, 2296, 2297, 2298, 2299, 2300, 2301, 2302, 2303, 2304, 2305, 2306, 2307, 2308, 2309, 2310, 2311, 2312, 2313, 2314, 2315, 2316, 2317, 2318, 2319, 2320, 2321, 2322, 2323, 2324, 2325, 2326, 2327, 2328, 2329, 2330, 2331, 2332, 2333, 2334, 2335, 2336, 2337, 2338, 2339, 2340, 2341, 2342, 2343, 2344, 2345, 2346, 2347, 2348, 2349, 2350, 2351, 2352, 2353, 2354, 2355, 2356, 2357, 2358, 2359, 2360, 2361, 2362, 2363, 2364, 2365, 2366, 2367, 2368, 2369, 2370, 2371, 2372, 2373, 2374, 2375, 2376, 2377, 2378, 2379, 2380, 2381, 2382, 2383, 2384, 2385, 2386, 2387, 2388, 2389, 2390, 2391, 2392, 2393, 2394, 2395, 2396, 2397, 2398, 2399, 2400, 2401, 2402, 2403, 2404, 2405, 2406, 2407, 2408, 2409, 2410, 2411, 2412, 2413, 2414, 2415, 2416, 2417, 2418, 2419, 2420, 2421, 2422, 2423, 2424, 2425, 2426, 2427, 2428, 2429, 2430, 2431, 2432, 2433, 2434, 2435, 2436, 2437, 2438, 2439, 2440, 2441, 2442, 2443, 2444, 2445, 2446, 2447, 2448, 2449, 2450, 2451, 2452, 2453, 2454, 2455, 2456, 2457, 2458, 2459, 2460, 2461, 2462, 2463, 2464, 2465, 2466, 2467, 2468, 2469, 2470, 2471, 2472, 2473, 2474, 2475, 2476, 2477, 2478, 2479, 2480, 2481, 2482, 2483, 2484, 2485, 2486, 2487, 2488, 2489, 2490, 2491, 2492, 2493, 2494, 2495, 2496, 2497, 2498, 2499, 2500, 2501, 2502, 2503, 2504, 2505, 2506, 2507, 2508, 2509, 2510, 2511, 2512, 2513, 2514, 2515, 2516, 2517, 2518, 2519, 2520, 2521, 2522, 2523, 2524, 2525, 2526, 2527, 2528, 2529, 2530, 2531, 2532, 2533, 2534, 2535, 2536, 2537, 2538, 2539, 2540, 2541, 2542, 2543, 2544, 2545, 2546, 2547, 2548, 2549, 2550, 2551, 2552, 2553, 2554, 2555, 2556, 2557, 2558, 2559, 2560, 2561, 2562, 2563, 2564, 2565, 2566, 2567, 2568, 2569, 2570, 2571, 2572, 2573, 2574, 2575, 2576, 2577, 2578, 2579, 2580, 2581, 2582, 2583, 2584, 2585, 2586, 2587, 2588, 2589, 2590, 2591, 2592, 2593, 2594, 2595, 2596, 2597, 2598, 2599, 2600, 2601, 2602, 2603, 2604, 2605, 2606, 2607, 2608, 2609, 2610, 2611, 2612, 2613, 2614, 2615, 2616, 2617, 2618, 2619, 2620, 2621, 2622, 2623, 2624, 2625, 2626, 2627, 2628, 2629, 2630, 2631, 2632, 2633, 2634, 2635, 2636, 2637, 2638, 2639, 2640, 2641, 2642, 2643, 2644, 2645, 2646, 2647, 2648, 2649, 2650, 2651, 2652, 2653, 2654, 2655, 2656, 2657, 2658, 2659, 2660, 2661, 2662, 2663, 2664, 2665, 2666, 2667, 2668, 2669, 2670, 2671, 2672, 2673, 2674, 2675, 2676, 2677, 2678, 2679, 2680, 26

JOB NO.
---------

CONTRACT ID
-------------

CONTRACT ID.

PROJECT NO.
-------------


[illegible]BRIDGE NO.[illegible][illegible]MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)




STANDARD DRAWING GUIDANCE (do not show on plans):  
(For all finger plate drawings. Some notes may not apply to this sheet.)

- ① Not a guidance note. Do not replace.
- ② Gap between fingers, barrier recess gap and, for intermediate bents, gap in
- ③ For end bents:  $② + 1/2" / \cos(\text{skew})$
- ④ Gap adjustment for temperature: along bridge longitudinal axis
- ⑤ Transverse gap between fingers
- ⑥ Maximum gap between fingers normal to joint @ 60°F.
- ⑦ Finger length.
- ⑧ Transverse gap between fingers: not the same as ⑤ for skewed joints.
- ⑨ Plate length =  $(18" + ⑥) / \cos(\text{skew})$
- ⑩ Gap between girder or between girder and end bent.
- ⑪ Include details of slab projection beyond C W-beam under barrier on plan of slab detail sheet. Consider similarly projection beyond front face of angle under barrier at end bents.
- ⑫ Delete panel for CIP slab.




PART PLAN OF DEVICE

SQ TYPE B BARRIER (SBC)




PART PLAN OF FINGER PLATE

LA




PART PLAN OF DEVICE

LA TYPE B BARRIER (SBC)




PART PLAN OF DEVICE


LA TYPE D BARRIER




PART PLAN OF DEVICE  
RA TYPE D BARRIER



PART PLAN OF FINGER PLATE  
RA




PART PLAN OF DEVICE  
RA TYPE B BARRIER (SBC)




PART ELEVATION  
AT END OF BENT  
BARRIER PLATE


SECTION B-B



SECTION C-C



SECTION A-A



ELEVATION OF BARRIER

TYPE B BARRIER (SBC) (ALL SKEWS)



STANDARD DRAWING GUIDANCE (do not show on plans):  
(For all finger plate drawings. Some notes may not apply to this sheet.)

- 1

Not a guidance note. Do not replace.
- 2

Gap between fingers, barrier recess gap and, for intermediate bents, gap in barrier.
- 3

For end bents: 2 + 1/2"/cos(skew)
- 4

Gap adjustment for temperature: along bridge longitudinal axis
- 5

Transverse gap between fingers
- 6

Maximum gap between fingers normal to joint @ 60°F.
- 7

Finger length.
- 8


Transverse gap between fingers: not the same as 5 for skewed joints.
- 9

Plate length = (18"+ 6 )/cos(skew)
- 10


Gap between girder or between girder and end bent.
- 11

Include details of slab projection beyond C W-beam under barrier on plan of slab detail sheet. Consider similarly projection beyond front face of angle under barrier at end bents.
- 12


Delete panel for CIP slab.




PART PLAN OF FINGER PLATE  
LA




PART PLAN OF DEVICE  
SQ TYPE B BARRIER (SBC)



PART PLAN OF DEVICE  
LA TYPE B BARRIER (SBC)




PART PLAN OF DEVICE  
LA TYPE D BARRIER




PART PLAN OF DEVICE

RA TYPE D BARRIER





PART PLAN OF FINGER PLATE

RA




PART PLAN OF DEVICE


RA TYPE B BARRIER (SBC)

PART ELEVATION  
AT END OF BENT  
BARRIER PLATE

SECTION B-B



SECTION C-C







SECTION A-A

ELEVATION OF BARRIER

## TYPE B BARRIER (SBC) (ALL SKEWS)





### ALTERNATE DETAILS FOR TYPE B BARRIER (SBC)





STANDARD DRAWING GUIDANCE (do not show on plans):

- ① Gap in barrier and barrier recess gap  
For gap in barrier at end bents: add  $1/2" / \cos(\text{skew})$
- ② Barrier plate length.
- ③ Include details of slab projection beyond C W-beam under barrier on plan of slab detail sheet. Consider similar projection beyond front face of angle under barrier at end bents.

For gap in barrier at end bents: add  $1/2" / \cos(\text{skew})$

- ② Barrier plate length.

- ③ Include details of slab projection beyond  $\frac{1}{4}$  W-beam under barrier on plan of slab detail sheet. Consider similar projection beyond front face of angle under barrier at end bents.



## FINGER PLATE EXPANSION DEVICE AT MEDIAN

Detailed  
CheckedDetailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No.      of

DATE PREPARED	
10/16/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	6

10/16/2023

ROUTE	STATE
	MO

	MO
DISTRICT	SHEET NO

SHEET NO. 6

COUNTY

---

JOB NO.

CONTRACT ID.

---

[illegible]

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

**MoDOT**


105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

100 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)


JEFFERSON CITY, MO 65102  
K-MODOT (1-888-275-6636)

100 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)




PART PLAN

Note: Concrete vent holes not shown for clarity.




SECTION AT END BENT

\* Dimension along ① Girder




PERMISSIBLE FIELD SPLICE AT END BENT




SECTION THRU DEVICE

(GRADE LESS THAN 3%)




SECTIONS THRU DEVICE


(GRADE 3% OF MORE)




PART PLAN SHOWING ROADWAY PLATE AND VERTICAL PLATE




SECTION B-B




PART PLAN OF ANGLE AND BAR




SECTION A-A



PART ELEVATION AT END OF BARRIER PLATE



SECTION C-C



ELEVATION OF BARRIER

GENERAL NOTES:

Expansion device shall be fabricated in one section, except for stage construction and when the length is over 50 feet. A complete joint penetration groove weld splice shall be required. Welds shall be ground flush to provide a smooth surface. The expansion device shall be fabricated and installed to the crown and grade of the roadway.

Plan dimensions are based on installation at 60°F. The expansion gap and other dimensions shall be increased or decreased ⑤ for each 10° fall or rise in temperature at installation.

Material for the expansion device shall be ASTM A709 Grade 36 structural steel. Anchors for the expansion device shall be in accordance with Sec 1037.


Structural steel for the expansion device and barrier plate shall be coated with a minimum of two coats of inorganic zinc primer to provide a total dry film thickness of 4 mils minimum, 6 mils maximum, or galvanized in accordance with ASTM A123. Anchors need not be protected from overspray.

Payment for furnishing, coating or galvanizing and installing the structural steel for the expansion device will be considered completely covered by the contract unit price for Expansion Device (Flat Plate) per linear foot.

Concrete shall be forced under and around flat plate, anchors and angles. Proper consolidation shall be achieved by localized internal vibration. Finishing of the concrete shall be achieved by hand finishing within one foot of the expansion device. The vertical and horizontal concrete vent holes shall be offset from each other. Do not alternate holes at the 12" spacing.

Longitudinal reinforcing steel shall be placed so that ends shall not be more than ±1" from vertical plate and the vertical leg of the angle at the expansion device.


Complete joint penetration welds utilized in the fabrication of the expansion device shall be nondestructively tested by an approved method.

		DATE PREPARED 10/16/2023	
ROUTE		STATE MO	
DISTRICT		SHEET NO. 1	
COUNTY			
JOB NO.			
CONTRACT ID.			
PROJECT NO.			
BRIDGE NO.			
DESCRIPTION			
DATE			
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION			
<div><div>105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)</div></div>			



## Guidance & Alternate Details (1 of 2)

- ① Bar height.
- ② Plate length =  $12"/\cos(\text{skew})$  [12" for 0° skew]
- ③ Barrier gap =  $3\frac{1}{2}"/\cos(\text{skew})$  [ $3\frac{1}{2}$ " for 0° skew]
- ④ Barrier recess gap =  $2\frac{3}{8}"/\cos(\text{skew})$  [ $2\frac{3}{8}$ " for 0° skew]. Assume recess ends at front edge of bar.
- ⑤ Installation gap adjustment for temperature: normal to joint.
- ⑥ Check and revise locations of slotted wells to clear girder end section reinforcement.
- ⑦ Delete panel for CIP slab.



Recess barrier to permit free movement of plate

7/16"Ø Hole countersunk in roadway plate; Slotted Hole 1/2" x 1" in angle; Bar 1 1/4" x 3/8" x 2" tapped for 3/8"Ø flat head stove bolt at abt. 4'-0" cts. Remove bolt after concrete has set.

3/4"Ø x 8" Long Welded Shear Connector Studs (Spaced alternately at about 9" cts.)(Typ.)

1/4" 2-8

Plate 12" x 7/8"

Angle 8 x 6 x 5/8

Bar 7/8" x 1" (1)

End of Slab

3/4" Welded Shear Connector Studs (3/4"Ø x 6" Long)

1/2" Bent Barrier Plate

3/4" Plate with two 13/16" x 1 1/2" vertical slotted holes for 3/4"Ø machine bolts and nuts.

1/2" Beveled Stiffener Plate

3/4" x 2 1/4" Wide Plate with two 13/16" x 3" slotted holes (Placed along centerline of girder parallel to roadway)


Ø Girder

Ø 1 1/4" x 2" x 4 1/2" Slotted Well (Cast in top of the prestressed girder) and 3/4"Ø x 7" Anchor Bolt with nut and washer. See Std. Specs. for grout for the anchor bolts.



Plate 6" x 5/8"

## SQ TYPE B BARRIER (SBC)






RA TYPE D BARRIER




RA TYPE B BARRIER (SBC)






STANDARD DRAWING GUIDANCE (do not show on plans):

- ①Bar height.
- ②Plate length = 12"/cos(skew) [12" for 0° skew]
- ③Barrier gap = 3½"/cos(skew) [3½" for 0° skew]
- ④Barrier recess gap = 2⅝"/cos(skew) [2⅝" for 0° skew]. Assume recess ends at front edge of bar.
- ⑤Installation gap adjustment for temperature: normal to joint.
- ⑥Check and revise locations of slotted wells to clear girder end section reinforcement.
- ⑦Delete panel for CIP slab.



PERMISSIBLE FIELD SPLICE AT INT. BENT


LA



PART PLAN

Note: Concrete vent holes not shown for clarity.


SQ TYPE B BARRIER (SBC)



PART PLAN

Note: Concrete vent holes not shown for clarity.

LA TYPE D BARRIER




PART PLAN

Note: Concrete vent holes not shown for clarity.

LA TYPE B BARRIER (SBC)






PART PLAN

Note: Concrete vent holes not shown for clarity.


## RA TYPE D BARRIER



PART PLAN


Note: Concrete vent holes not shown for clarity.

## RA TYPE B BARRIER (SBC)



PERMISSIBLE FIELD SPLICE AT INT. BENT

RA




### TYPE B BARRIER (SBC) (ALL)



FLAT03\_stl\_end      Guidance & Alternate Details (1 of 2)


STANDARD DRAWING GUIDANCE (do not show on plans):

- ① Bar height.
- ② Plate length = 12"/cos(skew) [12" for 0° skew]
- ③ Barrier gap = 3½"/cos(skew) [3½" for 0° skew]
- ④ Barrier recess gap = 2⅜"/cos(skew) [2⅜" for 0° skew]. Assume recess ends at front edge of bar.
- ⑤ Installation gap adjustment for temperature: normal to joint.
- ⑥ Check and revise locations of slotted wells to clear girder end section reinforcement.
- ⑦ Delete panel for CIP slab.



PERMISSIBLE FIELD SPLICE AT END BENT


LA



PART PLAN

Note: Concrete vent holes not shown for clarity.


LA TYPE D BARRIER



PART PLAN

Note: Concrete vent holes not shown for clarity.

SQ TYPE B BARRIER (SBC)




PART PLAN

Note: Concrete vent holes not shown for clarity.

① 3" (Min.)

LA TYPE B BARRIER (SBC)






PART PLAN


Note: Concrete vent holes not shown for clarity.

RA TYPE D BARRIER



PERMISSIBLE FIELD SPLICE AT END BENT


RA



PART PLAN

Note: Concrete vent holes not shown for clarity.

RA TYPE B BARRIER (SBC)



TYPE B BARRIER (SBC) (ALL)




## FLAT04\_stl\_int

## Guidance & Alternate Details (1 of 2)


STANDARD DRAWING GUIDANCE (do not show on plans):

- ① Bar height:
- ② Plate length =  $12"/\cos(\text{skew})$  [12" for 0° skew]
- ③ Barrier gap =  $3\frac{1}{2}"/\cos(\text{skew})$  [ $3\frac{1}{2}$ " for 0° skew]
- ④ Barrier recess gap =  $2\frac{3}{8}"/\cos(\text{skew})$  [ $2\frac{3}{8}$ " for 0° skew]. Assume recess ends at front edge of bar.
- ⑤ Installation gap adjustment for temperature: normal to joint.
- ⑥ Check and revise locations of slotted wells to clear girder end section reinforcement.
- ⑦ Delete panel for CIP slab.



PERMISSIBLE FIELD SPLICE AT INT. BENT


LA



PART PLAN

Note: Concrete vent holes not shown for clarity.


## SQ TYPE B BARRIER (SBC)



## PART PLAN

Note: Concrete vent holes not shown for clarity.

## LA TYPE D BARRIER




PART PLAN

Note: Concrete vent holes not shown for clarity.

① 3" (Min.)


## LA TYPE B BARRIER (SBC)



PART PLAN


Note: Concrete vent holes not shown for clarity.

RA TYPE D BARRIER



PERMISSIBLE FIELD SPLICE AT INT. BENT


RA



PART PLAN

Note: Concrete vent holes not shown for clarity.

RA TYPE B BARRIER (SBC)



TYPE B BARRIER (SBC) (ALL)


General Notes:

Open cell foam joint seal size (width and depth) shall be determined by the manufacturer. Manufacturer recommended seal size shall meet the movement and installation gap requirements and skew effect.

The open cell foam joint seal shall be installed according to the manufacturer's recommendations.

The installation temperature shall be taken as the actual air temperature averaged over the 24-hour period immediately preceding installation.

(1) Allowed installation gap ( $\pm$ ) normal to joint at roadway surface (see table)



SECTION THRU JOINT  
AT ABUTMENT NO.     

SKEW =     °

\* Manufacturer's recommended size

Extend seal 3" past edges of slab.

Standard Drawing Guidance (do not show on plans):

Revise notes and details per project as necessary.

Use standard detailing notes H5.31, H5.33 thru H5.36 (EPG 751.50) when new armor is to be used. Modify note H5.33 for open cell foam joint seal.

Use standard detailing note H5.55 when polymer concrete wearing surface is used with an open cell foam joint seal.

When new steel armor is to be installed, use armor information from P\_COM standard drawing and modify as needed.

Omit " $\pm$ " when not applicable.

[illegible]

MoDOT construction personnel will record the manufacturer and seal name that was used.

# OPEN CELL FOAM JOINT SEAL


Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No.      of

[illegible]

SEAL01\_OCF      Alternate Details




SECTION THRU JOINT AT END OF BRIDGE APPROACH SLAB

SKEW = \_\_°

\* Manufacturer's recommended size

Extend seal full width of approach slab.

Between bridge approach slab  
and concrete approach pavement  
(Use only with approval of SPM or SLE)




SECTION THRU JOINT AT \_\_\_\_ NO. \_

SKEW = \_\_°

\* Manufacturer's recommended size

Extend seal 3" past edges of slab.

With existing steel armor




SECTION THRU JOINT AT ABUTMENT NO. \_

SKEW = \_\_°

\* Manufacturer's recommended size

Extend seal 3" past edges of slab.

Between slab and approach slab




SECTION THRU JOINT AT BENT NO.

SKEW = \_\_°


\* Manufacturer's recommended size

Extend seal 3" past edges of slab.


Use for locations other than approach slab



SECTION THRU JOINT AT \_\_\_\_ NO.\_.



SECTION THRU EDGE OF  
SLAB NEAR JOINT



PART ELEVATION OF BARRIER

Preformed silicone or EPDM seal not shown for clarity. Seal installation between barriers in-place is required.


General Notes:

The seal shall be installed in joints in one continuous piece without field splices. Factory splicing will be permitted for joints in excess of 53 feet.

The installation temperature shall be taken as the actual air temperature averaged over the 24-hour period immediately preceding installation.

(1) Allowed installation gap ( $\pm$ ) normal to joint at roadway surface (see table)

(2) Installation depth ( $\pm$ ) per manufacturer's recommendation



DETAIL OF SEAL

\* Double hump seal shown in figure. Actual shape of seal may be double or single hump as per manufacturer.

Standard Drawing Guidance (do not show on plans):  
Remove non-applicable rows in table.  
Revise notes and details per project as necessary.  
  
Use standard detailing notes H5.31, H5.33 thru H5.36 (EPG 751.50) when new armor is to be used. Modify note H5.33 for preformed silicone or EPDM joint seal.  
  
When new steel armor is to be installed, use armor information from P COM standard drawing and modify as needed.  
  
Omit " $\pm$ " when not applicable.

Allowed Transverse Preformed Silicone or EPDM Joint Seals							
Manufacturer	Seal Name	Movement Parallel to Roadway	(1) Allowed Installation Gap Normal to Joint at Roadway Surface at Air/Surface Temperature				Type Used (✓)
			@ 40°F	@ 50°F	@ 60°F	@ 70°F	
R J Watson (Silicoflex Joint Seal)	Silicoflex SF150	XXX	XXX	XXX	XXX	XXX	<input type="checkbox"/>
R J Watson (Silicoflex Joint Seal)	Silicoflex SF225	XXX	XXX	XXX	XXX	XXX	<input type="checkbox"/>
R J Watson (Silicoflex Joint Seal)	Silicoflex SF400	XXX	XXX	XXX	XXX	XXX	<input type="checkbox"/>
Watson Bowman Acme Wabo (Preformed Silicone Joint Seal)	Wabo SPS-225	XXX	XXX	XXX	XXX	XXX	<input type="checkbox"/>
Watson Bowman Acme Wabo (Preformed Silicone Joint Seal)	Wabo SPS-400	XXX	XXX	XXX	XXX	XXX	<input type="checkbox"/>
D S Brown (EPDM Joint Seal)	V-Seal V-300	XXX	XXX	XXX	XXX	XXX	<input type="checkbox"/>
D S Brown (EPDM Joint Seal)	V-Seal V-400	XXX	XXX	XXX	XXX	XXX	<input type="checkbox"/>

MoDOT Construction personnel will indicate the type of seal used.

PREFORMED SILICONE OR EPDM JOINT SEAL

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

DATE PREPARED  
10/16/2023

ROUTE  
STATE  
DISTRICT  
SHEET NO.  
COUNTY

JOB NO.

CONTRACT ID.


PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION




105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)




SEAL02\_P\_SIL\_EPDM

Alternate Details



SECTION THRU JOINT AT \_\_\_\_ NO. \_

Polymer concrete shall be in accordance with Sec 623.



SECTION THRU JOINT AT \_\_\_\_ NO. \_

Joint gap (opening) wider than 3" during installation may require use of backer rod to keep seal in place while adhesive is curing.

X' MECHANICALLY STABILIZED EARTH (MSE) RETAINING WALL SYSTEM

⦿ Indicates location of borings.

Notice and Disclaimer Regarding Boring Log Data

The locations of all subsurface borings for this structure are shown on the plan sheet(s) for this structure. The boring data for all locations indicated, as well as any other boring logs or other factual records of subsurface data and investigations performed by the department for the design of the project, are shown on Sheet(s) No. \_\_\_ and may be included in the Electronic Bridge Deliverables. They will also be available from the Project Contact upon written request. No greater significance or weight should be given to the boring data depicted on the plan sheets than is given to the subsurface data available from the district or elsewhere.

The Commission does not represent or warrant that any such boring data accurately depicts the conditions to be encountered in constructing this project. A contractor assumes all risks it may encounter in basing its bid prices, time or schedule of performance on the boring data depicted here or those available from the district, or on any other documentation not expressly warranted, which the contractor may obtain from the Commission.

General Notes:

Design Specifications:

2002 AASHTO LFD (17th Ed.) Standard Specifications (Section 5 ASD Design)  
Seismic Performance Category =  
Acceleration Coefficient =

Design Loading:

$\Phi_b$  = ° and Unit weight,  $\gamma_b$  = pcf for retained backfill material to be retained by the mechanically stabilized earth wall system.

$\Phi_f$  = ° for unimproved foundation ground where wall is to bear.  
 $\Phi_f$  = ° for improved foundation ground where wall is to bear.

For unimproved foundation ground, the allowable bearing pressure is \_\_\_\_ ksf.  
For improved foundation ground, the allowable bearing pressure is \_\_\_\_ ksf.

The maximum applied bearing pressure for the controlling design case at the foundation level shall be shown on the shop drawings and shall be less than the allowable bearing pressure for foundation ground provided herein. For seismic design the maximum applied bearing pressure shall be less than two times the allowable bearing pressure.

Allowable bearing pressure and limits of improved foundation ground shall not be adjusted from that as shown on the plans.

Contractor shall include design  $\Phi_r$  (actual  $\Phi_r \geq 34^\circ$ ) and the total unit weight,  $\gamma_r$ , for the select granular backfill (reinforced backfill and wedge area backfill) for structural systems on shop drawings. Contractor shall identify source of select granular backfill material, submit proctor in accordance with AASHTO T 99 (ASTM D698) and gradation with the shop drawings. When backfill material is too coarse to develop a proctor curve the contractor shall determine the maximum dry density (relative density) in accordance with ASTM D4253 and ASTM D4254 and assume percent passing the 200 sieve for optimum water content.

Total unit weight,  $\gamma_r$  = (95% compaction) x (maximum dry density) x (1 + optimum water content)

Design  $\Phi_r$  = 34° for the select granular backfill (reinforced backfill) only for structural systems.

Factor of safety shall be 2.0 for overturning and 1.5 for sliding.

For seismic design the factor of safety shall be 1.5 for overturning and 1.1 for sliding.

Use default values for the pullout friction factor,  $F^*$ , in accordance with AASHTO figure 5.8.5.2A and default value for scale effect correction factor,  $\alpha$ , in accordance with AASHTO table 5.8.5.2A. For approved steel strips not shown in AASHTO figure 5.8.5.2A, use  $F^* \leq 2.0$  at zero depth and  $F^* \leq \tan \Phi_r$  at 20 feet depth and  $\Phi_r$  design = 34°.  $F^*$  and  $\alpha$  values shall be shown on the shop drawings.

Design Unit Stresses:

All concrete for leveling pad and coping shall be Class B or B-1 with  $f'c$  = 4000 psi.

The minimum compressive strength of concrete for precast panel precast concrete block shall be 4,000 psi in accordance with Sec 1052.

Miscellaneous:

The MSE wall system shall be built vertical.

The MSE wall system shall be built in accordance with Sec 720.

The MSE wall system shall be a small large block wall system.

The cost of joint filler and joint seal, complete in place, will be considered completely covered by the contract unit price for Concrete Traffic Barrier (Type A D). See Roadway Plans.

Panel, concrete block and coping (or capstone) reinforcement shall be epoxy coated.

A filter cloth meeting the requirements for a Separation Geotextile material shall be placed between the select granular backfill for structural systems and the backfill being retained by the mechanically stabilized earth wall system.

Coping shall be required on this structure. When CIP coping sections extend beyond the limits of a single panel, bond breaker (roofing felt or other approved alternate) between wall panel and coping is required. Coping joints shall use 3/4-inch chamfers and shall be sealed with 3/4-inch joint filler. Coping reinforcement shall terminate 1 1/2-inch minimum from face of coping joint.

The top and bottom elevations are given for a vertical wall. The height of the wall shall be adjusted as necessary to fit the ground slope and the concrete leveling pad shall be adjusted as necessary to account for the wall batter. If a fence is built on an extended gutter, then the height of the wall shall be adjusted further.

The baseline of the wall shown is for a vertical wall. This baseline shall correspond to Elevation \_\_\_\_\_.

The contractor shall be solely responsible to coordinate construction of the wall with bridge and roadway construction and ensure that the bridge and roadway construction, resulting or existing obstructions, shall not impact the construction or performance of the wall. Soil reinforcement shall be designed and placed to avoid damage by pile driving, guardrail post installation, utility and sign foundations. (See Roadway and Bridge plans.)

B.M.


RETAINING WALL ALONG \*

ROUTE \* FROM \* TO \*

ABOUT \* MILES \* OF \*

\* STATION \*

PLAN ④



DEVELOPED ELEVATION

Concrete Leveling pad not shown for clarity. (1)

(1) Wall contractor shall show the following items on the design drawings and/or on the fabricator shop drawings.

- Leveling pad horizontal.

- Leveling pad length and step elevations shall be based on wall manufacturer's recommendation. Top of leveling pad elevations shall not be higher than theoretical top of leveling pad elevations shown on these plans.

Estimated Quantities		
Item		Total
Mechanically Stabilized Earth Wall Systems	sq. foot	

DETAILS OF ③  
GROUND IMPROVEMENTS

LOCATION SKETCH

MSE Wall Systems Data Table					
Proprietary Wall Systems		Combination Wall Systems			
Manufacturer	System	Facing Unit Manufacturer	Facing Unit	Geogrid Manufacturer	Geogrid

MSE Wall Systems Data Table is to be completed by MoDOT construction personnel to record the manufacturer of the proprietary wall system or the manufacturers of the combination wall system that was used for constructing the MSE wall.

DATE PREPARED  
3/7/2023

ROUTE  
DISTRICT

STATE  
MO

SHEET NO.  
1

COUNTY

JOB NO.

CONTRACT ID.


PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION



105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

MSEW\_01\_LFD1

Guidance

Standard Drawing Guidance (do not shown on plans):

Revise notes and details per project as necessary.

Proposed grade & theoretical top of leveling pad elevation shall be shown in constant slope. Slope line shall be adjusted per project. Top of wall or coping elevation & stationing shall be shown in the developed elevation per project. Sample wall shown. Draw actual wall in elevation and plan per project.

- 1

Show the minimum embedment = maximum (2 feet; embedment based on Geotechnical Report and global stability requirements; and FHWA-NHI-10-024, Table 2-2).
- 2

Show theoretical top of leveling pad elevation on the plan based on minimum embedment requirements. Minimum embedment shall be provided in accordance with FHWA-NHI-10-024, Table 2-2, and Geotechnical Report.
- 3

The allowable bearing pressure and an angle of internal friction,  $\phi_f$ , for unimproved and improved ground where wall is to bear as determined by the Geotechnical Section and reported on the Foundation Investigation Geotechnical Report (FIGR) shall be shown on the plans. Show areas and locations of ground improvement along the wall where required, for example, using stationing or using changes in wall height. Provide cross-section of ground improvement based on FIGR. Provide any other geotechnical requirements in FIGR on plans.

Use the underlined portion from note EPG 751.50 J1.25a when limits of improved foundation ground is required by Geotechnical Section.
- 4

Show all boring locations on Plan.
- 5

Use for all large block MSE walls.
- 6

Use for all large block walls. Use for small block walls if applicable.
- 7

Use for small block walls unless the small block wall is to be built vertical.




NOTES TO ROADWAY AND BRIDGE DESIGNERS:

Excavation classes, quantities and pay items are the responsibility of District Design Division for including on the roadway 2B quantity sheets which is noted on the MSEW plans and required in accordance with Sec 720. All other quantities are the responsibility of the division responsible for the MSE wall plans.

If rock is not known to exist from a geotechnical report or study, place the following note on the plans:

"If rock is encountered in the proposed reinforced backfill area or wedge area of the MSE wall before or during excavation, the contractor shall immediately cease excavating and notify the engineer."

Otherwise, if rock is known to exist and it is to be excavated, then do not place above note on plans and determine the excavation class and estimate a rock quantity. For all Bridge Division MSE walls, Bridge Division and District Design Division shall coordinate in estimating excavation quantities when rock is known to exist from the geotechnical report and if rock is to be used as part of the wall backfill or excavated for MSE wall construction.



### General Notes Cont.:

- ⑦ Minimum 18" wide Geotextile strips shall be centered at vertical and horizontal joints of panel. Geotextile material shall be adhered to back face of panel using an adhesive compound supplied by the manufacturer. All edges of each fabric strip shall provide a positive seal. A minimum 18" overlap shall be provided between spliced filter fabric.
- Aluminized soil reinforcement shall have edges coated with coating material per manufacturer.
- Soil reinforcement shall be spaced to avoid roadway drop inlet behind wall.
- ③ Upper two layers of soil reinforcement shall be extended 3 feet beyond the lower layers when wall height is greater than or equal to 10 feet.
- ⑤ All steel soil reinforcements shall be separated from other metallic elements by at least 3 inches.
- The splay angle should be less than 15° and tensile capacity of splayed reinforcement shall be reduced by the cosine of the splay angle. Soil reinforcement shall clear the obstruction by at least 3 inches.
- No reinforcement shall be left unconnected to the wall face or arbitrarily cut/bent in the field to avoid the obstruction.
- ⑥ Where interference between the vertical obstruction and the soil reinforcement is unavoidable, the design of the wall near the obstruction may be modified using one of the alternatives in FHWA-NHI-10-24, Section 5.4.2. Show detail layout on the drawings. For wall designs with horizontal obstructions in reinforced soil mass, see FHWA-NHI-10-024, Section 5.4.3.

**Excavation:**  
Excavation quantities and pay items are given on the roadway plans.  
Excavation quantities are based on a soil reinforcement length of 12 ft.  
The soil reinforcement length may vary based upon the wall design  
selected by the contractor. Plan excavation quantities will be paid  
regardless of any actual quantities removed based on the soil  
reinforcement length and design selected.

- (1) Inverted U-shape reinforced capstone may be used in lieu of coping. Panel dowels for level-up concrete shall be required and provided by manufacturer. The dowels shall be field trimmed to clear the capstone by a minimum of 1 1/2 inches and a maximum of 2 1/2 inches.
- (2) Topmost layer of reinforcement shall be fully covered with select granular backfill for structural systems, as approved by the wall manufacturer, before placement of the Separation Geotextile.
- (3) Minimum ④ diameter perforated PVC or PE pipe.

Manufacturer shall show drain details on design plans to be submitted as shown on MoDOT MSE wall plans and/or roadway plans.

Contractor shall modify the drain details as shown if it will improve flow as may be the case for stepped leveling pad, and for an uneven ground line (approval of the engineer required).

Material Properties Used in Design				
Reinf. Fill/Select Granular Backfill		Active Force Computations		Foundation
$\phi^\circ$	$\gamma$ (pcf)	$\phi^\circ$	$\gamma$ (pcf)	$\phi^\circ$

Note: MSE Wall designer shall include table on shop drawings and provide values used in the design computations. Effects of cohesion shall be ignored unless approved by the engineer.

## DETAILS FOR GENERIC MSE WALL

(4) Select granular backfill shall extend a minimum of 12" beyond the end of all soil reinforcement. Where the angle,  $\theta$ , between the retained backfill excavation/fill line and the horizontal is less than  $90^\circ$ , the wedge area backfill between  $\theta$  and  $90^\circ$  shall be filled with select granular backfill for structural systems meeting the requirements of Section 1010.

- For  $(45^\circ + \Phi_b/3) < \Theta \leq 90^\circ$ , properties for retained backfill shall be used for active force computations.

- For  $\Theta \leq (45^\circ + \Phi_D/3)$ , contractor shall have the option to use select granular backfill,  $\Phi_r$ , or better aggregate material,  $\Phi_w$  for active force computations in the wedge area backfill. For active force computations, the angle of internal friction for wedge area backfill material,  $\Phi_r$  or  $\Phi_w$ , shall be limited to  $34^\circ$  unless determined otherwise in accordance with Section 1010. If  $\Phi_r$  or  $\Phi_w > 34^\circ$  is desired for wedge area backfill then test report shall be submitted with shop drawings.  $\Phi_r$  or  $\Phi_w$  shall not be greater than  $40^\circ$  for computations. Final configuration of this option shall be sent to Geotechnical Section for a new overall global stability analysis. Design  $\Phi_w$  shall be shown on the shop drawings if used.

The slope excavation line shall be benched and separation geotextile shall be placed between the retained backfill and either select granular backfill or better aggregate material, and between the select granular backfill and better aggregate material.

Show range of acceptable theta ( $\Theta$ ) angle on shop drawings which must be consistent with design computations and proposed construction of wall. Show active force computation properties on shop drawings and in design computations. Coordination between wall designer (manufacturer) and contractor is required before shop drawing submittal.

DATE PREPARED	
10/16/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	2
COUNTY	

[illegible]MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

MSEW\_02\_LFD2

Guidance

Standard Drawing Guidance (do not show on plans):

Revise notes and details per project as necessary.

For Modified Type A and Type B Gutter and Fence Post Connection details, see Missouri Standard Plans No. 607.11.

For Type A & Type B Gutter information, see Missouri Standard Plans No. 609.00.

See EPG 751.24.2.1 for drainage guidance.

- ①

Show the minimum embedment = maximum (2 feet; embedment based on Geotechnical Report and global stability requirements; and FHWA-NHI-10-024, Table 2-2).
- ②

Minimum soil reinforcement length shall be based on the following cases in accordance with EPG 751.6.2.17:

Maximum (0.7H, 8 ft, or FIGR) for a non-seismic design.

Maximum (0.7H, 8 ft, or FIGR, seismic loading requirement) for a seismic design.

Maximum (0.8H, 8 ft, or FIGR) for a sloping backfill surcharge case.

Soil reinforcement length shall be greater than or equal to as required for a stable feature wall for strong/stable rock case.

Where,

H = Height of the wall as measured from the top of the leveling pad to the top of the wall.

FIGR = Foundation Investigation Geotechnical Report

③

Use for MSE walls in Seismic Categories B, C & D.

④

District Design Division to verify 6" diameter pipe or increase diameter. Minimum pipe diameter shall be 6".
- ⑤

Use for MSE Walls when there may be contact between dissimilar metals.

⑥


Use for MSE Walls when there may be vertical and/or horizontal obstructions in reinforced soil mass.

⑦

Use for all large block MSE walls.


⑧

Do not show values in the plan details. MSE wall designer shall include this table on shop drawings and provide values used in the design computations.




TYPICAL SECTION THRU  
LARGE BLOCK WALL AT CULVERT

Notes: Vertical joint in MSE wall shall be located at each exterior culvert wall.



### FENCE POST CONNECTION BEHIND WALL (WITHOUT GUTTER)



TYPICAL SECTION THRU  
LARGE BLOCK WALL UNDER BRIDGE

Note: For additional information, see "TYPICAL SECTION THRU LARGE BLOCK WALL SHOWING FILTER CLOTH".

- (1) Inverted U-shape reinforced caststone may be used in lieu of coping. Panel dowels for level-up concrete shall be required and provided by manufacturer. The dowels shall be field trimmed to clear the caststone by a minimum of 1 1/2 inches and a maximum of 2 1/2 inches.
- (2) Topmost layer of reinforcement shall be fully covered with select granular backfill for structural systems, as approved by the wall manufacturer, before placement of the Separation Geotextile.
- (3) Minimum 2 diameter perforated PVC or PE pipe.  
Manufacturer shall show drain details on design plans to be submitted as shown on MoDOT MSE wall plans and/or roadway plans.  
Contractor shall modify the drain details as shown if it will improve flow as may be the case for stepped leveling pad, and for an uneven ground line (approval of the engineer required).
- (4) See bridge plans.

Standard Drawing Guidance (do not show on plans):

Revise notes and details per project as necessary.

Gutter type should be selected at core team meeting.

For Modified Type A and Modified Type B Gutter and Fence Post Connection Details, see Missouri Standard Plans No. 607.11.

For Type A and Type B Gutter information, see Missouri Standard Plans No. 609.00.

See EPG 751.24.2.1 for drainage guidance.

- ① For bridge lengths less than or equal to 200 feet, use 4'-6" minimum setback which is based on the use of 18" inside diameter pipe pile spacers and FHWA-NHI-10-024, Figure 5-17C. For larger than 18" diameter pipe pile spacers, increase clear space between MSE wall & front face of the end bent beam such that no soil reinforcement is skewed more than 15°. For bridge lengths greater than 200 feet, use 5'-6" minimum setback which is based on the use of 24" inside diameter pipe pile spacers.
- ② District Design Division to verify 6" diameter pipe or increase diameter. Minimum pipe diameter shall be 6".
- ③ When rock is anticipated within 5 feet below the MSE wall leveling pad, embed pipe pile spacers at least 12" into rock and bear pile on the rock.
- ④ For bridge length less than or equal to 200 feet, add "(See special provisions)". For bridge length greater than 200 feet, add pipe diameter.
- ⑤ For walls parallel to abutment, provide actual slope H:V. Otherwise, replace leadered note with "Varies (4)".







STANDARD DRAWING GUIDANCE (do not show on plans):

For slab thickness < 8 1/2", check shear connector stud length for clearance to flange or diaphragm and adjust length as necessary. See Structural Project Manager.

Use standard detailing note H5.55 when polymer concrete wearing surface is used with a preformed compression seal.

Remove non-applicable rows in table.



Ⓐ Piece angle length to center of first slotted hole.


Ⓑ Use squared, left advanced or right advanced Part Plan as needed.

Ⓒ = 3/4" (Min.) @ 60°. Verify only.

Ⓓ = Ⓐ @ 60°+ 3/4" (Min.). Verify only.

Delete panels for CIP slab.





GENERAL NOTES:

Table of Transverse Preformed Compression Seal Expansion Joint System Dimensions										
Seal Width Perpendicular to Joint	Height ③	Movement Capacity (Normal to Joint)	Min. Joint Width (Normal to Joint)	Max. Joint Width (Normal to Joint)	Allowed Installation Gap Normal to Joint at RDWY Surface @ Air/Surface Temperature ②				Manufacturer	Seal Name
					①					
					@ 40°F	@ 50°F	@ 60°F	@ 70°F		
2.25"	Manufacturer's Recommended Height	0.85"	1.06"	1.91"	XXX	XXX	XXX	XXX		
2.5"	Manufacturer's Recommended Height	1.00"	1.13"	2.13"	XXX	XXX	XXX	XXX		
3.0"	Manufacturer's Recommended Height	1.30"	1.25"	2.55"	XXX	XXX	XXX	XXX		
3.5"	Manufacturer's Recommended Height	1.60"	1.38"	2.98"	XXX	XXX	XXX	XXX		
4.0"	Manufacturer's Recommended Height	1.83"	1.57"	3.40"	XXX	XXX	XXX	XXX		
4.5"	Manufacturer's Recommended Height	2.27"	1.56"	3.83"	XXX	XXX	XXX	XXX		

Note: Depth of seal shall not be less than width of seal.

② The installation temperature shall be taken as the actual air temperature averaged over the 24-hour period immediately preceding installation.

STANDARD DRAWING GUIDANCE (do not show on plans):

For slab thickness < 8 1/2", check shear connector stud length for clearance to flange or diaphragm and adjust length as necessary. See Structural Project Manager.

Use standard detailing note H5.55 when polymer concrete wearing surface is used with a preformed compression seal.


Remove non-applicable rows in table.

Ⓐ Use squared, left advanced or right advanced Part Plan as needed.


Ⓑ = 3/4" (Min.) @ 60°. Verify only.

Ⓒ = Ⓐ @ 60°+ 3/4" (Min.). Verify only.


Delete panels for CIP slab.




Left Advanced




Right Advanced




PART SECTION A-A



PART PLAN




DETAIL A




PART SECTION B-B

\* Extend preformed compression seal 3" past the edge of slab (Typ.)



PART ELEVATION OF BARRIER



SECTION THRU DEVICE

GENERAL NOTES:


Expansion joint system shall be fabricated in one section, except for staged construction and when the length is over 50 feet. A complete joint penetration groove welded splice shall be required. Welds shall be ground flush to provide a smooth surface. The expansion joint system shall be fabricated and installed to the crown and grade of the roadway.

Structural steel for the expansion joint system shall be ASTM A709 Grade 36. Anchors for the expansion joint system shall be in accordance with Sec 1037. Preformed compression seal expansion joint system shall be in accordance with Sec 717.

Structural steel for the expansion joint system shall be coated with a minimum of two coats of inorganic zinc primer to provide a total dry film thickness of 4 mils minimum, 6 mils maximum, or galvanized in accordance with ASTM A123. Anchors need not be protected from overspray.

Concrete shall be forced under armor angle and around anchors. Proper consolidation of the concrete shall be achieved by localized internal vibration.

Longitudinal reinforcing steel shall be placed so that ends shall be 1" from the vertical leg of the angle at the expansion joint system.



DETAIL B

Table of Transverse Preformed Compression Seal Expansion Joint System Dimensions										
Seal Width Perpendicular to Joint	Height ③	Movement Capacity (Normal to Joint)	Min. Joint Width (Normal to Joint)	Max. Joint Width (Normal to Joint)	Allowed Installation Gap Normal to Joint at RDWY Surface @ Air/Surface Temperature ②				Manufacturer	Seal Name
					①					
					@ 40°F	@ 50°F	@ 60°F	@ 70°F		
2.25"	Manufacturer's Recommended Height	0.85"	1.06"	1.91"	XXX	XXX	XXX	XXX		
2.5"	Manufacturer's Recommended Height	1.00"	1.13"	2.13"	XXX	XXX	XXX	XXX		
3.0"	Manufacturer's Recommended Height	1.30"	1.25"	2.55"	XXX	XXX	XXX	XXX		
3.5"	Manufacturer's Recommended Height	1.60"	1.38"	2.98"	XXX	XXX	XXX	XXX		
4.0"	Manufacturer's Recommended Height	1.83"	1.57"	3.40"	XXX	XXX	XXX	XXX		
4.5"	Manufacturer's Recommended Height	2.27"	1.56"	3.83"	XXX	XXX	XXX	XXX		

Note: Depth of seal shall not be less than width of seal.

Size of armor angle: Vertical leg of angle shall be a minimum of Manufacturer's Recommended Height ③ + 3/4". Horizontal leg of angle shall be a minimum of 3". Minimum thickness of angle shall be 1/2".

② The installation temperature shall be taken as the actual air temperature averaged over the 24-hour period immediately preceding installation.

MoDOT Construction personnel will record the manufacturer and seal name that was used.

Detailed  
Checked

PREFORMED COMPRESSION SEAL EXPANSION JOINT SYSTEM AT INTERMEDIATE BENT NO. \_

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

DATE PREPARED 10/16/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 000
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)

STANDARD DRAWING GUIDANCE (do not show on plans):

For slab thickness < 8 1/2", check shear connector stud length for clearance to flange or diaphragm and adjust length as necessary. See Structural Project Manager.

Use standard detailing note H5.55 when polymer concrete wearing surface is used with a preformed compression seal.



Remove non-applicable rows in table.

Ⓐ Use squared, left advanced or right advanced Part Plan as needed.

Ⓑ = 3/4" (Min.) @ 60° Verify only.

Ⓒ = Ⓐ @ 60°+ 3/4" (Min.) Verify only.

Delete panels for CIP slab.








Standard Drawing Guidance (do not show on plans):

Choose the appropriate Plan of Flange.

Detail of Bolted Field Splice shown is for flange splices with a uniform hole pattern only, detail will need to be modified to accommodate flange splices with a staggered hole pattern (14" & 15" flanges).

- ① Use Type 3 for weathering steel bolted connections and Type 1 for painted or galvanized steel bolted connections.



DETAIL OF BOLTED FIELD SPLICE

- Bolts shall be 7/8-inch diameter ASTM F3125 Grade A325  
① Type 1 Type 3 in 15/16-inch diameter holes.  
Contact surfaces shall be in accordance with Sec 1081 for surface preparation.

TABLE OF DIMENSIONS - FIELD SPLICE													
LOCATION	A	B	C	D	E	F	G	I	J	L	N	P	Q
*	*	*	*	*	*	*	*	*	*	*	*	*	*

DESCRIPTION













DATE


MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION




105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-273-6636)

## PGS02      Alternate Details






GALVANIZED CLOSED ENDED CAST-IN-PLACE (CECIP) CONCRETE PILE WITHOUT PILE POINT REINFORCEMENT




STEEL PIPE PILE SPLICE  
\* Galvanizing material shall be omitted or removed one inch clear of weld locations in accordance with Sec 702.




CRUCIFORM PILE POINT

Note: Cost of closure plate is included with cast-in-place concrete pile.




ELEVATION B-B




MANUFACTURED CONICAL PILE POINT  
(Omit closure plate)


\*\* If the conical pile point is not pre-beveled, place a 3/8" bevel at 40 degrees on the pipe.



T1 PLATE DETAILS



T2 PLATE DETAILS  
(2 REQUIRED)



SECTION C-C

CRUCIFORM PILE POINT REINFORCEMENT

GALVANIZED CLOSED ENDED CAST-IN-PLACE (CECIP) CONCRETE PILE

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

① Cruciform Pile Point Reinforcement Data				
D1, CECIP Pile (O.D.)	14"	16"	20"	24"
B1	14"	16"	20"	24"
B2	6"	7"	8 7/8"	10 5/8"
B3	5 7/8"	6 7/8"	8 3/4"	10 1/2"
B4	6 5/8"	7 5/8"	9 1/2"	11 1/4"
B5	2"	2"	2 1/4"	2 3/4"
B6	3/4"	3/4"	1"	1 1/2"
H1	9 1/8"	10 1/2"	13"	15 3/8"
H2	8 1/8"	9 1/2"	12"	14 3/8"
H3	8 3/8"	9 3/4"	12 1/4"	14 5/8"
T1 and T2 Plate Thickness	3/4"	3/4"	1"	1 1/2"

① Galvanized Closed Ended Cast-In-Place (CECIP) Concrete Pile Data				
Bent Number	1	2	3	4
D1, CECIP Pile (O.D.)	x			
Min. Nominal Wall Thickness	x			
Closure Plate Thickness	x			
Pile Point Reinforcement	x			
Vertical Bars	x			
L1, Length of Vertical Bars	x			
Upper Stirrup Bars	x			
Lower Stirrup Bars	x			

Notes:

Welded or seamless steel shell (pipe) shall be ASTM A252 Grade 3 (fy = 45,000 psi).

Concrete for cast-in-place pile shall be Class B-1.

Steel for closure plate shall be ASTM A709 Grade 50.

Steel for cruciform pile point reinforcement shall be ASTM A709 Grade 50.

③ Steel casting for conical pile point reinforcement shall be ASTM A27 Grade 65-35 ASTM A148 Grade 90-60.

The minimum wall thickness of any spot or local area of any type shall not be more than 12.5% under the specified nominal wall thickness.

The contractor shall determine the pile wall thickness required to avoid damage from all driving activities, but wall thickness shall not be less than the minimum specified. No additional payment will be made for furnishing a thicker pile wall than specified on the plans.

Closure plate shall not project beyond the outside diameter of the pipe pile. Satisfactory weldments may be made by beveling tip end of pipe or by use of inside backing rings. In either case, proper gaps shall be used to obtain weld penetration full thickness of pipe. Payment for furnishing and installing closure plate will be considered completely covered by the contract unit price for Galvanized Cast-In-Place Concrete Piles.

Splices of pipe for cast-in-place concrete pile shall be made watertight and to the full strength of the pipe above and below the splice to permit hard driving without damage. Pipe damaged during driving shall be replaced without cost to the state. Pipe sections used for splicing shall be at least 5 feet in length.

⑤ At the contractor's option, the hooks of vertical bars embedded in the beam cap may be oriented inward or outward.

The hooks of vertical bars embedded in the beam cap should not be turned outward, away from the pile core.

The hook of vertical bars embedded in the pile cap footing should be oriented outward for all seismic categories.


Closure plate need not be galvanized.

Reinforcing steel for cast-in-place piles is included in the Bill of Reinforcing Steel.

All reinforcement for cast-in-place pile is included in the estimated quantities for bents.

For Foundation Data table, see Sheet No. .

Detailed  
Checked

DATE PREPARED <b>10/16/2023</b>	
ROUTE	STATE <b>MO</b>
DISTRICT <b>BR</b>	SHEET NO. <b>1</b>
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
 105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	

Standard Drawing Guidance (do not show on plans):

Do not use 20" and 24" diameter closed ended cast-in-place (CECIP) concrete pile without approval of Structural Project Manager or Liaison.

①

Typical Data for CECIP Piles				
D1, CECIP Pile (O.D.) (by design)	14"	16"	20"	24"
Min. Nominal Wall Thickness (by design)	1/2" (See EPG 751.36.2.2.2 for commonly available nominal wall thicknesses.)			
Closure Plate Thickness ④	3/4"		1"	1 1/2"
Pile Point Reinforcement	"Cruciform", "Conical" or "None"			
Vertical Bars	6-#5-Vxxx	6-#6-Vxxx	8-#6-Vxxx	12-#6-Vxxx
L1, Length of Vertical Bars	5' -3"		7' -3"	
Upper Stirrup Bars	3-#4-Pxxx			
Lower Stirrup Bars				
	5-#4-Pxxx		7-#4-Pxxx	

②

For LFD seismic performance category (SPC) A and LRFD seismic design category (SDC) A, minimum number of vertical bars, size and length and seismic stirrup bar information is provided in Galvanized Closed Ended Cast-In-Place (CECIP) Concrete Pile Data. Modify reinforcement size, length of vertical bars (L1), number of vertical bars, number of stirrup bars, and bar mark information as needed for specific project.

Min. L1 = 5'-3" for 14"Ø and 16"Ø CECIP &  
7'-3" for 20"Ø and 24"Ø CECIP

Min. Lower Stirrup Bars = 5-#4 for 14"Ø and 16"Ø CECIP &  
7-#4 for 20"Ø and 24"Ø CECIP

Min. Vertical Bars = 6-#5 for 14"Ø CECIP,  
6-#6 for 16"Ø CECIP,  
8-#6 for 20"Ø CECIP &  
12-#6 for 24"Ø CECIP

For SPC B, C and D, modify reinforcement as needed to meet AASHTO 17th edition (LFD) and for SDC B, C and D, modify reinforcement as needed to meet AASHTO Guide Specification for LRFD Seismic Bridge Design (SGS).

③

For hard driving conditions consider ASTM A148 Grade 90-60. If conical pile points are not used, this note may be removed.

④


Minimum Closure Plate Thickness		
CECIP Pile (O.D.), D1	No pile point reinforcement required	Cruciform pile point reinforcement required
14"	3/4"	3/4"
16"	3/4"	3/4"
20"	3/4"	1"
24"	3/4"	1 1/2"


⑤

Use appropriate note based on seismic category (See EPG 751.50, Notes G5a9a & G5a9b)


⑥

These details of bar array 6, 8 and 12 count, can be used as needed in sheet details "Section A-A" & "DETAIL OF SEISMIC STIRRUP BAR" by using centroid as the handle.







GALVANIZED OPEN ENDED CAST-IN-PLACE (OECIP)  
CONCRETE PILE  
WITHOUT PILE POINT REINFORCEMENT




MANUFACTURED OPEN ENDED  
CUTTING SHOE ( INSIDE FLANGE )



SECTION A-A (5)



DETAIL OF SEISMIC STIRRUP BAR (5)



STEEL PIPE PILE SPLICE

\* Galvanizing material shall be omitted or removed one inch clear of weld locations in accordance with Sec 702.

1 GALVANIZED OPEN ENDED CAST-IN-PLACE (OECIP) CONCRETE PILE DATA				
Bent Number	1	2	3	4
D1, OECIP Pile (O.D.)	x			
Min. Nominal Wall Thickness	x			
Pile Point Reinforcement	x			
Min. Pile Cleanout Penetration (Elev.)	x			
Vertical Bars	x			
L1, Length of Vertical Bars	x			
Upper Stirrup Bars	x			
Lower Stirrup Bars	x			

Notes:

Welded or seamless steel shell (pipe) shall be ASTM A252 Grade 3 ( $f_y = 45,000$  psi).

Open ended pile shall be augered out to the minimum pile cleanout penetration elevation and filled with Class B-1 concrete.

Concrete for cast-in-place pile shall be Class B-1.

Steel casting for open ended cutting shoe pile point reinforcement shall be ASTM A27 Grade 65-35 ASTM A148 Grade 90-60.

The minimum wall thickness of any spot or local area of any type shall not be more than 12.5% under the specified nominal wall thickness.

The contractor shall determine the pile wall thickness required to avoid damage from all driving activities, but wall thickness shall not be less than the minimum specified. No additional payment will be made for furnishing a thicker pile wall than specified on the plans.

Splices of pipe for cast-in-place pipe pile shall be made watertight and to the full strength of the pipe above and below the splice to permit hard driving without damage. Pipe damaged during driving shall be replaced without cost to the state. Pipe sections used for splicing shall be at least 5 feet in length.

At the contractor's option, the hooks of vertical bars embedded in the beam cap may be oriented inward or outward.

The hooks of vertical bars embedded in the beam cap should not be turned outward, away from the pile core.

The hooks of vertical bars embedded in the pile cap footing should be oriented outward for all seismic categories.

Reinforcing steel for cast-in-place pile is included in the Bill of Reinforcing Steel.

All reinforcement for cast-in-place pile is included in the estimated quantities for bents.

For Foundation Data table, see Sheet No. .

DATE PREPARED	
10/16/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
BR	2
COUNTY	

[illegible]MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

Standard Drawing Guidance (do not show on plans):

Do not use 20" and 24" diameter open ended cast-in-place (OECIP) concrete pile without approval of Structural Project Manager or Liaison.

①

Typical Data for OECIP Piles				
D1, OECIP Pile (O.D.) (by design)	14"	16"	20"	24"
Min. Nominal Wall Thickness (by design)	1/2" (See EPG 751.36.2.2.2 for commonly available nominal wall thicknesses.)			
Pile Point Reinforcement	"**" (add note below) or "None"			
Min. Pile Cleanout Penetration (Elev.)	300	302	282	295
Vertical Bars	6-#5-Vxxx	6-#6-Vxxx	8-#6-Vxxx	12-#6-Vxxx
L1, Length of Vertical Bars	5'-3"		7'-3"	
Upper Stirrup Bars	3-#4-Pxxx			
Lower Stirrup Bars	5-#4-Pxxx		7-#4-Pxxx	

\*\* Open ended cutting shoe

② For LFD seismic performance category (SPC) A and LRFD seismic design category (SDC) A, minimum number of vertical bars, size and length and seismic stirrup bar information is provided in Galvanized Open Ended Cast-In-Place (OECIP) Concrete Pile Data. Modify reinforcement size, length of vertical bars (L1), number of vertical bars, number of stirrup bars, and bar mark information as needed for specific project.

Min. L1 = 5'-3" for 14"Ø and 16"Ø OECIP &

7'-3" for 20"Ø and 24"Ø OECIP

Min. Lower Stirrup Bars = 5-#4 for 14"Ø and 16"Ø OECIP &

7-#4 for 20"Ø and 24"Ø OECIP

Min. Vertical Bars = 6-#5 for 14"Ø OECIP,

6-#6 for 16"Ø OECIP,

8-#6 for 20"Ø OECIP &


12-#6 for 24"Ø OECIP

For SPC B, C and D, modify reinforcement as needed to meet AASHTO 17th edition (LFD) and for SDC B, C and D, modify reinforcement as needed to meet AASHTO Guide Specification for LRFD Seismic Bridge Design (SGS).

③ For hard driving conditions consider ASTM A148 Grade 90-60. If cutting shoe is not used, this note may be removed.

④ Use appropriate note based on seismic category (See EPG 751.50, Notes G5b7a & G5b7b)

⑤ These details of bar array 6, 8 and 12 count, can be used as needed in sheet details "Section A-A" & "DETAIL OF SEISMIC STIRRUP BAR" by using centroid as the handle.



Standard Drawing Guidance (Do not show on plans):

Sheet for piles WITHOUT dynamic pile testing.

Draw layout with bents labeled and provide numbering of piles. List in the tables the piles grouped by bents with the name of the bent included in the remarks column as a header for the piles located at that bent. Provide two blank rows after the last pile of each bent grouping to allow for additions in the field.

Combine with As-Built Drilled Shaft Data if both piles and drilled shafts are shown on same sheet.

PART PLAN SHOWING PILE NUMBERING FOR RECORDING AS-BUILT PILE DATA

[illegible][illegible][illegible]

Note:  
Indicate in remarks column:  
A. Pile type and grade  
B. Batter  
C. Driven to practical refusal

This sheet to be completed by MoDOT construction personnel.

[illegible]



Standard Drawing Guidance (Do not show on plans):

Sheet for piles WITH dynamic pile testing.

Draw layout with bents labeled and provide numbering of piles. List in the tables the piles grouped by bents with the name of the bent included in the remarks column as a header for the piles located at that bent. Provide two blank rows after the last pile of each bent grouping to allow for additions in the field.

Combine with As-Built Drilled Shaft Data if both piles and drilled shafts are shown on same sheet.

PART PLAN SHOWING PILE NUMBERING FOR RECORDING AS-BUILT PILE DATA

[illegible][illegible][illegible]

Note:  
Indicate in remarks column:  
A. Pile type and grade  
B. Batter  
C. Driven to practical refusal  
D. PDA test pile  
E. Minimum tip elevation controlled  
(Use when actual blow count is less than PDA blow count due to minimum tip elevation requirement. A plus sign (+) shall be placed after the PDA nominal axial compressive resistance value indicating actual value is higher than PDA value.)

This sheet to be completed by MoDOT construction personnel.

[illegible]



STANDARD DRAWING GUIDANCE (do not show on plans):  
(Turn off Level Bridge-Guidance to hide guidance)

- ①

Actual strand arrangement, bent up strands, and debonding (if any) is by design (top two strands are required). Add or remove symbols and instructions as required. Strands may be placed continuously across beam (eliminating 4" space), but dimension to drain hole in Part Plan shall be revised to 10".
- ②

Revise if #5 is required. Use 6'-7" for #5-S1 actual length and 6'-1" for #5-S2 actual length.
- ③

Splices shown only when necessary (girder length > 60'-2"). Use 2'-1" lap for #4 & 2'-7" lap for #5.

When lap is unnecessary:

- Delete grouped elements.

- Extend A bars to C Beam.

- Revise 10 to 5 A1 bars & 8 to 4 A2 bars.
- ④

Interior diaphragm & vent pipe shall be shown only when necessary (when structure may be submerged).

When not necessary:

- Delete the two grouped elements.





- In Half Elev. extend hidden lines to C Beam.

- In Part Plan revise remaining dimension to full length of void.
- ⑤

Revise minimum dimension if required by design.
- ⑥





By design. Typically 30.98 kips per 0.5" strand & 43.94 kips per 0.6" strand, rounded to nearest whole kip.
- ⑦

Strand location not available when vent pipe is required.



Detailed Checked

Note: This drawing is not to scale. Follow dimensions.



BILL OF REINFORCING STEEL - EACH BEAM									
NO.	SIZE & MARK	ACTUAL LENGTH	SHAPE	BENDING DIAGRAM					
10	5 A1	X'-X"	20	(S1) 3'-7"					
8	4 A2	X'-X"	20	(S4) 3'-8½"					
				(S6) 2'-8½"					
X	4 C1	3'-7"	20	(S1, S4, S6) (S5, S7)					
X	4 S1	6'-4"	10	SHAPE 10					
X	4 S2	6'-2"	51	SHAPE 20					
18	5 S4	6'-8"	10	SHAPE 10					
18	5 S5	5'-10"	10	SHAPE 21					
2	5 S6	5'-8"	10	SHAPE 50					
2	5 S7	4'-10"	10	SHAPE 51					
12	6 U1	4'-3"	10						
4	4 U2	8'-4"	21						

All dimensions are out to out. Use symmetry for dimensions not shown.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

Actual lengths are measured along centerline of bar to the nearest inch.

Minimum clearance to reinforcing shall be 1", unless otherwise shown.

All reinforcement shall be Grade 60.

All S2 bars shall be epoxy coated.

**General Notes:**

Concrete for prestressed beams shall be Class A-1 with  $f'c =$  psi and  $f'ci =$  psi.

Use strands, #0 Grade 270, with an initial prestress force of 6 kips.

Pretensioned members shall be in accordance with Sec 1029.

Fabricator shall be responsible for location and design of lifting devices.

Exterior and interior beams are the same except: coil ties, application of bond breaker, coil inserts for slab drains.

For Beam Camber Diagram, see Sheet No. \_\_.

For location of coil inserts at slab drains, see Sheet No. \_\_.

For location of coil ties at concrete bent diaphragms, see Sheets No. \_\_ and \_\_.

SPREAD BOX BEAMS - SPANS (X-X) AND (X-X)

Sheet No. of

DATE PREPARED  
5/4/2023

ROUTE  
STATE  
MO

DISTRICT  
SHEET NO.  
2

COUNTY

JOB NO.

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

- STANDARD DRAWING GUIDANCE (do not show on plans):  
(Turn off Level Bridge-Guidance to hide guidance)
- ①

Actual strand arrangement, bent up strands, and debonding (if any) is by design (top two strands are required). Add or remove symbols and instructions as required. Strands may be placed continuously across beam (eliminating 4" space), but dimension to drain hole in Part Plan shall be revised to 10".
- ②

Revise if #5 is required. Use 6'-7" for #5-S1 actual length and 6'-1" for #5-S2 actual length.
- ③

Splices shown only when necessary (girder length > 60'-2"). Use 2'-1" lap for #4 & 2'-7" lap for #5.

When lap is unnecessary:

- Delete grouped elements.

- Extend A bars to C Beam.

- Revise 10 to 5 A1 bars & 8 to 4 A2 bars.
- ④

Interior diaphragm & vent pipe shall be shown only when necessary (when structure may be submerged).

When not necessary:

- Delete the two grouped elements.


- In Half Elev. extend hidden lines to C Beam.

- In Part Plan revise remaining dimension to full length of void.
- ⑤

Revise minimum dimension if required by design.
- ⑥

By design. Typically 30.98 kips per 0.5" strand & 43.94 kips per 0.6" strand, rounded to nearest whole kip.
- ⑦


Strand location not available when vent pipe is required.




## DIMENSIONS

(1) Fabricator shall apply a bond breaker to this region excluding where joint filler will be applied.


(2) 1½" (Typ.) (¾" Optional)



HALF ELEVATION




PART PLAN




BEARING PLATE

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.




STRANDS AT BEAM ENDS




ELEVATION A-A

Strands not shown for clarity.



SECTION B-B

SECTION C-C



COIL TIES

[illegible]

All dimensions are out to out. Use symmetry for dimensions not shown.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

Actual lengths are measured along  
centerline of bar to the nearest  
inch.

Minimum clearance to reinforcing  
shall be 1", unless otherwise shown.

All reinforcement shall be Grade 60.

All S2 bars shall be epoxy coated.

General Notes:

Concrete for prestressed beams shall be Class A-1 with  $f'c =$  psi and  $f'ci =$  psi.

6. Use strands, "Ø Grade 270, with an initial prestress force of kips.

Pretensioned members shall be in accordance with Sec 1029.

Fabricator shall be responsible for location and design of lifting devices.

Exterior and interior beams are the same except: coil ties, application of bond breaker, coil inserts for slab drains.

For Beam Camber Diagram, see Sheet  
No. .

For location of coil inserts at  
slab drains, see Sheet No. .

For location of coil ties at  
concrete bent diaphragms, see  
Sheets No.      and      .

[illegible]

- STANDARD DRAWING GUIDANCE (do not show on plans):  
(Turn off Level Bridge-Guidance to hide guidance)
- ①

Actual strand arrangement, bent up strands, and debonding (if any) is by design (top two strands are required). Add or remove symbols and instructions as required. Strands may be placed continuously across beam (eliminating 4" space), but dimension to drain hole in Part Plan shall be revised to 10".
- ②

Revise if #5 is required. Use 7'-3" for #5-S1 actual length and 6'-9" for #5-S2 actual length.
- ③

Splices shown only when necessary (girder length > 60'-2"). Use 2'-1" lap for #4 & 2'-7" lap for #5.

When lap is unnecessary:

- Delete grouped elements.

- Extend A bars to  $\text{\textcircled{C}}$  Beam.

- Revise 10 to 5 A1 bars & 8 to 4 A2 bars.
- ④

Interior diaphragm & vent pipe shall be shown only when necessary (when structure may be submerged).

When not necessary:

- Delete the two grouped elements.

- In Half Elev. extend hidden lines to  $\text{\textcircled{C}}$  Beam.


- In Part Plan revise remaining dimension to full length of void.
- ⑤

Revise minimum dimension if required by design.
- ⑥

By design. Typically 30.98 kips per 0.5" strand & 43.94 kips per 0.6" strand, rounded to nearest whole kip.
- ⑦

Strand location not available when vent pipe is required.






DIMENSIONS

(1) Fabricator shall apply a bond breaker to this region excluding where joint filler will be applied.

(2) 1½" (Typ.) (¾" Optional)



STRAND ARRANGEMENT


All strands are fully bonded unless otherwise noted.

+ Indicates prestressing strand.

○ Indicates cut and shop bend with 2'-0" projection.

□ Indicates debonded for X'-X" from end of beam.

△ Indicates debonded for X'-X" from end of beam.



STRANDS AT BEAM ENDS

BILL OF REINFORCING STEEL - EACH BEAM									
NO.	SIZE & MARK	ACTUAL LENGTH	SHAPE	BENDING DIAGRAM					
10	5 A1	X'-X"	20	(S1) 3'-7"					
8	4 A2	X'-X"	20	(S4) 3'-8½"					
				(S5) 3'-8½"					
				(S6) 2'-8½"					
				(S7) 2'-8½"					
				(S1, S4, S6) (S5, S7)					
				SHAPE 10					
				SHAPE 21					
				SHAPE 50					
				SHAPE 51					

All dimensions are out to out. Use symmetry for dimensions not shown.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

Actual lengths are measured along centerline of bar to the nearest inch.

Minimum clearance to reinforcing shall be 1", unless otherwise shown.

All reinforcement shall be Grade 60.

All S2 bars shall be epoxy coated.

General Notes:

Concrete for prestressed beams shall be Class A-1 with f'c = psi and f'ci = psi.

Use strands, #0 Grade 270, with an initial prestress force of kips.

Pretensioned members shall be in accordance with Sec 1029.


Fabricator shall be responsible for location and design of lifting devices.

Exterior and interior beams are the same except: coil ties, application of bond breaker, coil inserts for slab drains.

For Beam Camber Diagram, see Sheet No. \_\_.

For location of coil inserts at slab drains, see Sheet No. \_\_.

For location of coil ties at concrete bent diaphragms, see Sheets No. \_\_ and \_\_.




HALF ELEVATION


Dimensions taken along C Beam.

(5) 2 Spa. @ 4"

Strands not shown for clarity.




ELEVATION A-A



PART PLAN

Mirror about C Beam for left advanced.



BEARING PLATE

Detailed Checked

Note: This drawing is not to scale. Follow dimensions.

SPREAD BOX BEAMS - SPANS (X-X) AND (X-X)

Sheet No. of

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION



105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

- STANDARD DRAWING GUIDANCE (do not show on plans):  
(Turn off Level Bridge-Guidance to hide guidance)
- ①

Actual strand arrangement, bent up strands, and debonding (if any) is by design (top two strands are required). Add or remove symbols and instructions as required. Strands may be placed continuously across beam (eliminating 4" space), but dimension to drain hole in Part Plan shall be revised to 10".
- ②

Revise if #5 is required. Use 7'-3" for #5-S1 actual length and 6'-9" for #5-S2 actual length.
- ③

Splices shown only when necessary (girder length > 60'-2"). Use 2'-1" lap for #4 & 2'-7" lap for #5.

When lap is unnecessary:

- Delete grouped elements.

- Extend A bars to  $\text{\textcircled{C}}$  Beam.

- Revise 10 to 5 A1 bars & 8 to 4 A2 bars.
- ④

Interior diaphragm & vent pipe shall be shown only when necessary (when structure may be submerged).

When not necessary:

- Delete the two grouped elements.





- In Half Elev. extend hidden lines to  $\text{\textcircled{C}}$  Beam.

- In Part Plan revise remaining dimension to full length of void.
- ⑤

Revise minimum dimension if required by design.
- ⑥





By design. Typically 30.98 kips per 0.5" strand & 43.94 kips per 0.6" strand, rounded to nearest whole kip.
- ⑦

Strand location not available when vent pipe is required.



Detailed Checked

Note: This drawing is not to scale. Follow dimensions.



BILL OF REINFORCING STEEL - EACH BEAM					BENDING DIAGRAM	
NO.	SIZE & MARK	ACTUAL LENGTH	SHAPE			
10	5 A1	X'-X"	20			
8	4 A2	X'-X"	20			
X	4 C1	3'-7"	20			
X	4 S1	7'-5"	10			
X	4 S2	7'-10"	51			
X	4 S3	4'-6"	50			
18	5 S4	7'-4"	10			
18	5 S5	7'-4"	10			
12	6 U1	5'-1"	10			
6	4 U2	7'-4"	10			

All dimensions are out to out. Use symmetry for dimensions not shown.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

Actual lengths are measured along centerline of bar to the nearest inch.

Minimum clearance to reinforcing shall be 1", unless otherwise shown.

All reinforcement shall be Grade 60.

All S2 bars shall be epoxy coated.

**General Notes:**

Concrete for prestressed beams shall be Class A-1 with  $f'c =$  psi and  $f'ci =$  psi.

Use strands, #0 Grade 270, with an initial prestress force of kips.

Pretensioned members shall be in accordance with Sec 1029.

Fabricator shall be responsible for location and design of lifting devices.

Exterior and interior beams are the same except: coil ties, application of bond breaker, coil inserts for slab drains.

For Beam Camber Diagram, see Sheet No. \_\_.

For location of coil inserts at slab drains, see Sheet No. \_\_.

For location of coil ties at concrete bent diaphragms, see Sheets No. \_\_ and \_\_.

DATE PREPARED  
5/4/2023

ROUTE  
STATE  
MO

DISTRICT  
SHEET NO.  
5

COUNTY

JOB NO.

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

- STANDARD DRAWING GUIDANCE (do not show on plans):  
(Turn off Level Bridge-Guidance to hide guidance)
- ①

Actual strand arrangement, bent up strands, and debonding (if any) is by design (top two strands are required). Add or remove symbols and instructions as required. Strands may be placed continuously across beam (eliminating 4" space), but dimension to drain hole in Part Plan shall be revised to 10".
- ②

Revise if #5 is required. Use 7'-4" for #5-S1 actual length and 7'-9" for #5-S2 actual length.
- ③

Splices shown only when necessary (girder length > 60'-2"). Use 2'-1" lap for #4 & 2'-7" lap for #5.

When lap is unnecessary:

- Delete grouped elements.

- Extend A bars to C Beam.

- Revise 10 to 5 A1 bars & 8 to 4 A2 bars.
- ④

Interior diaphragm & vent pipe shall be shown only when necessary (when structure may be submerged).

When not necessary:

- Delete the two grouped elements.

- In Half Elev. extend hidden lines to C Beam.

- In Part Plan revise remaining dimension to full length of void.
- ⑤

Revise minimum dimension if required by design.
- ⑥

By design. Typically 30.98 kips per 0.5" strand & 43.94 kips per 0.6" strand, rounded to nearest whole kip.
- ⑦

Strand location not available when vent pipe is required.



PSBXB06\_27\_sk-end

Guidance

STANDARD DRAWING GUIDANCE (do not show on plans):  
(Turn off Level Bridge-Guidance to hide guidance)

- ①

Actual strand arrangement, bent up strands, and debonding (if any) is by design (top two strands are required). Add or remove symbols and instructions as required. Strands may be placed continuously across beam (eliminating 4" space), but dimension to drain hole in Part Plan shall be revised to 10".
- ②

Revise if #5 is required. Use 7'-4" for #5-S1 actual length and 7'-9" for #5-S2 actual length.
- ③

Splices shown only when necessary (girder length > 60'-2"). Use 2'-1" lap for #4 & 2'-7" lap for #5.

When lap is unnecessary:

- Delete grouped elements.

- Extend A bars to  $\text{\textcircled{C}}$  Beam.

- Revise 10 to 5 A1 bars & 8 to 4 A2 bars.
- ④

Interior diaphragm & vent pipe shall be shown only when necessary (when structure may be submerged).

When not necessary:

- Delete the two grouped elements.

- In Half Elev. extend hidden lines to  $\text{\textcircled{C}}$  Beam.

- In Part Plan revise remaining dimension to full length of void.
- ⑤

Revise minimum dimension if required by design.
- ⑥

By design. Typically 30.98 kips per 0.5" strand & 43.94 kips per 0.6" strand, rounded to nearest whole kip.
- ⑦

Strand location not available when vent pipe is required.





STANDARD DRAWING GUIDANCE (do not show on plans):  
(Turn off Level Bridge-Guidance to hide guidance)

- ①

Actual strand arrangement, bent up strands, and debonding (if any) is by design (top two strands are required). Add or remove symbols and instructions as required. Strands may be placed continuously across beam (eliminating 4" space), but dimension to drain hole in Part Plan shall be revised to 10".
- ②

Revise if #5 is required. Use 8'-4" for #5-S1 actual length and 7'-9" for #5-S2 actual length.
- ③

Splices shown only when necessary (girder length > 60'-2"). Use 2'-1" lap for #4 & 2'-7" lap for #5.

When lap is unnecessary:

- Delete grouped elements.

- Extend A bars to  $\text{\textcircled{C}}$  Beam.

- Revise 10 to 5 A1 bars & 8 to 4 A2 bars.
- ④

Interior diaphragm & vent pipe shall be shown only when necessary (when structure may be submerged).

When not necessary:


- Delete the two grouped elements.

- In Half Elev. extend hidden lines to  $\text{\textcircled{C}}$  Beam.

- In Part Plan revise remaining dimension to full length of void.
- ⑤

Revise minimum dimension if required by design.
- ⑥


By design. Typically 30.98 kips per 0.5" strand & 43.94 kips per 0.6" strand, rounded to nearest whole kip.



DIMENSIONS


(1) Fabricator shall apply a bond breaker to this region excluding where joint filler will be applied.

(2) 1 1/2" (Typ.) (3/4" Optional)



STRAND ARRANGEMENT

All strands are fully bonded unless otherwise noted.  
+ Indicates prestressing strand.  
○ Indicates cut and shop bend with 2'-6" projection.  
□ Indicates debonded for X'-X" from end of beam.  
△ Indicates debonded for X'-X" from end of beam.



STRANDS AT BEAM ENDS

BILL OF REINFORCING STEEL - EACH BEAM					BENDING DIAGRAM	
NO.	SIZE & MARK	ACTUAL LENGTH	SHAPE			
10	5 A1	X'-X"	20		(S1) 3'-7"	(S5) 3'-8 1/2"
8	4 A2	X'-X"	20		(S4) 3'-8 1/2"	(S7) 2'-8 1/2"
					(S6) 2'-8 1/2"	
X	4 C1	3'-7"	20		(S1, S4, S6)	(S5, S7)
X	4 S1	8'-5"	10		SHAPE 10	
X	4 S2	7'-10"	51			
X	4 S3	4'-6"	50			
18	5 S4	8'-6"	10			
18	5 S5	7'-6"	10			
2	5 S6	7'-6"	10			
2	5 S7	6'-6"	10			
					SHAPE 20	
12	6 U1	5'-7"	10			
6	4 U2	8'-4"	21			
					SHAPE 50	
					SHAPE 51	

All dimensions are out to out. Use symmetry for dimensions not shown.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

Actual lengths are measured along centerline of bar to the nearest inch.

Minimum clearance to reinforcing shall be 1", unless otherwise shown.

All reinforcement shall be Grade 60.

All S2 bars shall be epoxy coated.

General Notes:

Concrete for prestressed beams shall be Class A-1 with f'c = psi and f'ci = psi.

Use strands, #Ø Grade 270, with an initial prestress force of kips.

Pretensioned members shall be in accordance with Sec 1029.


Fabricator shall be responsible for location and design of lifting devices.

Exterior and interior beams are the same except: coil ties, application of bond breakers, coil inserts for slab drains.

For Beam Camber Diagram, see Sheet No. \_\_.

For location of coil inserts at slab drains, see Sheet No. \_\_.

For location of coil ties at concrete bent diaphragms, see Sheets No. \_\_ and \_\_.




HALF ELEVATION

Dimensions taken along C Beam.


(5) 2 Spa. @ 4"

Strands not shown for clarity.



PART PLAN

Mirror about C Beam for left advanced.



BEARING PLATE

Detailed Checked

Note: This drawing is not to scale. Follow dimensions.

SPREAD BOX BEAMS - SPANS (X-X) AND (X-X)

Sheet No. of

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION



105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

STANDARD DRAWING GUIDANCE (do not show on plans):  
(Turn off Level Bridge-Guidance to hide guidance)

- ①

Actual strand arrangement, bent up strands, and debonding (if any) is by design (top two strands are required). Add or remove symbols and instructions as required. Strands may be placed continuously across beam (eliminating 4" space), but dimension to drain hole in Part Plan shall be revised to 10".
- ②

Revise if #5 is required. Use 8'-4" for #5-S1 actual length and 7'-9" for #5-S2 actual length.
- ③

Splices shown only when necessary (girder length > 60'-2"). Use 2'-1" lap for #4 & 2'-7" lap for #5.

When lap is unnecessary:

- Delete grouped elements.

- Extend A bars to C Beam.

- Revise 10 to 5 A1 bars & 8 to 4 A2 bars.
- ④

Interior diaphragm & vent pipe shall be shown only when necessary (when structure may be submerged).

When not necessary:





- Delete the two grouped elements.

- In Half Elev. extend hidden lines to C Beam.

- In Part Plan revise remaining dimension to full length of void.
- ⑤





Revise minimum dimension if required by design.
- ⑥

By design. Typically 30.98 kips per 0.5" strand & 43.94 kips per 0.6" strand, rounded to nearest whole kip.



Detailed Checked

Note: This drawing is not to scale. Follow dimensions.



BILL OF REINFORCING STEEL - EACH BEAM					BENDING DIAGRAM	
NO.	SIZE & MARK	ACTUAL LENGTH	SHAPE			
10	5 A1	X'-X"	20		3'-7"	3'-7"
8	4 A2	X'-X"	20		2'-11"	23 3/4"
					(S1, S4)	(S5)
X	4 C1	3'-7"	20		21"	3'-5 3/4"
					(U1)	(U2)
X	4 S1	9'-5"	10		SHAPE 10	
X	4 S2	7'-10"	51		SHAPE 20	
X	4 S3	4'-6"	50			
18	5 S4	9'-4"	10			
18	5 S5	7'-4"	10			
12	6 U1	6'-1"	10			
6	4 U2	7'-4"	10			
					10"	2 1/2"
					6"	18"
					SHAPE 50	
					7 3/4"	7 3/4"
					23 3/4"	12"
					SHAPE 51	

All dimensions are out to out. Use symmetry for dimensions not shown.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

Actual lengths are measured along centerline of bar to the nearest inch.

Minimum clearance to reinforcing shall be 1", unless otherwise shown.

All reinforcement shall be Grade 60.

All S2 bars shall be epoxy coated.

**General Notes:**

Concrete for prestressed beams shall be Class A-1 with f'c = psi and f'ci = psi.

Use strands, #Ø Grade 270, with an initial prestress force of kips.

Pretensioned members shall be in accordance with Sec 1029.

Fabricator shall be responsible for location and design of lifting devices.

Exterior and interior beams are the same except: coil ties, application of bond breaker, coil inserts for slab drains.

For Beam Camber Diagram, see Sheet No. \_\_.

For location of coil inserts at slab drains, see Sheet No. \_\_.

For location of coil ties at concrete bent diaphragms, see Sheets No. \_\_ and \_\_.

DATE PREPARED  
5/4/2023

ROUTE  
STATE  
MO

DISTRICT  
SHEET NO.  
9

COUNTY

JOB NO.

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

SPREAD BOX BEAMS - SPANS (X-X) AND (X-X)

Sheet No. of

STANDARD DRAWING GUIDANCE (do not show on plans):  
(Turn off Level Bridge-Guidance to hide guidance)

- ①

Actual strand arrangement, bent up strands, and debonding (if any) is by design (top two strands are required). Add or remove symbols and instructions as required. Strands may be placed continuously across beam (eliminating 4" space), but dimension to drain hole in Part Plan shall be revised to 10".
- ②

Revise if #5 is required. Use 9'-4" for #5-S1 actual length and 7'-9" for #5-S2 actual length.
- ③

Splices shown only when necessary (girder length > 60'-2"). Use 2'-1" lap for #4 & 2'-7" lap for #5.

When lap is unnecessary:

- Delete grouped elements.

- Extend A bars to  $\text{\textcircled{C}}$  Beam.

- Revise 10 to 5 A1 bars & 8 to 4 A2 bars.
- ④

Interior diaphragm & vent pipe shall be shown only when necessary (when structure may be submerged).

When not necessary:





- Delete the two grouped elements.

- In Half Elev. extend hidden lines to  $\text{\textcircled{C}}$  Beam.

- In Part Plan revise remaining dimension to full length of void.
- ⑤

Revise minimum dimension if required by design.
- ⑥



By design. Typically 30.98 kips per 0.5" strand & 43.94 kips per 0.6" strand, rounded to nearest whole kip.





Detailed Checked

SPREAD BOX BEAMS - SPANS (X-X) AND (X-X)

Note: This drawing is not to scale. Follow dimensions.



Strands not shown for clarity.



BILL OF REINFORCING STEEL - EACH BEAM					BENDING DIAGRAM	
NO.	SIZE & MARK	ACTUAL LENGTH	SHAPE			
10	5 A1	X'-X"	20		(S1) 3'-7"	(S5) 3'-8½"
8	4 A2	X'-X"	20		(S4) 3'-8½"	(S7) 2'-8½"
					(S6) 2'-8½"	
X	4 C1	3'-7"	20		(S1,S4,S6)	(S5,S7)
X	4 S1	9'-5"	10		SHAPE 10	
X	4 S2	7'-10"	51			
X	4 S3	4'-6"	50			
18	5 S4	9'-6"	10		SHAPE 10	
18	5 S5	7'-6"	10			
2	5 S6	8'-6"	10		SHAPE 20	
2	5 S7	6'-6"	10			
12	6 U1	6'-1"	10			
6	4 U2	8'-4"	21			

All dimensions are out to out. Use symmetry for dimensions not shown.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

Actual lengths are measured along centerline of bar to the nearest inch.

Minimum clearance to reinforcing shall be 1", unless otherwise shown.

All reinforcement shall be Grade 60.

All S2 bars shall be epoxy coated.

General Notes:

Concrete for prestressed beams shall be Class A-1 with  $f'c =$  psi and  $f'ci =$  psi.

Use strands,  $\varnothing$  Grade 270, with an initial prestress force of kips.

Pretensioned members shall be in accordance with Sec 1029.

Fabricator shall be responsible for location and design of lifting devices.

Exterior and interior beams are the same except: coil ties, application of bond breaker, coil inserts for slab drains.

For Beam Camber Diagram, see Sheet No. \_\_.

For location of coil inserts at slab drains, see Sheet No. \_\_.

For location of coil ties at concrete bent diaphragms, see Sheets No. \_\_ and \_\_.

DATE PREPARED  
5/4/2023

ROUTE  
STATE  
MO

DISTRICT  
SHEET NO.  
10

COUNTY

JOB NO.

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

MDOT

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MDOT (1-888-275-6636)

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

STANDARD DRAWING GUIDANCE (do not show on plans):  
(Turn off Level Bridge-Guidance to hide guidance)

- ①

Actual strand arrangement, bent up strands, and debonding (if any) is by design (top two strands are required). Add or remove symbols and instructions as required. Strands may be placed continuously across beam (eliminating 4" space), but dimension to drain hole in Part Plan shall be revised to 10".
- ②

Revise if #5 is required. Use 9'-4" for #5-S1 actual length and 7'-9" for #5-S2 actual length.
- ③

Splices shown only when necessary (girder length > 60'-2"). Use 2'-1" lap for #4 & 2'-7" lap for #5.

When lap is unnecessary:

- Delete grouped elements.

- Extend A bars to  $\text{\textcircled{C}}$  Beam.

- Revise 10 to 5 A1 bars & 8 to 4 A2 bars.
- ④

Interior diaphragm & vent pipe shall be shown only when necessary (when structure may be submerged).

When not necessary:

- Delete the two grouped elements.

- In Half Elev. extend hidden lines to  $\text{\textcircled{C}}$  Beam.

- In Part Plan revise remaining dimension to full length of void.
- ⑤

Revise minimum dimension if required by design.
- ⑥

By design. Typically 30.98 kips per 0.5" strand & 43.94 kips per 0.6" strand, rounded to nearest whole kip.





STANDARD DRAWING GUIDANCE (do not show on plans):  
(Turn off Level Bridge-Guidance to hide guidance)

- ①

Actual strand arrangement, bent up strands, and debonding (if any) is by design (top two strands are required). Add or remove symbols and instructions as required. Strands may be placed continuously across beam (eliminating 4" space), but dimension to drain hole in Part Plan shall be revised to 10".
- ②

Revise if #5 is required. Use 9'-10" for #5-S1 actual length and 7'-9" for #5-S2 actual length.
- ③

Splices shown only when necessary (girder length > 60'-2"). Use 2'-1" lap for #4 & 2'-7" lap for #5.

When lap is unnecessary:

- Delete grouped elements.

- Extend A bars to  $\text{\textcircled{C}}$  Beam.

- Revise 10 to 5 A1 bars & 8 to 4 A2 bars.
- ④

Interior diaphragm & vent pipe shall be shown only when necessary (when structure may be submerged).

When not necessary:





- Delete the two grouped elements.

- In Half Elev. extend hidden lines to  $\text{\textcircled{C}}$  Beam.

- In Part Plan revise remaining dimension to full length of void.
- ⑤


Revise minimum dimension if required by design.
- ⑥

By design. Typically 30.98 kips per 0.5" strand & 43.94 kips per 0.6" strand, rounded to nearest whole kip.






Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.



Strands not shown for clarity.



BILL OF REINFORCING STEEL - EACH BEAM					BENDING DIAGRAM	
NO.	SIZE & MARK	ACTUAL LENGTH	SHAPE			
10	5 A1	X'-X"	20		(S1) 3'-7"	(S5) 3'-8½"
8	4 A2	X'-X"	20		(S4) 3'-8½"	(S7) 2'-8½"
					(S6) 2'-8½"	
X	4 C1	3'-7"	20		(S1,S4,S6)	(S5,S7)
X	4 S1	9'-11"	10		SHAPE 10	
X	4 S2	7'-10"	51		SHAPE 21	
X	4 S3	4'-6"	50		SHAPE 10	
18	5 S4	10'-0"	10		SHAPE 21	
18	5 S5	7'-6"	10		SHAPE 50	
2	5 S6	9'-0"	10		SHAPE 51	
2	5 S7	6'-6"	10			
12	6 U1	6'-4"	10			
8	4 U2	8'-4"	21			

All dimensions are out to out. Use symmetry for dimensions not shown.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

Actual lengths are measured along centerline of bar to the nearest inch.

Minimum clearance to reinforcing shall be 1", unless otherwise shown.

All reinforcement shall be Grade 60.

All S2 bars shall be epoxy coated.

**General Notes:**

Concrete for prestressed beams shall be Class A-1 with  $f'c =$  psi and  $f'ci =$  psi.

Use strands, #Ø Grade 270, with an initial prestress force of kips.

Pretensioned members shall be in accordance with Sec 1029.

Fabricator shall be responsible for location and design of lifting devices.

Exterior and interior box beams are the same except: coil ties, application of bond breaker, coil inserts for slab drains.

For Beam Camber Diagram, see Sheet No. \_\_.

For location of coil inserts at slab drains, see Sheet No. \_\_.

For location of coil ties at concrete bent diaphragms, see Sheets No. \_\_ and \_\_.

DATE PREPARED  
5/4/2023

ROUTE  
STATE  
MO

DISTRICT  
SHEET NO.  
12

COUNTY

JOB NO.

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

STANDARD DRAWING GUIDANCE (do not show on plans):  
(Turn off Level Bridge-Guidance to hide guidance)

- ①

Actual strand arrangement, bent up strands, and debonding (if any) is by design (top two strands are required). Add or remove symbols and instructions as required. Strands may be placed continuously across beam (eliminating 4" space), but dimension to drain hole in Part Plan shall be revised to 10".
- ②

Revise if #5 is required. Use 9'-10" for #5-S1 actual length and 7'-9" for #5-S2 actual length.
- ③

Splices shown only when necessary (girder length > 60'-2"). Use 2'-1" lap for #4 & 2'-7" lap for #5.

When lap is unnecessary:

- Delete grouped elements.

- Extend A bars to  $\text{\textcircled{C}}$  Beam.

- Revise 10 to 5 A1 bars & 8 to 4 A2 bars.
- ④

Interior diaphragm & vent pipe shall be shown only when necessary (when structure may be submerged).

When not necessary:

- Delete the two grouped elements.

- In Half Elev. extend hidden lines to  $\text{\textcircled{C}}$  Beam.

- In Part Plan revise remaining dimension to full length of void.
- ⑤

Revise minimum dimension if required by design.
- ⑥

By design. Typically 30.98 kips per 0.5" strand & 43.94 kips per 0.6" strand, rounded to nearest whole kip.




Standard Drawing Guidance (do not show on plans):

To display the strand details open the reference files dialog box and activate the display option of the file with the description that best matches what is required by the design.


See EPG for actual length of B1 bars which vary by size.

The details of the coil ties are for closed diaphragms. Include additional detail below for open diaphragms.

- ① This detail only needs to be used if the structure is over water. For all other crossings remove this detail.
- ② Remove if #5-B1 bars are used.
- ③ Use with end spans when both interior & exterior girders are detailed on the same sheet, and the 2'-6" long tie rod will not fit in the exterior diaphragm portion. Remove when not necessary.
- ④ By design. Typically 30.98 kips per 1/2" strand & 43.94 kips per 0.6" strand, rounded to nearest whole kip.




DIMENSIONS




STRAND ARRANGEMENT


+ Indicates prestressing strand.      ○ Indicates cut & shop bend with 2'-6" projection.




STRANDS AT GIRDER ENDS




HALF ELEVATION



SECTION B-B  
Strands not shown for clarity.




BEARING PLATE



VENT HOLE


Place vent holes at or near upgrade 1/3 point of girders and clear reinforcing steel or strands by 1 1/2" minimum and steel intermediate diaphragm bolt connections by 6" minimum.



COIL TIES

Exclude coil tie at exterior face of exterior girders except at integral end bents.

\* x'-x" at exterior face of exterior girders at end bents



B1 BAR PERMISSIBLE ALTERNATE SHAPE

BILL OF REINFORCING STEEL - EACH GIRDER				
NO.	SIZE & MARK	ACTUAL LENGTH	SHAPE	BENDING DIAGRAM
XXX	X A1	X'-X"	20	
XXX	X B1	X'-X"	11	
16	6 B2	4'-0"	11	
XXX	4 C1	13"	10	
XXX	4 D1	2'-5"	9	
SHAPE 20				SHAPE 11

All dimensions are out to out.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

Actual lengths are measured along centerline of bar to the nearest inch.

Minimum clearance to reinforcing shall be 1".

All reinforcement shall be Grade 60.

The two D1 bars may be furnished as one bar at the fabricator's option.

All B1 bars shall be epoxy coated.

### General Notes:

Concrete for prestressed girders shall be Class A-1 with  $f'c =$  psi and  $f'ci =$  psi.

Use strands, 1/2"Ø Grade 270, with an initial prestress force of ④ kips.

Pretensioned members shall be in accordance with Sec 1029.

Fabricator shall be responsible for location and design of lifting devices.

Exterior and interior girders are the same except: coil ties, coil inserts for slab drains, holes for steel intermediate diaphragms.

For Girder Camber Diagram, see Sheet No. .

The 1 1/2"Ø holes shall be cast in the web for steel intermediate diaphragms. Drilling is not allowed. For location of holes and details of steel intermediate diaphragms, see Sheet No. .

For location of coil inserts at slab drains, see Sheet No. .

For location of coil ties at concrete bent diaphragms, see Sheets No. & .



Standard Drawing Guidance (do not show on plans):

To display the strand details open the reference files dialog box and activate the display option of the file with the description that best matches what is required by the design.

See EPG for actual length of B1 bars which vary by size.

The details of the coil ties are for closed diaphragms. Include additional detail below for open diaphragms.

- ① This detail only needs to be used if the structure is over water. For all other crossings remove this detail.
- ② Remove if #5-B1 bars are used.
- ③ Use with end spans when both interior & exterior girders are detailed on the same sheet, and the 2'-6" long tie rod will not fit in the exterior diaphragm portion. Remove when not necessary.
- ④ By design. Typically 30.98 kips per 1/2" strand & 43.94 kips per 0.6" strand, rounded to nearest whole kip.













Standard Drawing Guidance (do not show on plans):

To display the strand details open the reference files dialog box and activate the display option of the file with the description that best matches what is required by the design.

See EPG for actual length of B1 bars which vary by size.

The details of the coil ties are for closed diaphragms. Include additional detail below for open diaphragms.

- ① This detail only needs to be used if the structure is over water. For all other crossings remove this detail.
- ② Remove if #5-B1 bars are used.
- ③ Use with end spans when both interior & exterior girders are detailed on the same sheet, and the 2'-6" long tie rod will not fit in the exterior diaphragm portion. Remove when not necessary.
- ④ By design. Typically 30.98 kips per 1/2" strand & 43.94 kips per 0.6" strand, rounded to nearest whole kip.



BILL OF REINFORCING STEEL - EACH GIRDER				
NO.	SIZE & MARK	ACTUAL LENGTH	SHAPE	BENDING DIAGRAM
XXX	X A1	X' - X"	20	<p>SHAPE 10</p>
XXX	X B1	X' - X"	11	<p>SHAPE 9</p>
16	6 B2	5' - 3"	11	
XXX	4 C1	2' - 2"	10	<p>SHAPE 11</p>
XXX	4 D1	3' - 0"	9	<p>SHAPE 20</p>

All dimensions are out to out.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

Actual lengths are measured along centerline of bar to the nearest inch.

Minimum clearance to reinforcing shall be 1".

All reinforcement shall be Grade 60.

The two D1 bars may be furnished as one bar at the fabricator's option.

All B1 bars shall be epoxy coated.

General Notes:

Concrete for prestressed girders shall be Class A-1 with  $f'_c =$  psi and  $f'_{ci} =$  psi.

Use 4 strands, 1/2"Ø Grade 270, with an initial prestress force of 4 kips.

Pretensioned members shall be in accordance with Sec 1029.

Fabricator shall be responsible for location and design of lifting devices.

Exterior and interior girders are the same except: coil ties, coil inserts for slab drains, holes for steel intermediate diaphragms.

For Girder Camber Diagram, see Sheet  
No. .

The 1 1/2"Ø holes shall be cast in the web for steel intermediate diaphragms. Drilling is not allowed. For location of holes and details of steel intermediate diaphragms, see Sheet No. .

For location of coil inserts at slab drains, see Sheet No. .

For location of coil ties at concrete bent diaphragms, see Sheets No.      &

DATE PREPARED	
10/16/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	4
COUNTY	

JOB NO.
CONTRACT ID.
PROJECT NO.
BRIDGE NO.

[illegible]

MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)


Standard Drawing Guidance (do not show on plans):

To display the strand details open the reference files dialog box and activate the display option of the file with the description that best matches what is required by the design.

See EPG for actual length of B1 bars which vary by size.


The details of the coil ties are for closed diaphragms. Include additional detail below for open diaphragms.

- ① This detail only needs to be used if the structure is over water. For all other crossings remove this detail.
- ② Remove if #5-B1 bars are used.
- ③ Use with end spans when both interior & exterior girders are detailed on the same sheet, and the 2'-6" long tie rod will not fit in the exterior diaphragm portion. Remove when not necessary.
- ④ By design. Typically 30.98 kips per 1/2" strand & 43.94 kips per 0.6" strand, rounded to nearest whole kip.



⊕ GIRDER      ⊕ END OF GIRDER

+ Indicates prestressing strand.      ⊕ Indicates cut & shop bend with 2'-6" projection.



END BENT      INTERMEDIATE BENT

STRANDS AT GIRDER ENDS

BILL OF REINFORCING STEEL - EACH GIRDER				
NO.	SIZE & MARK	ACTUAL LENGTH	SHAPE	BENDING DIAGRAM
XXX	X A1	X'-X"	20	
XXX	X B1	X'-X"	11	
16	6 B2	6'-11"	11	
XXX	4 C1	3'-5"	19	
XXX	4 D1	3'-1"	9	

All dimensions are out to out.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.


Actual lengths are measured along centerline of bar to the nearest inch.

Minimum clearance to reinforcing shall be 1".


All reinforcement shall be Grade 60.

The two D1 bars may be furnished as one bar at the fabricator's option.


All B1 and C1 bars shall be epoxy coated.




SECTION A-A  
Strands not shown for clarity.




HALF ELEVATION



SECTION B-B  
Strands not shown for clarity.




BEARING PLATE



VENT HOLE


Place vent holes at or near upgrade 1/3 point of girders and clear reinforcing steel or strands by 1 1/2" minimum and steel intermediate diaphragm bolt connections by 6" minimum.



COIL TIES

Exclude coil tie at exterior face of exterior girders except at integral end bents.

\* x'-x" at exterior face of exterior girders at end bents.



B1 BAR  
PERMISSIBLE  
ALTERNATE  
SHAPE

### General Notes:

Concrete for prestressed girders shall be Class A-1 with  $f'c =$  psi and  $f'ci =$  psi.

Use strands, 1/2"Ø Grade 270, with an initial prestress force of 4 kips.

Pretensioned members shall be in accordance with Sec 1029.

Fabricator shall be responsible for location and design of lifting devices.

Exterior and interior girders are the same except: coil ties, coil inserts for slab drains, holes for steel intermediate diaphragms.

For Girder Camber Diagram, see Sheet No. --.

The 1 1/2"Ø holes shall be cast in the web for steel intermediate diaphragms. Drilling is not allowed. For location of holes and details of steel intermediate diaphragms, see Sheet No. --.

For location of coil inserts at slab drains, see Sheet No. --.

For location of coil ties at concrete diaphragms and integral bents, see Sheets No. -- and --.

DATE PREPARED	
10/16/2023	
ROUTE	STATE
DISTRICT	SHEET NO.
COUNTY	

JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	

DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION		105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-273-6636)

PSI\_05\_bulbt\_6-0

Guidance & Alternate Details

Standard Drawing Guidance (do not show on plans):

To display the strand details open the reference files dialog box and activate the display option of the file with the description that best matches what is required by the design.

See EPG for actual length of B1 bars which vary by size.

The details of the coil ties are for closed diaphragms. Include additional detail below for open diaphragms.

- ①

This detail only needs to be used if the structure is over water. For all other crossings remove this detail.
- ②

Remove if #5-B1 bars are used.
- ③

Use with end spans when both interior & exterior girders are detailed on the same sheet, and the 2'-6" long tie rod will not fit in the exterior diaphragm portion. Remove when not necessary.
- ④

By design. Typically 30.98 kips per 1/2" strand & 43.94 kips per 0.6" strand, rounded to nearest whole kip.





## PSI\_06\_NU\_WWR

## Guidance & Alternate Details

Standard Drawing Guidance (do not show on plans)

- ① Choose one of the 4 details for the top flange blackout detail and follow the provided detail guidance. For 0-7° skew remove G6 bars from bill of reinforcing.

The left advanced details shown may be used for right advanced bridges. May remove mirror note if left advanced.

Blockout shall be dimensioned along the girder to 1 1/2 inches inside the face of the diaphragm and adjusted for girder tilt if present.

Revise bent references as required. Specify the bent number if blockout varies by bent.

The skew angle value need not be shown for tangent bridges. Consult SPM or Liaison on replacing "skew angle" with actual value for curved bridges.

Revised titles for non-integral end bents (exterior girder at end bent will be same detail as at intermediate bent).

FLANGE BLOCKOUT DATA			
Skew	X Eq. Spa.	X #4-G6	Bar Lengths
>14° to 21°	3	2	G3 bar = $\frac{46.25"}{\cos(\text{skew})}$
>21° to 27°	4	3	
>27° to 32°	5	4	G5 bar = $\frac{32.125"}{\cos(\text{skew})}$
>32° to 37°	6	5	
>37° to 42°	7	6	For skews > 7° to 14°: G6 bar = $\frac{\text{G3 bar} + 46.25"}{2}$
>42° to 46°	8	7	
>46° to 49°	9	8	For skews > 14° to 60°:  Report length of G6 bars as "Varies".
>49° to 52°	10	9	
>52° to 55°	11	10	
>55° to 57°	12	11	
>57° to 60°	13	12	

- ② The maximum strand arrangement is shown in details including top straight strands. Remove unnecessary strands from the four details where shown.
- ③ Detail only needs to be used if the structure is over water. For all other crossings remove detail.
- ④ Indicate 10 strands as shown for NU 35, 43 & 53. Indicate two more strands for NU 63, 70 and 78.

$$\oplus \oplus \oplus \oplus \oplus + \oplus + \quad + \oplus + \oplus \oplus \oplus \oplus \oplus$$





Strands are not typically debonded for NU girders, but if required by design, add symbols to End of Girder strand arrangement detail and add the appropriate notes (Note H2c1.44 and as shown below).

- Indicates debonded for  
x'-0" from end of girder
- △ Indicates debonded for  
x'-0" from end of girder

- ⑤ 7" Maximum and 1" Minimum.
- ⑥ By design. Typically 30.98 kips per 1/2" strand & 43.94 kips per 0.6" strand, rounded to nearest whole kip.
- ⑦ Revise minimum dimension if required by design.
- ⑧ Adjust for modified flange thickness.
- ⑨ Use with end spans when both interior & exterior girders are detailed on same sheet and the 2'-6" long tie rod will not fit in the exterior diaphragm portion. Remove when not necessary.
- ⑩ Substitute these values into drawing

NU	a	b	c
35	20 <sup>1</sup> / <sub>16</sub> "	2' - 11 <sup>7</sup> / <sub>16</sub> "	23 <sup>3</sup> / <sub>4</sub> "
43	2' - 4 <sup>9</sup> / <sub>16</sub> "	3' - 7 <sup>5</sup> / <sub>16</sub> "	2' - 7 <sup>1</sup> / <sub>2</sub> "
53	3' - 2 <sup>13</sup> / <sub>32</sub> "	4' - 5 <sup>5</sup> / <sub>32</sub> "	3' - 5 <sup>1</sup> / <sub>4</sub> "
63	4' - 0 <sup>1</sup> / <sub>4</sub> "	5' - 3"	4' - 3 <sup>3</sup> / <sub>4</sub> "
70	4' - 8 <sup>1</sup> / <sub>8</sub> "	5' - 10 <sup>7</sup> / <sub>8</sub> "	4' - 11"
78	5' - 4"	6' - 6 <sup>3</sup> / <sub>4</sub> "	5' - 7"

- ⑪ Remove note for NU 53, 63, 70 and 78.
- ⑫ Remove notes for NU 35 and 43.
- ⑬ The overall height of the WWR6 shall not be increased for girder steps. Reduce this dimension by the accumulated girder step height.





PSI\_07\_NU\_Bars

Guidance & Alternate Details

Standard Drawing Guidance (do not show on plans)

① Choose one of the 4 details for the top flange breakout detail and follow the provided detail guidance. For 0-7° skew remove G6 bars from bill of reinforcing.

The left advanced details shown may be used for right advanced bridges. May remove mirror note if left advanced.

Blockout shall be dimensioned along the girder to 1 1/2 inches inside the face of the diaphragm and adjusted for girder tilt if present.

Revise bent references as required. Specify the bent number if blockout varies by bent.

The skew angle value need not be shown for tangent bridges. Consult SPM or Liaison on replacing "skew angle" with actual value for curved bridges.

Revised titles for non-integral end bents (exterior girder at end bent will be same detail as at intermediate bent).

FLANGE BLOCKOUT DATA			
Skew	X Eq. Spa.	X #4-G6	Bar Lengths
>14° to 21°	3	2	G3 bar = $\frac{46.25"}{\cos(\text{skew})}$
>21° to 27°	4	3	
>27° to 32°	5	4	
>32° to 37°	6	5	G5 bar = $\frac{32.125"}{\cos(\text{skew})}$
>37° to 42°	7	6	
>42° to 46°	8	7	For skews > 7° to 14°: G6 bar = $\frac{\text{G3 bar} + 46.25"}{2}$
>46° to 49°	9	8	
>49° to 52°	10	9	For skews > 14° to 60°: Report length of G6 bars as "Varies".
>52° to 55°	11	10	
>55° to 57°	12	11	
>57° to 60°	13	12	

- ② The maximum strand arrangement is shown in details including top straight strands. Remove unnecessary strands from the four details where shown.
- ③ Detail only needs to be used if the structure is over water. For all other crossings remove detail.
- ④ Indicate 10 strands as shown for NU 35, 43 & 53. Indicate two more strands for NU 63, 70 and 78.

⊠⊠⊠⊠⊠⊠+⊕+ ⊕+⊠⊠⊠⊠⊠⊠

Strands are not typically debonded for NU girders, but if required by design, add symbols to End of Girder strand arrangement detail and add the appropriate notes (Note H2c1.44 and as shown below).

⊠ Indicates debonded for x'-0" from end of girder

△ Indicates debonded for x'-0" from end of girder


⑤ Actual length of B1 bars:

	NU 35	NU 43	NU 53	NU 63	NU 70	NU 78
#4	4'-4"	5'-0"	5'-10"	6'-8"	7'-4"	8'-0"
#5	4'-4"	5'-0"	5'-10"	6'-8"	7'-3"	7'-11"
#6	4'-3"	4'-11"	5'-8"	6'-6"	7'-2"	7'-10"


- ⑥ By design. Typically 30.98 kips per 1/2" strand & 43.94 kips per 0.6" strand, rounded to nearest whole kip.
- ⑦ Revise minimum dimension if required by design.
- ⑧ Adjust for modified flange thickness.
- ⑨ Use with end spans when both interior & exterior girders are detailed on same sheet and the 2'-6" long tie rod will not fit in the exterior diaphragm portion. Remove when not necessary.
- ⑩ Substitute these values into drawing.

NU	a	b	c	d
35	20 <sup>1</sup> / <sub>16</sub> "	2'-11 <sup>7</sup> / <sub>16</sub> "	3'-4"	23 <sup>3</sup> / <sub>4</sub> "
43	2'-4 <sup>9</sup> / <sub>16</sub> "	3'-7 <sup>5</sup> / <sub>16</sub> "	3'-11 <sup>3</sup> / <sub>4</sub> "	2'-7 <sup>1</sup> / <sub>2</sub> "
53	3'-2 <sup>13</sup> / <sub>32</sub> "	4'-5 <sup>5</sup> / <sub>32</sub> "	4'-9 <sup>3</sup> / <sub>4</sub> "	3'-5 <sup>1</sup> / <sub>4</sub> "
63	4'-0 <sup>1</sup> / <sub>4</sub> "	5'-3"	5'-7 <sup>1</sup> / <sub>2</sub> "	4'-3 <sup>1</sup> / <sub>4</sub> "
70	4'-8 <sup>3</sup> / <sub>8</sub> "	5'-10 <sup>7</sup> / <sub>8</sub> "	6'-3 <sup>1</sup> / <sub>2</sub> "	4'-11"
78	5'-4"	6'-6 <sup>3</sup> / <sub>4</sub> "	6'-11 <sup>1</sup> / <sub>4</sub> "	5'-7"


- ⑪ Remove note for NU 53, 63, 70 and 78.
- ⑫ Remove notes for NU 35 and 43.
- ⑬ The overall height of the WWR6 shall not be increased for girder steps. Reduce this dimension by the accumulated girder step height.
- ⑭ Remove if #5-B1 bars are used.




NO SKEW



>0° TO 7° LA SKEW



>7° TO 14° LA SKEW




>14° TO 60° LA SKEW





Standard Drawing Guidance (do not show on plans):

- ① Modify details if expansion gap is used and add Section B-B at expansion device and additional reference notes as shown on standard drawing for steel structures (PSP06).



General Notes:

Prestressed Panels:  
Concrete for prestressed panels shall be Class A-1 with  $f'c = 6,000$  psi,  $f'ci = 4,000$  psi.

The top surface of all panels shall receive a scored finish with a depth of scoring of 1/8" perpendicular to the prestressing strands in the panels.

Prestressing tendons shall be high-tensile strength, uncoated, seven-wire, low-relaxation strands for prestressed concrete in accordance with AASHTO M 203 Grade 270, with nominal diameter of strand = 3/8" and nominal area = 0.085 sq.in. and minimum ultimate strength = 22.95 kips (270 ksi). Larger strands may be used with the same spacing and initial tension.

Initial prestressing force = 17.2 kips/strand.

The method and sequence of releasing the strands shall be shown on the shop drawings.


Suitable anchorage devices for lifting panels may be cast in panels, provided the devices are shown on the shop drawings and approved by the engineer. Panel lengths shall be determined by the contractor and shown on the shop drawings.

PLAN SHOWING PANEL PLACEMENT




U1 Bars may be oriented at right angles to location and spacing shown. U1 Bars shall be placed between P1 bars.


May be cast square and sawn to skew



SECTION B-B



PLAN OF OPTIONAL TRUNCATED END PANEL



PLAN OF SQUARED PANEL

Reference Notes:

- Plan of Panel Placement:
- (1) S-bars shown are bottom steel in slab between panels and used with squared and truncated end panels only.
  - (2) Extend S-bars 18 inches beyond the front face of end bents and int. bents for squared and truncated end panels only.
  - (3) Extend S-bars 9 inches beyond edge of girder (Typ.).
  - (4) End panels shall be dimensioned 1/2" min. to 1 1/2" max. from the inside face of diaphragm.
  - (5) For truncated end panels, use a min. of #5-S bars at 6" crossings in openings, or min. 4x4-W7xW7.
  - (6) For end panels only, P1 bars shall be 2'-0" in length and embedded 12". P1 bars will not be required for panels at squared integral end bents.
  - (7) #3-P2 bars near edge of panel at bottom (under strands).
  - (8) Use #3-P3 bars if panel is skewed 45° or greater.
  - (9) Any strand 2'-0" or shorter shall have a #4 reinforcing bar on each side of it, centered between strands. Strands 2'-0" or shorter may then be deboned at the fabricator's option.
  - (10) Optional 1/2" x 45° Chamfer one or both sides at bottom.
- Section A-A:
- (11) Slab thickness over prestressed panels varies due to girder camber. In order to maintain minimum slab thickness, it may be necessary to raise the grade uniformly throughout the structure. No payment will be made for additional labor or materials required for necessary grade adjustment.
  - (12) Contractor shall ensure proper consolidation under and between panels.
  - (13) At the contractor's option, the variation in slab thickness over prestressed panels may be eliminated or reduced by increasing and varying the girder top flange thickness. Dimensions shall be shown on the shop drawings.

PRESTRESSED PANELS

DATE PREPARED	
2/24/2023	
ROUTE	STATE
DISTRICT	SHEET NO.
2	
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	DATE
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.




PSP02\_PS\_Type\_6

Guidance

Standard Drawing Guidance (do not show on plans):

- ① Modify details if expansion gap is used and add Section B-B at expansion device and additional reference notes as shown on standard drawing for steel structures (PSP06).




SQUARED END PANELS OR TRUNCATED END PANELS

SKWEKED END PANELS


PLAN SHOWING PANEL PLACEMENT

\* #5-S Bars at abt. 9" cts. (1)  
\*\* #3-P1 at 12" cts. (End panels only)




BENDING DIAGRAM FOR U1 BAR


U1 Bars may be oriented at right angles to location and spacing shown. U1 Bars shall be placed between P1 bars.



SECTION B-B




PLAN OF OPTIONAL SKWEKED END PANEL



PLAN OF OPTIONAL TRUNCATED END PANEL

\*\*\* 3" (Min.), 6" (Max.)



PLAN OF SQUARED PANEL

SECTION A-A  
Reference Notes:

Plan of Panel Placement:  
(1) S-bars shown are bottom steel in slab between panels and used with squared and truncated end panels only.

(2) Extend S-bars 18 inches beyond the front face of end bents and int. bents for squared and truncated end panels only.

(3) Extend S-bars 9 inches beyond edge of girder (Typ.).

(4) End panels shall be dimensioned 1/2" min. to 1 1/2" max. from the inside face of diaphragm.

(5) For truncated end panels, use a min. of #5-S bars at 6" crossings in openings, or min. 4x4-W7xW7.

Plans of Panels:  
(6) For end panels only, P1 bars shall be 2'-0" in length and embedded 12". P1 bars will not be required for panels at squared integral end bents.

(7) #3-P2 bars near edge of panel at bottom (under strands).

(8) Use #3-P3 bars if panel is skewed 45° or greater.

(9) Any strand 2'-0" or shorter shall have a #4 reinforcing bar on each side of it, centered between strands. Strands 2'-0" or shorter may then be debonded at the fabricator's option.

(10) Optional 1/2" x 45° Chamfer one or both sides at bottom.

Section A-A:  
(11) Slab thickness over prestressed panels varies due to girder camber. In order to maintain minimum slab thickness, it may be necessary to raise the grade uniformly throughout the structure. No payment will be made for additional labor or materials required for necessary grade adjustment.

(12) Contractor shall ensure proper consolidation under and between panels.

(13) At the contractor's option, the variation in slab thickness over prestressed panels may be eliminated or reduced by increasing and varying the girder top flange thickness. Dimensions shall be shown on the shop drawings.

PRESTRESSED PANELS

General Notes:

Prestressed Panels:  
Concrete for prestressed panels shall be Class A-1 with  $f'c = 6,000$  psi,  $f'ci = 4,000$  psi.  
The top surface of all panels shall receive a scored finish with a depth of scoring of 1/8" perpendicular to the prestressing strands in the panels.

Prestressing tendons shall be high-tensile strength, uncoated, seven-wire, low-relaxation strands for prestressed concrete in accordance with AASHTO M 203 Grade 270, with nominal diameter of strand = 3/8" and nominal area = 0.085 sq.in. and minimum ultimate strength = 22.95 kips (270 ksi). Larger strands may be used with the same spacing and initial tension.

Initial prestressing force = 17.2 kips/strand.

The method and sequence of releasing the strands shall be shown on the shop drawings.

Suitable anchorage devices for lifting panels may be cast in panels, provided the devices are shown on the shop drawings and approved by the engineer. Panel lengths shall be determined by the contractor and shown on the shop drawings.

When squared end panels are used at skewed bents, the skewed portion shall be cast full depth. No separate payment will be made for additional concrete and reinforcing required.

Support from diaphragm forms is required under the optional skewed end until cast-in-place concrete has reached 3,000 psi compressive strength.

Prestressed panels shall be brought to saturated surface-dry (SSD) condition just prior to the deck pour. There shall be no free standing water on the panels or in the area to be cast.

The prestressed panel quantities are not included in the table of estimated quantities for the slab.

Reinforcing Steel:  
All dimensions are out to out.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

Minimum clearance to reinforcing steel shall be 1 1/2", unless otherwise shown.

If U1 bars interfere with placement of slab steel, U1 loops may be bent over, as necessary, to clear slab steel.

Deformed welded wire reinforcement (WWR) providing a minimum area of reinforcing perpendicular to strands of 0.22 sq in./ft, with spacing parallel to strands sufficient to ensure proper handling, may be used in lieu of the #3-P2 bars shown. Wire diameter shall not be larger than 0.375 inch. The above alternative reinforcement criteria may be used in lieu of the #3-P3 bars, when required, and placed over a width not less than 2 feet.

The following reinforcing steel shall be tied securely to the strands with the following maximum spacing in each direction:  
#3-P2 bars at 16 inches.  
WWR at 24 inches.

The #3-U1 bars shall be tied securely to #3-P2 bars, to WWR or to strands (when placed between P1 bars) at about 3-foot centers.

Minimum reinforcement steel length shall be 2'-0".

All reinforcement other than prestressing strands shall be epoxy coated.

Precast panels may be in contact with stirrup reinforcing in diaphragms.

S-bars are not listed in the bill of reinforcing.

Cost of S-bars will be considered completely covered by the contract unit price for the slab.

Joint Filler:  
Joint filler shall be preformed fiber expansion joint material in accordance with Sec 1057 or expanded or extruded polystyrene bedding material in accordance with Sec 1073.

Use Slab Haunching Diagram on Sheet No. (XX) for determining thickness of joint filler within the limits noted in the table of Joint Filler Dimensions.

Thicker material may be used on one or both sides of the girder to reduce cast-in-place concrete thickness to within tolerances.

The same thickness of preformed fiber expansion joint material shall be used under any one edge of any panel except at locations where top flange thickness may be stepped. The maximum change in thickness between adjacent panels shall be 1/2 inch. The polystyrene bedding material may be cut with a transition to match haunch height above top of flange.

Joint filler shall be glued to the girder. When thickness exceeds 1 1/2 inches, the joint filler shall be glued top and bottom. The glue used shall be the type recommended by the joint filler manufacturer.

Edges of panels shall be uniformly seated on the joint filler before slab reinforcement is placed.

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No.      of

DATE PREPARED 2/24/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 3
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.


Standard Drawing Guidance (do not show on plans):

- ① Modify details if expansion gap is used and add Section B-B at expansion device and additional reference notes as shown on standard drawing for steel structures (PSP06).



Standard Drawing Guidance (do not show on plans):

- ① Modify details if expansion gap is used and add Section B-B at expansion device and additional reference notes as shown on standard drawing for steel structures (PSP06).




SQUARED END PANELS OR TRUNCATED END PANELS

SKewed END PANELS


PLAN SHOWING PANEL PLACEMENT

\* #5-S Bars at abt. 9" cts. (1)  
\*\* #3-P1 at 12" cts. (End panels only)




BENDING DIAGRAM FOR U1 BAR


U1 Bars may be oriented at right angles to location and spacing shown. U1 Bars shall be placed between P1 bars.



SECTION B-B




PLAN OF OPTIONAL SKewed END PANEL




PLAN OF OPTIONAL TRUNCATED END PANEL

\*\*\* 3" (Min.), 6" (Max.)



PLAN OF SQUARED PANEL



SECTION A-A

Reference Notes:

- Plan of Panel Placement:
- (1) S-bars shown are bottom steel in slab between panels and used with squared and truncated end panels only.
  - (2) Extend S-bars 18 inches beyond the front face of end bents and int. bents for squared and truncated end panels only.
  - (3) Extend S-bars 9 inches beyond edge of girder (Typ.).
  - (4) End panels shall be dimensioned 1/2" min. to 1 1/2" max. from the inside face of diaphragm.
  - (5) For truncated end panels, use a min. of #5-S bars at 6" crossings in openings, or min. 4x4-W7xW7.

Plans of Panels:

- (6) For end panels only, P1 bars shall be 2'-0" in length and embedded 12". P1 bars will not be required for panels at squared integral end bents.

- (7) #3-P2 bars near edge of panel at bottom (under strands).
- (8) Use #3-P3 bars if panel is skewed 45° or greater.
- (9) Any strand 2'-0" or shorter shall have a #4 reinforcing bar on each side of it, centered between strands. Strands 2'-0" or shorter may then be debonded at the fabricator's option.
- (10) Optional 1/2" x 45° Chamfer one or both sides at bottom.

Section A-A:

(11) Slab thickness over prestressed panels varies due to beam camber. In order to maintain minimum slab thickness, it may be necessary to raise the grade uniformly throughout the structure. No payment will be made for additional labor or materials required for necessary grade adjustment.

(12) Contractor shall ensure proper consolidation under and between panels.

(13) At the contractor's option, the variation in slab thickness over prestressed panels may be eliminated or reduced by increasing and varying the girder top flange thickness. Dimensions shall be shown on the shop drawings.

General Notes:

Prestressed Panels:  
Concrete for prestressed panels shall be Class A-1 with  $f'c = 6,000$  psi,  $f'ci = 4,000$  psi.

The top surface of all panels shall receive a scored finish with a depth of scoring of 1/8" perpendicular to the prestressing strands in the panels.

Prestressing tendons shall be high-tensile strength, uncoated, seven-wire, low-relaxation strands for prestressed concrete in accordance with AASHTO M 203 Grade 270, with nominal diameter of strand = 3/8" and nominal area = 0.085 sq.in. and minimum ultimate strength = 22.95 kips (270 ksi). Larger strands may be used with the same spacing and initial tension.

Initial prestressing force = 17.2 kips/strand.

The method and sequence of releasing the strands shall be shown on the shop drawings.

Suitable anchorage devices for lifting panels may be cast in panels, provided the devices are shown on the shop drawings and approved by the engineer. Panel lengths shall be determined by the contractor and shown on the shop drawings.

When squared end panels are used at skewed bents, the skewed portion shall be cast full depth. No separate payment will be made for additional concrete and reinforcing required.

Support from diaphragm forms is required under the optional skewed end until cast-in-place concrete has reached 3,000 psi compressive strength.

Prestressed panels shall be brought to saturated surface-dry (SSD) condition just prior to the deck pour. There shall be no free standing water on the panels or in the area to be cast.

The prestressed panel quantities are not included in the table of estimated quantities for the slab.

Reinforcing Steel:  
All dimensions are out to out.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

Minimum clearance to reinforcing steel shall be 1 1/2", unless otherwise shown.

If U1 bars interfere with placement of slab steel, U1 loops may be bent over, as necessary, to clear slab steel.

Deformed welded wire reinforcement (WWR) providing a minimum area of reinforcing perpendicular to strands of 0.22 sq in./ft, with spacing parallel to strands sufficient to ensure proper handling, may be used in lieu of the #3-P2 bars shown. Wire diameter shall not be larger than 0.375 inch. The above alternative reinforcement criteria may be used in lieu of the #3-P3 bars, when required, and placed over a width not less than 2 feet.

The following reinforcing steel shall be tied securely to the strands with the following maximum spacing in each direction:  
#3-P2 bars at 16 inches.  
WWR at 24 inches.

The #3-U1 bars shall be tied securely to #3-P2 bars, to WWR or to strands (when placed between P1 bars) at about 3-foot centers.

Minimum reinforcement steel length shall be 2'-0".

All reinforcement other than prestressing strands shall be epoxy coated.

Precast panels may be in contact with stirrup reinforcing in diaphragms.

S-bars are not listed in the bill of reinforcing.

Cost of S-bars will be considered completely covered by the contract unit price for the slab.

Joint Filler:  
Joint filler shall be preformed fiber expansion joint material in accordance with Sec 1057 or expanded or extruded polystyrene bedding material in accordance with Sec 1073.

Use Slab Haunching Diagram on Sheet No. XX for determining thickness of joint filler within the limits noted in the table of Joint Filler Dimensions.

Thicker material may be used on one or both sides of the girder to reduce cast-in-place concrete thickness to within tolerances.

The same thickness of preformed fiber expansion joint material shall be used under any one edge of any panel except at locations where top flange thickness may be stepped. The maximum change in thickness between adjacent panels shall be 1/2 inch. The polystyrene bedding material may be cut with a transition to match haunch height above top of flange.

Joint filler shall be glued to the girder. When thickness exceeds 1 1/2 inches, the joint filler shall be glued top and bottom. The glue used shall be the type recommended by the joint filler manufacturer.

Edges of panels shall be uniformly seated on the joint filler before slab reinforcement is placed.

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

PRESTRESSED PANELS

DATE PREPARED 2/24/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 5
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	


IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.




Standard Drawing Guidance (do not show on plans):

- ① Modify details if expansion gap is used and add Section B-B at expansion device and additional reference notes as shown on standard drawing for steel structures (PSP06).







PLAN SHOWING PANEL PLACEMENT



BENDING DIAGRAM FOR U1 BAR




SECTION B-B




PLAN OF OPTIONAL TRUNCATED END PANEL


\*\*\* 3" (Min.), 6" (Max.)



PLAN OF OPTIONAL SKEWED END PANEL



PLAN OF SQUARED PANEL



SECTION A-A


Reference Notes:

Plan of Panel Placement:

- (1) S-bars shown are bottom steel in slab between panels and used with squared and truncated end panels only.
- (2) Extend S-bars 18 inches beyond the front face of end bents and int. bents for squared and truncated end panels only.
- (3) Extend S-bars 9 inches beyond edge of girder (Typ.).
- (4) End panels shall be dimensioned 1/2" min. to 1 1/2" max. from the inside face of diaphragm.
- (5) For truncated end panels, use a min. of #5-S bars at 6" crossings in openings, or min. 4x4-W7xW7.
- (6) For end panels only, P1 bars shall be 2'-0" in length and embedded 12". P1 bars will not be required for panels at squared integral end bents.
- (7) #3-P2 bars near edge of panel at bottom (under strands).
- (8) Use #3-P3 bars if panel is skewed 45° or greater.
- (9) Any strand 2'-0" or shorter shall have a #4 reinforcing bar on each side of it, centered between strands. Strands 2'-0" or shorter may then be debonded at the fabricator's option.
- (10) Optional 1/2" x 45° Chamfer one or both sides at bottom.
- (11) P1 bars not required for integral end bents.
- (12) Adjustment in the slab thickness, joint filler, or grade will be necessary if the girder camber after erection differs from plan camber by more than the % of dead load deflection due to the weight of structural steel. No payment will be made for additional labor or materials for the adjustment.
- (13) Contractor shall ensure proper consolidation under and between panels.

Section B-B:

- (14) S-bars shown are used with skewed end panels, or squared end panels of squared structures only. The #5 S-bars shall extend the width of slab (2'-6" lap if necessary) or to within 3 inches of expansion device assemblies.



SECTION C-C

General Notes:

Prestressed Panels:

Concrete for prestressed panels shall be Class A-1 with f'c = 6,000 psi, f'ci = 4,000 psi.

The top surface of all panels shall receive a scored finish with a depth of scoring of 1/8" perpendicular to the prestressing strands in the panels.

Prestressing tendons shall be high-tensile strength uncoated seven-wire low-relaxation strands for prestressed concrete in accordance with AASHTO M 203 Grade 270, with nominal diameter of strand = 3/8" and nominal area = 0.085 sq. in. and minimum ultimate strength = 22.95 kips (270 ksi). Larger strands may be used with the same spacing and initial tension.

Initial prestressing force = 17.2 kips/strand.

The method and sequence of releasing the strands shall be shown on the shop drawings.

Suitable anchorage devices for lifting panels may be cast in panels, provided the devices are shown on the shop drawings and approved by the engineer. Panel lengths shall be determined by the contractor and shown on the shop drawings.

When squared end panels are used at skewed bents, the skewed portion shall be cast full depth. No separate payment will be made for additional concrete and reinforcing required.

Support from diaphragm forms is required under the optional skewed end until cast-in-place concrete has reached 3,000 psi compressive strength.

Prestressed panels shall be brought to saturated surface-dry (SSD) condition just prior to the deck pour. There shall be no free standing water on the panels or in the area to be cast.

The prestressed panel quantities are not included in the table of estimated quantities for slab.

Reinforcing Steel:

All dimensions are out to out.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

Minimum clearance to reinforcing steel shall be 1 1/2", unless otherwise shown.

If U1 bars interfere with placement of slab steel, U1 loops may be bent over, as necessary, to clear slab steel.

Deformed welded wire reinforcement (WWR) providing a minimum area of reinforcing perpendicular to strands of 0.22 sq. in./ft. with spacing parallel to strands sufficient to ensure proper handling, may be used in lieu of the #3-P2 bars shown. Wire diameter shall not be larger than 0.375 inch. The above alternative reinforcement criteria may be used in lieu of the #3-P3 bars, when required, and placed over a width not less than 2 feet.

The following reinforcing steel shall be tied securely to the strands with the following maximum spacing in each direction: #3-P2 bars at 16 inches. WWR at 24 inches.

The #3-U1 bars shall be tied securely to #3-P2 bars, to WWR or to strands (when placed between P1 bars) at about 3-foot centers.

Minimum reinforcement steel length shall be 2'-0".

All reinforcement other than prestressing strands shall be epoxy coated.

Precast panels may be in contact with stirrup reinforcing in diaphragms.

S-bars are not listed in the bill of reinforcing.

Cost of S-bars will be considered completely covered by the contract unit price for the Slab.

Joint Filler:

Joint filler shall be preformed fiber expansion joint material in accordance with Sec 1057 or expanded or extruded polystyrene bedding material in accordance with Sec 1073.

The thickness of the joint filler shall be adjusted to achieve the slab haunching dimension found on Sheet No. (XX). These adjustments shall be within the limits noted in the table of Joint Filler Dimensions.

Thicker material shall be used on one or both sides of the girder to reduce cast-in-place concrete thickness to within tolerances.

The same thickness of material shall be used under any one edge of any panel except at splices, and the maximum change in thickness between adjacent panels shall be 1/4 inch to correct for variations from Girder Camber Diagram. The polystyrene bedding material may be cut to match haunch height above top of flange.

Joint filler shall be glued to the girder. When thickness exceeds 1 1/2 inches, the joint filler shall be glued top and bottom. The glue used shall be the type recommended by the joint filler manufacturer.

Edges of panels shall be uniformly seated on the joint filler before slab reinforcement is placed.

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION



105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.

DATE PREPARED  
2/24/2023  
ROUTE STATE  
DISTRICT SHEET NO.  
6

COUNTY

JOB NO.

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

## PSP06\_St I Guidance

Standard Drawing Guidance (do not show on plans):

- ① Update with correct sheet no.
- ② For wide flange beams, turn off Level 20 & turn on Level 21.
- ③  $XX = G - 1\frac{1}{4}"$  ( $1\frac{1}{2}"$  max.) If  $XX$  equals  $\frac{3}{4}"$ , remove asterisk and note.  
G is from the edge of the splice plate to the centerline of the nearest splice bolt.
- ④ Trade Section B-B as needed or omit if integral end bents.
- ⑤ Replace all expansion gap with integral end bents in "Plan Showing Panels Placement".





Table Showing S2 Bar Lengths			
Int. Bent No. 2		Int. Bent No. 3	
Span 1	Span 2	Span 2	Span 3
__'-__"	__'-__"	__'-__"	__'-__"

Required Lap Length For Bar Splices **	
Bar Size	Splice Length
4	2'-7"
5	3'-3"
6	3'-10"
7	4'-11"

\*\* Unless otherwise shown.

U.I.P., REDECK AND MAKE COMPOSITE EXISTING ( \_\_'- \_\_'- \_\_' ) CONTINUOUS WIDE FLANGE BEAM SPANS

General Notes:

Design Specifications:  
2002 AASHTO LFD (17th Ed.) Standard Specifications  
Seismic Performance Category A

Design Loading:  
HS \_\_-\_\_ (19 \_\_) (Existing)  
HS20-44 (New Construction)  
35 lb/sf Future Wearing Surface  
Earth - 120 lb/cf, Equivalent Fluid Pressure 45 lb/cf  
Fatigue Stress - Case III

Design Unit Stresses:  
Class B-1 Concrete (Barrier) f'c = 4,000 psi  
Class B-2 Concrete (End Bents & Superstructure, except Barrier) f'c = 4,000 psi  
Reinforcing Steel (Grade 60) fy = 60,000 psi

Joint Filler:  
All joint filler shall be in accordance with Sec 1057 for preformed sponge rubber expansion and partition joint filler, except as noted.

Reinforcing Steel:  
Minimum clearance to reinforcing steel shall be 1 1/2", unless otherwise shown.

Miscellaneous:  
Protective coating for concrete bents and piers (Urethane or Epoxy) shall be applied as shown on the bridge plans and in accordance with Sec 711.

Bars bonded in existing concrete not removed shall be cleanly stripped and embedded into new concrete where possible. If length is available, existing bars shall extend into new concrete at least 40 diameters for plain bars and 30 diameters for deformed bars, unless otherwise noted.

Roadway surfacing adjacent to bridge ends shall match new bridge slab surface. (Roadway item)

Outline of existing work is indicated by light dashed lines. Heavy lines indicate new work.


Contractor shall verify all dimensions in field before ordering new material.

The area exposed by the removal of concrete and not covered with new concrete shall be coated with an approved qualified special mortar in accordance with Sec 704.


Rubblized concrete from the existing bridge deck that qualifies as clean fill may be placed on spill slopes at end bents above ordinary high water line (Roadway item).

Traffic Handling:


Structure to be closed during construction. Traffic to be maintained on \_\_\_\_\_ during construction. See roadway plans for traffic control and Sheet No. \_\_\_\_\_ for staged construction details.



DETAIL B



DETAIL A



OPTIONAL SHIFTING  
TOP BARS AT BARRIER

Estimated Quantities		
Item		Total
Removal of Existing Bridge Deck	sq. foot	X
Partial Removal of Substructure Concrete	lump sum	1
Slab on Steel	sq. yard	X
Type D Barrier	linear foot	X
Protective Coating - Concrete Bents and Piers (Urethane)	lump sum	1
Shear Connectors	each	X
Slab Drain	each	X

Cost of any required excavation for bridge will be considered completely covered by the contract unit price for other items.

Estimated Quantities for Slab on Steel		
Item		Total
Class B-2 Concrete	cu. yard	x
Reinforcing Steel (Epoxy Coated)	pound	x

The table of Estimated Quantities for Slab on Steel represents the quantities used by the State in preparing the cost estimate for concrete slabs. The area of the concrete slab will be measured to the nearest square yard longitudinally from end of slab to end of slab and transversely from out to out of bridge slab (or with the horizontal dimensions as shown on the plan of slab). Payment for prestressed panels, stay-in-place corrugated steel forms, conventional forms, all concrete and epoxy coated reinforcing steel will be considered completely covered by the contract unit price for the slab. Variations may be encountered in the estimated quantities but the variations cannot be used for an adjustment in the contract unit price.

Method of forming the slab shall be in accordance with Sec 703. All hardware for forming the slab to be left in place as a permanent part of the structure shall be coated in accordance with ASTM A123 or ASTM B633 with a thickness Class SC 4 and a finish Type I, II or III.

Slab shall be cast-in-place with conventional forming or stay-in-place corrugated steel forms. Precast prestressed panels will not be permitted.

For Optional Stay-In-Place Form Details, see Sheet No. 2.

REPAIRS TO BRIDGE:  
ROUTE \* OVER \*

ROUTE \* FROM \* TO \*  
ABOUT \* MILES \* OF \*  
BEGINNING STATION ± (MATCH EXISTING)

DATE PREPARED  
12/22/2022

ROUTE  
STATE  
DISTRICT  
SHEET NO.  
BR REDECKO  
COUNTY

JOB NO.

CONTRACT ID.


PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION



105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-273-6636)

IF A SEAL IS PRESENT ON THIS SHEET IT HAS BEEN ELECTRONICALLY SEALED AND DATED.


Standard Drawing Guidance (do not show on plans):  
(Turn off Level Bridge-Constructions to hide)

- ① Remove if not required; may be incorporated into half section slab details.
- ② Use this note only when specified in Bridge Memo or Design Layout.
- ③ For skewed bridges, add these items to section details to call out varied transverse bars at end bent.

④ Bar spacing shown is for Type D barrier. Below spacing may be used for Type H barrier.

Roadway	22 feet	22 feet	24 feet	24 feet	26 feet	26 feet
Beam Spa.	4 @ 6'-8"	4 @ 6'-0"	4 @ 6'-10"	4 @ 6'-8"	4 @ 7'-8"	4 @ 7'-4"
Bar Spa.	7"	7½"	8"	7½"	8"	8"


Roadway	28 feet	30 feet	32 feet	34 feet	38 feet	
Beam Spa.	4 @ 8'-0"	4 @ 8'-8"	4 @ 9'-4"	5 @ 7'-6"	5 @ 8'-6"	
Bar Spa.	8"	8"	8"	8"	6"	



ROCK BLANKET ON SPILL SLOPES

Use when Rock Blanket is specified on BR Memo.

Type H Barrier



Structural Steel Protective Coating:

Protective Coating: System G in accordance with Sec 1081 except thinners are not permitted.

Surface Preparation: Surface preparation of the existing steel shall be in accordance with Sec 1081 for Overcoating of Structural Steel. The cost of surface preparation will be considered completely covered by the contract lump sum unit price per sq. foot for Surface Preparation for Overcoating Structural Steel (System G).

Field Coat(s): The color of the field overcoat shall be Gray (Federal Standard #26373) Brown (Federal Standard #30045) Black (Federal Standard #17038) Dark Blue (Federal Standard #25052) Bright Blue (Federal Standard #25095) and shall be applied in accordance with Sec 1081.10.3.4. The cost of the intermediate field coat will be considered completely covered by the contract lump sum unit price per sq. foot for Intermediate Field Coat (Sytem G). The cost of the finish field coat will be considered completely covered by the contract lump sum unit price per sq. foot for Finish Field Coat (System G).

(Existing Bearings at End Bents and Int. Bents)

Structural Steel Protective Coating:

Protective Coating: System G in accordance with Sec 1081. All existing bearings shall be recoated with System G.

Surface Preparation: Surface preparation of the existing steel shall be in accordance with Sec 1081 for Recoating of Structural Steel (System G, H or I) with organic inorganic zinc primer. The cost of surface preparation will be considered completely covered by the contract unit price for Recoating Existing Bearings.

Prime Coat: The cost of the prime coat will be considered completely covered by the contract unit price for Recoating Existing Bearings. Tint of the prime coat for System G shall be similar to the color of the field coat to be used.


Field Coat: The color of the finish field coat shall be Gray (Federal Standard #26373). The cost of the intermediate field coat will be considered completely covered by the contract unit price for Recoating Existing Bearings. The cost of the finish field coat will be considered completely covered by the contract unit price for Recoating Existing Bearings.

Sec 1081.10.4.6 shall be modified such that the word "RECOATED" is replaced by the word "RECOATED - SYSTEM G - BEARINGS ONLY".





(Structures with Exposed Piling)

Structural Steel Protective Coating:

All exposed surfaces of the existing structural steel piles shall be coated with one 6-mil thickness of aluminum gray epoxy-mastic primerapplied over an SSPC-SP3 surface preparation in accordance with Sec 1081. The bituminous coating shall be applied one foot above and one foot below the existing ground line and in accordance with Sec 702. These protective coatings will not be required below the normal low water line. The cost of surface preparation will be considered completely covered by the contract lump sum price for Surface Preparation for Applying Epoxy-Mastic Primer. The cost of the aluminum gray epoxy-mastic primer and bituminous coating will be considered completely covered by the contract lump sum price for Aluminum Gray Epoxy-Mastic Primer.



TYPICAL SECTION THRU SLAB  
22' RDWY-4 BEAMS @ 6'-8"  
\*\*\* SKEWED BRIDGES \*\*\*




















32' RDWY-4 BEAMS @ 9' -4"




34' RDWY-5 BEAMS @ 7' -6"



TYPICAL SECTION THRU SLAB

38' RDWY-5 BEAMS @ 8'-6"



## DETAILS OF CONCRETE REMOVAL AT END BENTS

The cost of concrete removal as shown will be considered completely covered by the contract unit price for Removal of Existing Bridge Deck. Vertical backwall and wingwall reinforcement to be cut off one inch below concrete removal surface and the resulting holes shall be filled with a qualified special mortar.

A smooth, level surface shall be provided at Bent No.      removal lines.

General Notes:

### Stay-In-Place Forms:

Corrugated steel forms, supports, closure elements and accessories shall be in accordance with grade requirement and coating designation G165 of ASTM A653. Complete shop drawings of the permanent steel deck forms shall be required in accordance with Sec 1080.

Corrugations of stay-in-place forms shall be filled with an expanded polystyrene material. The polystyrene material shall be placed in the forms with an adhesive in accordance with the manufacturer's recommendations.

Form sheets shall not rest directly on the top of beam flanges. Sheets shall be securely fastened to form supports with a minimum bearing length of one inch on each end. Form supports shall be placed in direct contact with the flange. Welding on or drilling holes in the beam flanges will not be permitted. All steel fabrication and construction shall be in accordance with Sec 1080 and 712. Certified field welders will not be required for welding of the form supports.

The design of stay-in-place corrugated steel forms is per manufacturer which shall be in accordance with Sec 703 for false work and forms. Maximum actual weight of corrugated steel forms allowed shall be 4 psf assumed for beam loading.

The contractor shall provide a method of preventing the direct contact of the stay-in-place forms and connection components with uncoated weathering steel members that is approved by the engineer.

### Pouring and Finishing Slab:


The contractor shall provide bracing necessary for lateral and torsional stability of the beams during construction of the concrete slab and remove the bracing after the slab has attained 75% design strength. Contractor shall not weld on or drill holes in the beams. The cost for furnishing, installing, and removing bracing will be considered completely covered by the contract unit price for Slab on Steel.

Slab shall be poured upgrade from end to end at a minimum rate of 25 cubic yards per hour.



Alternate pour sequences may be submitted to the engineer for approval. Keyed construction joints shall be provided between pours.

Haunching:

(1) Slab is to be considered a uniform thickness as shown on the plans. Haunching will vary. See front sheet for slab thickness.







## OPTIONAL STAY-IN-PLACE FORM DETAILS



ELEVATION SHOWING SHEAR  
CONNECTOR SPACING

TABLE SHOWING SHEAR CONNECTOR UNIT SPACING				
Span	S.C. per unit	A	B	C
1	2	X"±	XX Units @ 8" cts.	X"±
2	2	X"±	XX Units @ 8" cts.	X"±
3	2	X"±	XX Units @ 8" cts.	X"±
Total shear connectors required				XXXX




PLAN OF SHEAR CONN. (2 PER UNIT)


### DETAILS OF SHEAR CONNECTORS

The cost of supplying and installing shear connectors will be considered completely covered by the contract unit price for Shear Connectors.

Shear connectors shall be in accordance with Sec 712, 1037 & 1080.



TYPICAL SECTION THRU  
END BENTS 1 & 4 SHOWING  
PROTECTIVE COATING



TYPICAL SECTION THRU  
INT. BENTS 2 & 3 SHOWING  
PROTECTIVE COATING

DATE PREPARED	
10/17/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	2

COUNTY

JOB NO.

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

[illegible]MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

REDECK02\_rehab\_details      Guidance & Alternate Details


Standard Drawing Guidance (do not show on plans):

Some notes on the standard redecking template drawings are not shown in EPG 751.50 Standard Detailing Notes.


Remove details that do not apply.

Check slab pouring sequencing and revise notes as required.


Including alternate pour sequences is per approval of Structural Project Manager or Liaison.




DETAILS OF CONCRETE REMOVAL AT END BENTS




ELEVATION SHOWING SHEAR CONNECTOR SPACING FOR END BEAMS




ELEVATION SHOWING SHEAR CONNECTOR SPACING FOR COMBINED BEARING & MID SPAN BEAMS



ELEVATION SHOWING SHEAR CONNECTOR SPACING FOR INT. BENT BEARING BEAMS



ELEVATION SHOWING SHEAR CONNECTOR SPACING FOR END BEAMS








ELEVATION SHOWING SHEAR CONNECTOR SPACING FOR MID SPAN & BEARING BEAMS


TABLE SHOWING SHEAR CONNECTOR UNIT SPACING					
Beam	S.C. per unit	A	B	C	D
End Beam (Spans 1-2 & 5-4)	x	__"±	__ Units @ __" cts.	__"±	--
Brg. Beam (Bent 2 & Span 2-3) & Brg. Beam (Bent 4 & Span 4-3)	x	__"±	__ Units @ __" cts.	__"±	__ Units @ __" cts.
Brg. Beam (Bent 3)	x	__"±	__ Units @ __" cts.	__"±	--
Total shear connectors required					xxx

TABLE SHOWING SHEAR CONNECTOR UNIT SPACING				
Beam	S.C. per unit	A	B	C
End Beam (SpanS 1-2 & 3-4)	x	__"±	__ Units @ __" cts.	__"±
Brg. Beam (Bents 2 & 3)	x	__"±	__ Units @ __" cts.	__"±
Mid Span (Span 2-3)	x	__"±	__ Units @ __" cts.	__"±
Total shear connectors required				xxx


CONTINUOUS SPANS



Use when replacing expansion joint with sliding slab.




PART ELEVATION OF EXTERIOR BEAM SHOWING COVER PLATE INSTALLATION  
SPAN (X-X) AND SPAN (X-X)



PART ELEVATION OF EXTERIOR BEAM SHOWING COVER PLATE INSTALLATION  
SPAN (X-X)

Standard Drawing Guidance (do not show on plans):

- ① Use Type 3 for weathering steel bolted connections and Type 1 for plain or galvanized steel bolted connections.



TYPICAL DETAIL OF THE  
ENDS OF COVER PLATES  
(BOTTOM VIEW)

Notes:

Beam with end-bolted cover plates shall be installed in the following sequence after existing bridge deck is removed:

1. Drill holes in cover plate and flange.
2. Clean faying surfaces. (See Special Provisions)
3. Install and tighten bolts.
4. Weld cover plate to flange.

Fabricated Structural Steel shall be ASTM A709 Grade 36, except as noted.

Payment for \_\_\_ pounds of new cover plates complete in place will be considered completely covered by the contract lump sum price for Strengthening Existing Beams.

Notch toughness is required for all cover plates.

STRENGTHENING EXISTING BEAMS

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of \_

DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 3

COUNTY
JOB NO.
CONTRACT ID.
PROJECT NO.
BRIDGE NO.

DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-273-6636)
--	--

U.I.P. AND REHABILITATE EXISTING (X'-X'-X') SPANS (SKEW: x)

SEC/SUR \* TWP \* RGE \*

DATE PREPARED	
10/17/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	000
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	

Estimated Quantities			
Item			Total
Total Surface Hydro Demolition	216-10.01	sq. yard	X
Removal of Concrete Wearing Surface	216-15.02	sq. foot	X
Removal of Existing Deck Repair	216-15.03	sq. foot	X
* Supplementary Wearing Surface Material	505-00.04	cu. yard	X
Latex Modified Concrete Wearing Surface	505-20.00	sq. yard	X
Substructure Repair (Formed)	704-01.01	sq. foot	X
Substructure Repair (Unformed)	704-01.02	sq. foot	X
Superstructure Repair (Unformed)	704-01.03	sq. foot	X
Half-Sole Repair	704-01.04	sq. foot	X
Full Depth Repair	704-01.06	sq. foot	X
Slab Edge Repair (Bridges)	704-01.07	linear foot	X
Cleaning and Epoxy Coating	704-01.13	sq. foot	X

Replace  
as  
required

B3.8 \* Supplementary wearing surface material for monolithic deck repair will be paid for at the fixed unit price in accordance with Sec 109.  
Note B3.9 if required.

General Notes:

- A1.1 Design Specifications:  
2002 AASHTO LFD (17th Ed.) Standard Specifications  
Bridge Deck Rating =
- A1.2 Design Loading: Year      Year  
HS20-44 Modified ( ) and Military 24,000 lb Tandem Axle ( )
- A1.3 Design Unit Stresses:  
Class B-2 Concrete (Half-Sole and Full Depth Repair)    f'c = 4,000 psi  
Miscellaneous:
- I1.0.1 Roadway surfacing adjacent to bridge ends shall match new bridge wearing surface (roadway item).
- I1.0.2 All concrete repairs shall be in accordance with Sec 704, unless otherwise noted.
- I1.1 Outline of existing work is indicated by light dashed lines. Heavy lines indicate new work.
- I1.2 Contractor shall verify all dimensions in field before ordering new material.
- I1.10 In order to maintain grade and a minimum thickness of wearing surface as shown on plans it may be necessary to use additional quantities of wearing surface at various locations throughout the structure. The cost of furnishing and installing the wearing surface will be considered completely covered in the contract unit price, including all additional labor, materials or equipment for variations in thickness of wearing surface.
- Traffic Handling:
- A3.8 Structure to be closed during construction. Traffic to be maintained on during construction. See roadway plans for traffic control and Sheet No. for staged construction details.

I1.0.3 (If  
required)

REPAIRS TO BRIDGE: ROUTE \*  
OVER \*  
ROUTE \* FROM \* TO \*  
ABOUT \* MILES \* OF \*  
BEGINNING STATION ± (Match Existing)

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. 1 of



STANDARD DRAWING GUIDANCE  
(do not show on plans)

This is an index of Standard Drawing details. Draw typical section as required and scale to fit within attached border. Use appropriate deck repair details and modify as required (match orientation of actual reinforcement).

For bridges with epoxy coated steel, see Sec 710 for repairing bars and add notes as necessary. See SPM.

Wearing surface thickness can vary according to grade elevation requirements and minimum barrier curb height requirements. Maximum thickness should be limited to 3" (Ref. Organizational Results Research Report ORO6.004, May 2006). Limit excludes reinforced concrete slab wearing surfaces.

Will need to adjust wearing surface thickness when detailing a thin wearing surface (1" or less), but it is a preferred detailing practice to show a discernable thickness on the plans. No thickness is shown for crack filler application.

- A

Show difference as 

plus/minus X"±

 (see Bridge Memo or SPM).  
e.g. 

Match existing grade plus 2¼"±
- B

Identify new wearing surface (see Bridge Memo or SPM) and specify minimum thickness in deck details.
- C

Identify existing wearing surface and thickness, see Bridge Memo or existing plans.
- D


See Bridge Memo or SPM, typically 1/2". Use 1" if more than 30% of existing deck needs repair. Verify there will be a minimum of 1/2" of concrete above the top bars after scarification.
- E

See Bridge Memo or SPM, typically 1/2".
- F

See existing plans.
- G

Use appropriate reference (℄ Structure, ℄ Roadway, ℄ Median, etc.)
- H

Cleaning and epoxy coating is preferred because of the relative short life of slab edge repair and unformed repair especially when over traffic. However in urban regions repairing the overhang may be preferred. Consult with SPM or SLE.




- 1


Scarification prior to adding first wearing surface or removing a portion of the deck when removing an existing wearing surface is not required for seal coat, asphalt, UBAWS, epoxy polymer or MMA polymer slurry wearing surfaces.

FILLED JOINT DETAILS FOR ALL APPLICATIONS

FOR EPOXY POLYMER OR MMA POLYMER SLURRY WEARING SURFACE




SECTION THRU JOINT  
(EPOXY POLYMER OR MMA POLYMER SLURRY)




SECTION THRU JOINT  
(EPOXY POLYMER OR MMA POLYMER SLURRY)

FOR ALL OTHER WEARING SURFACES




\* Width of joint seal to be not less than the depth and not more than twice the depth of the joint seal.

SECTION THRU JOINT  
(POLYESTER POLYMER, LATEX, LOW SLUMP OR SILICA FUME CONCRETE)



SECTION THRU JOINT  
(ASPHALTIC CONCRETE WEARING SURFACE)



SECTION THRU JOINT  
(ASPHALTIC CONCRETE WEARING SURFACE)

# Hydro Demolition Case 1:      Monolithic Deck Repair After Hydro Demolition

STANDARD DRAWING GUIDANCE (do not show on plans):

ⓈMay be used with the following concrete wearing surfaces:


- 1 3/4" to 3" Latex Modified
- 2 1/4" to 3" Silica Fume
- 1 3/4" to 3" Latex Modified Very Early Strength
- 1 3/4" to 3" CSA Cement Very Early Strength
- 3" to 4" Steel Fiber Reinforced

If optional concrete wearing surface is specified and either low slump or polyester polymer is an option:


Use appropriate details below on first sheet and add a sheet title using the allowed options for the below details,

e.g. "LATEX MODIFIED CONCRETE DETAILS"

## (Adding First Wearing Surface)



## (Replacing Existing Wearing Surface)



# Hydro Demolition Case 2: Conventional Deck Repair After Hydro Demolition

STANDARD DRAWING GUIDANCE (do not show on plans):


- Ⓒ May be used with the following concrete wearing surfaces:
  - 2 1/4" to 3" Low Slump
  - 3/4" to 3" Polyester Polymer

If optional concrete wearing surface is specified and either low slump or polyester polymer is an option:


Use appropriate details below on second sheet and add a sheet title using the allowed options for the below details,

e.g. "LOW SLUMP CONCRETE DETAILS"

## (Adding First Wearing Surface)



## (Replacing Existing Wearing Surface)



## Conventional Deck Repair Only

STANDARD DRAWING GUIDANCE (do not show on plans):

May be used with all wearing surfaces.


- ② 2 1/4" to 3" Low Slump Concrete
- 1 3/4" to 3" Latex Modified Concrete
- 2 1/4" to 3" Silica Fume Concrete
- 1 3/4" to 3" Latex Modified Very Early Strength Concrete
- 1 3/4" to 3" CSA Cement Very Early Strength Concrete
- 3" to 4" Steel Fiber Reinforced Concrete
- 1/4" Epoxy Polymer
- 3/4" to 3" Polyester Polymer Concrete
- 3/8" MMA Polymer Slurry
- 4" to 5" Reinforced Concrete Slab
- 3/8" Chip Seal Grade A1
- 1" to 3" Alternate Asphaltic Concrete
- 1/2" to 3/4" Alternate Ultrathin Bonded Asphalt

Scarification not required with the following wearing surfaces:


- Seal Coat
- Asphalt
- UBAWS
- Epoxy Polymer
- MMA Polymer Slurry

Or when applying concrete crack filler.

### (Adding First Wearing Surface or Applying Concrete Crack Filler)



### (Replacing Existing Wearing Surface)



U.I.P. AND REHABILITATE EXISTING (X'-X'-X') \_\_\_\_ SPANS (SKEW: x)

SEC/SUR \* TWP \* RGE \*

DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 2
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	

Estimated Quantities			
Item			Total
Total Surface Hydro Demolition	216-10.01	sq. yard	X
Removal of Concrete Wearing Surface	216-15.02	sq. foot	X
Removal of Existing Deck Repair	216-15.03	sq. foot	X
* Supplementary Wearing Surface Material	505-00.04	cu. yard	X
Latex Modified Concrete Wearing Surface	505-20.00	sq. yard	X
Substructure Repair (Formed)	704-01.01	sq. foot	X
Substructure Repair (Unformed)	704-01.02	sq. foot	X
Superstructure Repair (Unformed)	704-01.03	sq. foot	X
Half-Sole Repair	704-01.04	sq. foot	X
Full Depth Repair	704-01.06	sq. foot	X
Slab Edge Repair (Bridges)	704-01.07	linear foot	X
Cleaning and Epoxy Coating	704-01.13	sq. foot	X

B3.8 \* Supplementary wearing surface material for monolithic deck repair will be paid for at the fixed unit price in accordance with Sec 109.

Note B3.9 if required

General Notes:

A1.1 Design Specifications:

2002 AASHTO LFD (17th Ed.) Standard Specifications  
Bridge Deck Rating =

A1.2 Design Loading:

HS20-44 Modified ( ) and Military 24,000 lb Tandem Axle ( )

A1.3 Design Unit Stresses:

Class B-2 Concrete (Half-Sole and Full Depth Repair) f'c = 4,000 psi

Miscellaneous:

I1.0.1 Roadway surfacing adjacent to bridge ends shall match new bridge wearing surface (roadway item).

I1.0.3 (If required)

I1.0.2 All concrete repairs shall be in accordance with Sec 704, unless otherwise noted.

I1.1 Outline of existing work is indicated by light dashed lines. Heavy lines indicate new work.

I1.2 Contractor shall verify all dimensions in field before ordering new material.

I1.10 In order to maintain grade and a minimum thickness of wearing surface as shown on plans it may be necessary to use additional quantities of wearing surface at various locations throughout the structure. The cost of furnishing and installing the wearing surface will be considered completely covered in the contract unit price, including all additional labor, materials or equipment for variations in thickness of wearing surface.

Traffic Handling:

A3.8 Structure to be closed during construction. Traffic to be maintained on during construction. See roadway plans for traffic control and Sheet No. for staged construction details.

REPAIRS TO BRIDGE: ROUTE \*  
OVER \*

ROUTE \* FROM \* TO \*  
ABOUT \* MILES \* OF \*  
BEGINNING STATION ± (Match Existing)

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. 1 of

Hydro Demolition Case 1: Monolithic Deck Repair After Hydro Demolition


STANDARD DRAWING GUIDANCE (do not show on plans):

- Ⓑ May be used with the following concrete wearing surfaces:

  - 1 3/4" to 3" Latex Modified
  - 2 1/4" to 3" Silica Fume
  - 1 3/4" to 3" Latex Modified Very Early Strength
  - 1 3/4" to 3" CSA Cement Very Early Strength
  - 3" to 4" Steel Fiber Reinforced
- If optional concrete wearing surface is specified and either low slump or polyester polymer is an option:

Use appropriate details below on first sheet and add a sheet title using the allowed options for the below details,

e.g. "LATEX MODIFIED CONCRETE DETAILS"



# Hydro Demolition Case 2: Conventional Deck Repair After Hydro Demolition

STANDARD DRAWING GUIDANCE (do not show on plans):


May be used with the following concrete wearing surfaces:

- 2 1/4" to 3" Low Slump
- 3/4" to 3" Polyester Polymer

If optional concrete wearing surface is specified and either low slump or polyester polymer is an option:

Use appropriate details below on second sheet and add a sheet title using the allowed options for the below details,

e.g. "LOW SLUMP CONCRETE DETAILS"





# Conventional Deck Repair Only


STANDARD DRAWING GUIDANCE (do not show on plans):

- May be used with all wearing surfaces.
- 2 1/4" to 3" Low Slump Concrete
  - 3/4" to 3" Latex Modified Concrete
  - 1/4" to 3" Silica Fume Concrete
- 3/4" to 3" Latex Modified Very Early Strength Concrete
- 3/4" to 3" CSA Cement Very Early Strength Concrete
- 3" to 4" Steel Fiber Reinforced Concrete
- 1/4" Epoxy Polymer
- 3/4" to 3" Polyester Polymer Concrete
- 3/8" MMA Polymer Slurry
- 4" to 5" Reinforced Concrete Slab
- 3/8" Chip Seal Grade A1
- 1" to 3" Alternate Asphaltic Concrete
- 1/2" to 3/4" Alternate Ultrathin Bonded Asphalt


Scarification not required with the following wearing surfaces:  
Seal Coat  
Asphalt  
UBAWS  
Epoxy Polymer  
MMA Polymer Slurry

Or when applying concrete crack filler.

(Adding First Wearing Surface or Applying Concrete Crack Filler)



(Replacing Existing Wearing Surface)



STANDARD DRAWING GUIDANCE (do not show on plans)

This is an index of Standard Drawing details. Draw typical section as required and scale to fit within attached border. Use appropriate deck repair details and modify as required (match orientation of actual reinforcement).

For bridges with epoxy coated steel, see Sec 710 for repairing bars and add notes as necessary. See SPM.

Wearing surface thickness can vary according to grade elevation requirements and minimum barrier curb height requirements. Maximum thickness should be limited to 3" (Ref. Organizational Results Research Report OR06.004, May 2006). Limit excludes reinforced concrete slab wearing surfaces.

Will need to adjust wearing surface thickness when detailing a thin wearing surface (1" or less), but it is a preferred detailing practice to show a discernable thickness on the plans. No thickness is shown for crack filler application.

Consideration shall be made for additional notes for repairing deterioration of the precast prestressed panels. See SPM.

The Prestressed Panel Joint Repair detail is shown transverse because typically deterioration follows the strand closest to the panel edge, referred to as a "joint".

(A) Show difference as plus/minus X"±, see Bridge Memo or SPM.

e.g. Match existing grade plus 2¼"±

(B) Identify new wearing surface (See Bridge Memo or SPM). Specify minimum thickness in deck details.

(C) Identify existing wearing surface and thickness, see Bridge Memo or existing plans.


(D) See Bridge Memo or SPM, typically 1/2". Use 1" if more than 30% of existing deck need repair. Verify there will be a minimum of 1/2" of concrete above the top bars after scarification.

(E) See Bridge Memo or SPM, typically 1/2".

(F) See existing plans.

(G) Use appropriate reference (☐ Structure, ☐ Roadway, ☐ Median, etc.)

(H) Cleaning and epoxy coating is preferred because of the relative short life of slab edge repair and unformed repair especially when over traffic. However in urban regions repairing the overhang may be preferred. Consult with SPM or SLE.




(1) Scarification prior to adding first wearing surface or removing a portion of the deck when removing an existing wearing surface is not required for seal coat, asphalt, UBAWS, epoxy polymer or MMA polymer slurry wearing surfaces.

(2) The following note will be required if concrete removal exposing prestressing strands is anticipated.


Adequate precaution shall be taken to prevent any nicks or cuts of the prestressing strands.

If full depth repair thru panels is anticipated additional deck repair details will be required. Details shown are for conventional deck repair post-hydro demolition when adding first wearing surface. Details for other cases are similar.



If severe panel deterioration is anticipated at the strand ends (within the development lengths of the strands) either at a transverse joint or in the interior between transverse joints, a repair method will need to be expertly developed. Contact the Development Section and/or reference similar repairs to Bridge A4729. One solution is to show the limits of strand development and require a hold point on the plans for engineer review when panel deterioration is discovered within these limits.

Add note: (5) One inch vertical side shall be established outside the deteriorated area. See Sec 704.




\*\* Hold Point: Concrete removal exposing prestressing strands within a special repair zone shall require engineer approved repair.


SDG: This will allow time for bridge office to assess situation and develop repair method.

FILLED JOINT DETAILS FOR ALL APPLICATIONS

FOR EPOXY POLYMER OR MMA POLYMER SLURRY WEARING SURFACE




SECTION THRU JOINT  
(EPOXY POLYMER OR MMA POLYMER SLURRY)




SECTION THRU JOINT  
(EPOXY POLYMER OR MMA POLYMER SLURRY)

FOR ALL OTHER WEARING SURFACES




\* Width of joint seal to be not less than the depth and not more than twice the depth of the joint seal.

SECTION THRU JOINT  
(POLYESTER POLYMER, LATEX, LOW SLUMP OR SILICA FUME CONCRETE)





SECTION THRU JOINT  
(ASPHALTIC CONCRETE WEARING SURFACE)



SECTION THRU JOINT  
(ASPHALTIC CONCRETE WEARING SURFACE)

If severe panel deterioration is anticipated outside the development lengths of the strands at a transverse joint, it is advisable to consider full depth repair even if not required from above. If only cleaned and coated, there is a chance new reflection cracks will appear and the strand deterioration will accelerate due to chlorides being trapped behind the epoxy.





# Hydro Demolition Case 1A:

Zoned Conventional Deck Repair Before Hydro Demolition and Non-Zoned Monolithic Deck Repair After Hydro Demolition

(Adding First Wearing Surface)

Replace as required

Estimated Quantities			
Item			Total
Scarification of Bridge Deck	216-10.00	sq. yard	X
Total Surface Hydro Demolition	216-10.01	sq. yard	X
Removal of Existing Deck Repair	216-15.03	sq. foot	X
Supplementary Wearing Surface Material	505-00.04	cu. yard	X
Latex Modified Concrete Wearing Surface	505-20.00	sq. yard	X
Substructure Repair (Formed)	704-01.01	sq. foot	X
Substructure Repair (Unformed)	704-01.02	sq. foot	X
Superstructure Repair (Unformed)	704-01.03	sq. foot	X
Half-Sole Repair	704-01.04	sq. foot	X
Full Depth Repair	704-01.06	sq. foot	X
Slab Edge Repair (Bridges)	704-01.07	linear foot	X
Cleaning and Epoxy Coating	704-01.13	sq. foot	X

STANDARD DRAWING GUIDANCE (do not show on plans):

Use for the following concrete wearing surfaces:

- (B)
- 1 3/4" to 3" Latex Modified
  - 2 1/4" to 3" Silica Fume
  - 1 3/4" to 3" Latex Modified Very Early Strength
  - 1 3/4" to 3" CSA Cement Very Early Strength
  - 3" to 4" Steel Fiber Reinforced

If optional concrete wearing surface is specified and low slump or polyester polymer is an option:

1. Add the allowed options in parentheses to the typical section title below and also to the RHB03e sheet title.
2. Add to this sheet the typical section from Sheet RHB03e with "(Low Slump Concrete)" added to the title.
3. Add "(Low Slump Concrete)" to the RHB03f sheet title and revise the sheet number from two to three. Sheet RHB03e will not be used.

B3.8 \* Supplementary wearing surface material for monolithic deck repair will be paid for at the fixed unit price in accordance with Sec 109.

B3.9 (If required)

## General Notes:

A1.1 Design Specifications:

2002 AASHTO LFD (17th Ed.) Standard Specifications  
Bridge Deck Rating =

A1.2 Design Loading:

HS20-44 Modified ( ) and Military 24,000 lb Tandem Axle ( )

A1.3 Design Unit Stresses:

Class B-1 Concrete (Half-Sole and Full Depth Repair) f'c = 4,000 psi

Miscellaneous:

11.0.1 Roadway surfacing adjacent to bridge ends shall match new bridge wearing surface (roadway item).

11.0.3 (If required)

11.0.2 All concrete repairs shall be in accordance with Sec 704, unless otherwise noted.

11.1 Outline of existing work is indicated by light dashed lines. Heavy lines indicate new work.

11.2 Contractor shall verify all dimensions in field before ordering new material.

11.10 In order to maintain grade and a minimum thickness of wearing surface as shown on plans it may be necessary to use additional quantities of wearing surface at various locations throughout the structure. The cost of furnishing and installing the wearing surface will be considered completely covered in the contract unit price, including all additional labor, materials or equipment for variations in thickness of wearing surface.

Traffic Handling:

A3.8 Structure to be closed during construction. Traffic to be maintained on during construction. See roadway plans for traffic control and Sheet No. for staged construction details.

REPAIRS TO BRIDGE: ROUTE \* OVER \*

ROUTE \* FROM \* TO \*  
ABOUT \* MILES \* OF \*  
BEGINNING STATION ± (Match Existing)


Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.




Sheet No. 1 of

DATE PREPARED	10/17/2023
ROUTE	STATE
DISTRICT	MO
	SHEET NO.
	3
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
MDOT	
105 WEST CAPITOL	
JEFFERSON CITY, MO 65102	
1-888-ASK-MDOT (1-888-275-6636)	




Three spans shown, detail for two spans is on the sheet RHB03f. Detail for four spans is on sheet RHB03d. Detail for five spans is on sheet RHB03h.




PART PLAN OF SLAB SHOWING SPECIAL REPAIR ZONES




DECK REPAIR INSIDE SPECIAL REPAIR ZONES (BEFORE HYDRO DEMOLITION)



DECK REPAIR OUTSIDE SPECIAL REPAIR ZONES (AFTER HYDRO DEMOLITION)



DETAIL A



DETAIL B

- (1) **D** " scarification of existing deck
- (2) 1" vertical side shall be established outside the deteriorated area.
- (3) Total surface hydro demolition of sound concrete, measured to mortar line:
- (4) **E** " minimum inside special repair zones
- (4) **B** " minimum outside special repair zones
- (4) **B** concrete wearing surface:
- " minimum inside special repair zones
- " minimum outside special repair zones
- (5) Original thickness of top slab

DECK REPAIR DETAILS

Remove notes for repairs not required, possibly entire steps.

Replace with Note 13.3 for structures with single column bents.

Deck Repair Notes:

- Order of Repair:
1. Scarify existing deck **D** ".
  2. Power wash deck to identify sound and unsound existing deck repair.
  3. Inside special repair zones, complete the following repairs:
    - a. Removal of existing deck repair
    - b. Half-sole repair
    - c. Full depth repair
  4. Outside special repair zones, remove existing deck repair.
  5. Complete total surface hydro demolition, removing **E** " minimum of sound concrete inside special repair zones and removing **E** " minimum of sound concrete and all deteriorated concrete outside special repair zones.
  6. Sound deck and if needed complete incidental concrete removal.
  7. Outside special repair zones, complete full depth repair.
  8. Place new wearing surface including additional material for areas of monolithic deck repair.

**Special Repair Zones:**

13.2 Deck repair required in the areas designated as special repair zones shall be completed before hydro demolition in alphabetical sequence beginning with Zone A. Zones with the same letter designation may be repaired at the same time. Hydro demolition shall not move forward until the repairs in all special repair zones are completed and properly cured.

- 13.4 Any deck repair in areas not designated as a special repair zone shall be completed after hydro demolition.
- 13.5 Removal and deck repair shall be completed in one special repair zone and concrete shall have attained a compressive strength of 3200 psi before work can be started in the next special repair zone.
- 13.16 Total width of full depth repair shall not exceed 1/3 of the deck width at one time. For any area of deck repair that extends over a web and is more than 18 inches in length along the web, the concrete removal including removal with hydro demolition shall stop at the centerline of web and repair completed in this area. Prior to continuing work in this area, the concrete shall have attained a compressive strength of 3200 psi. No traffic shall be permitted over the web that is undergoing repair.
- 13.17 When the full depth repair extends over a diaphragm or web and the deteriorated concrete extends into the diaphragm or web, all deteriorated concrete shall be removed and replaced as full depth repair. Concrete in webs shall not be removed below the slab haunch of the girder without prior review and approval from the engineer.
- 13.20 Interior falsework installed by the contractor resting on the bottom slab shall be removed where entry access is available.
- 13.21 If any single repair area does not exceed 9 square feet in size and the total repair area within a special repair zone does not exceed 27 square feet, the special repair zone may repaired at the same time as an adjacent zone.
- 13.22 Half-sole repair in the special repair zone, on either side of the intermediate bents, shall be to a depth that will not expose half the diameter of the longitudinal reinforcing bar. Full depth repair shall be made when removal of deteriorated concrete exposes half or more of the diameter of the longitudinal reinforcing bar.

Detailed  
Checked


Note: This drawing is not to scale. Follow dimensions.

Sheet No. of


DATE PREPARED		10/17/2023	
ROUTE		STATE	
DISTRICT		MO	
		SHEET NO.	
		4	
COUNTY			
JOB NO.			
CONTRACT ID.			
PROJECT NO.			
BRIDGE NO.			
DESCRIPTION			
		DATE	
		</	








PART PLAN OF SLAB SHOWING SPECIAL REPAIR ZONES




DECK REPAIR INSIDE SPECIAL REPAIR ZONES (BEFORE HYDRO DEMOLITION)

DECK REPAIR OUTSIDE SPECIAL REPAIR ZONES (AFTER HYDRO DEMOLITION)



DETAIL A



DETAIL B

- (1) Removal of existing  $\pm$  wearing surface plus  $\pm$  of existing deck
- (2) 1" vertical side shall be established outside the deteriorated area.
- (3) Total surface hydro demolition of sound concrete, measured to mortar line:
- $\pm$  minimum inside special repair zones
- $\pm$  minimum outside special repair zones
- (4)  $\pm$  concrete wearing surface:
- $\pm$  minimum inside special repair zones
- $\pm$  minimum outside special repair zones
- (5) Original thickness of top slab minus previous scarification

DECK REPAIR DETAILS

Deck Repair Notes:

- Order of Repair:
1. Remove existing wearing surface plus  $\pm$  of existing deck.
  2. Power wash deck to identify sound and unsound existing deck repair.
  3. Inside special repair zones, complete the following repairs:
    - a. Removal of existing deck repair
    - b. Half-sole repair
    - c. Full depth repair
  4. Outside special repair zones, remove existing deck repair.
  5. Complete total surface hydro demolition, removing  $\pm$  minimum of sound concrete inside special repair zones and removing  $\pm$  minimum of sound concrete and all deteriorated concrete outside special repair zones.
  6. Sound deck and if needed complete incidental concrete removal.
  7. Outside special repair zones, complete full depth repair.
  8. Place new wearing surface including additional material for areas of monolithic deck repair.

13.2 Deck repair required in the areas designated as special repair zones shall be completed before hydro demolition in alphabetical sequence beginning with Zone A. Zones with the same letter designation may be repaired at the same time. Hydro demolition shall not move forward until the repairs in all special repair zones are completed and properly cured.

13.4 Any deck repair in areas not designated as a special repair zone shall be completed after hydro demolition.

13.5 Removal and deck repair shall be completed in one special repair zone and concrete shall have attained a compressive strength of 3200 psi before work can be started in the next repair zone.

13.16 Total width of full depth repair shall not exceed 1/3 of the deck width at one time. For any area of deck repair that extends over a web and is more than 18 inches in length along the web, the concrete removal including removal with hydro demolition shall stop at the centerline of web and repair completed in this area. Prior to continuing work in this area, the concrete shall have attained a compressive strength of 3200 psi. No traffic shall be permitted over the web that is undergoing repair.

13.17 When the full depth repair extends over a diaphragm or web and the deteriorated concrete extends into the diaphragm or web, all deteriorated concrete shall be removed and replaced as full depth repair. Concrete in webs shall not be removed below the slab haunch of the girder without prior review and approval from the engineer.

13.20 Interior falsework installed by the contractor resting on the bottom slab shall be removed where entry access is available.

13.21 If any single repair area does not exceed 9 square feet in size and the total repair area within a special repair zone does not exceed 27 square feet, the special repair zone may be repaired at the same time as an adjacent zone.


13.22 Half-sole repair in the special repair zone, on either side of the intermediate bents, shall be to a depth that will not expose half the diameter of the longitudinal reinforcing bar. Full depth repair shall be made when removal of deteriorated concrete exposes half or more of the diameter of the longitudinal reinforcing bar.

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

DATE PREPARED		10/17/2023	
ROUTE		STATE	
DISTRICT		MO	
		SHEET NO.	
		6	
COUNTY			
JOB NO.			
CONTRACT ID.			
PROJECT NO.			
BRIDGE NO.			



Hydro Demolition Case 2A:

Zoned Conventional Deck Repair Before Hydro Demolition and Non-Zoned Conventional Deck Repair After Hydro Demolition

(Adding First Wearing Surface)

STANDARD DRAWING GUIDANCE (do not show on plans):

Use for the following concrete wearing surfaces:

- (B) 2 1/4" to 3" Low Slump
- (B) 3/4" to 3" Polyester Polymer

If optional concrete wearing surface is specified and low slump or polyester polymer is an option follow guidance on Sheet RHB03a.

Estimated Quantities			
Item			Total
Scarfification of Bridge Deck	216-10.00	sq. yard	X
Total Surface Hydro Demolition	216-10.01	sq. yard	X
Removal of Existing Deck Repair	216-15.03	sq. foot	X
Supplementary Wearing Surface Material	505-00.04	cu. yard	X
Low Slump Concrete Wearing Surface	505-10.00	sq. yard	X
Substructure Repair (Formed)	704-01.01	sq. foot	X
Substructure Repair (Unformed)	704-01.02	sq. foot	X
Superstructure Repair (Unformed)	704-01.03	sq. foot	X
Half-Sole Repair	704-01.04	sq. foot	X
Full Depth Repair	704-01.06	sq. foot	X
Slab Edge Repair (Bridges)	704-01.07	linear foot	X
Cleaning and Epoxy Coating	704-01.13	sq. foot	X

B3.8 \* Supplementary wearing surface material for monolithic deck repair will be paid for at the fixed unit price in accordance with Sec 109.

B3.9 (If required)

General Notes:

- A1.1 Design Specifications:  
2002 AASHTO LFD (17th Ed.) Standard Specifications  
Bridge Deck Rating =
- A1.2 Design Loading:  
HS20-44 Modified ( ) and Military 24,000 lb Tandem Axle ( )
- A1.3 Design Unit Stresses:  
Class (B-1) Concrete (Half-Sole and Full Depth Repair) f'c = 4,000 psi
- Miscellaneous:
- 11.0.1 Roadway surfacing adjacent to bridge ends shall match new bridge wearing surface (roadway item).
- 11.0.2 All concrete repairs shall be in accordance with Sec 704, unless otherwise noted.
- 11.1 Outline of existing work is indicated by light dashed lines. Heavy lines indicate new work.
- 11.2 Contractor shall verify all dimensions in field before ordering new material.
- 11.10 In order to maintain grade and a minimum thickness of wearing surface as shown on plans it may be necessary to use additional quantities of wearing surface at various locations throughout the structure. The cost of furnishing and installing the wearing surface will be considered completely covered in the contract unit price, including all additional labor, materials or equipment for variations in thickness of wearing surface.
- Traffic Handling:
- A3.8 Structure to be closed during construction. Traffic to be maintained on during construction. See roadway plans for traffic control and Sheet No. for staged construction details.

REPAIRS TO BRIDGE: ROUTE \*  
OVER \*  
ROUTE \* FROM \* TO \*  
ABOUT \* MILES \* OF \*  
BEGINNING STATION ± (Match Existing)

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. 1 of

DATE PREPARED  
10/17/2023

ROUTE STATE  
DISTRICT SHEET NO.  
7

COUNTY

JOB NO.

CONTRACT ID.

PROJECT NO.

BRIDGE NO.


DESCRIPTION

DATE


MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)







PART PLAN OF SLAB SHOWING SPECIAL REPAIR ZONES



DECK REPAIR INSIDE SPECIAL REPAIR ZONES (BEFORE HYDRO DEMOLITION)



DECK REPAIR OUTSIDE SPECIAL REPAIR ZONES (AFTER HYDRO DEMOLITION)



Monolithic deck repair shall be used when only half the diameter or less of the top bar is exposed.

Clearance around top bar and around bottom bar at the intersection of top bar shall be required when more than half the diameter of the top bar is exposed.

DECK REPAIR DETAILS

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

Deck Repair Notes:

- Order of Repair:
1. Scarify existing deck **D**.
  2. Power wash deck to identify sound and unsound existing deck repair.
  3. Inside special repair zones, complete the following repairs:
    - a. Removal of existing deck repair
    - b. Half-sole repair
    - c. Full depth repair
  4. Outside special repair zones, remove existing deck repair.
  5. Complete total surface hydro demolition, removing **E** minimum of sound concrete inside special repair zones and removing **E** minimum of sound concrete and all deteriorated concrete outside special repair zones.
  6. Sound deck and if needed complete incidental concrete removal.
  7. Outside special repair zones, complete the following repairs:
    - a. Half-sole repair
    - b. Full depth repair
  8. Place new wearing surface including additional material for areas of monolithic deck repair.

**Special Repair Zones:**

**13.2** Deck repair required in the areas designated as special repair zones shall be completed before hydro demolition in alphabetical sequence beginning with Zone A. Zones with the same letter designation may be repaired at the same time. Hydro demolition shall not move forward until the repairs in all special repair zones are completed and properly cured.

**13.4** Any deck repair in areas not designated as a special repair zone shall be completed after hydro demolition.

**13.5** Removal and deck repair shall be completed in one special repair zone and concrete shall have attained a compressive strength of 3200 psi before work can be started in the next special repair zone.

**13.16** Total width of full depth repair shall not exceed 1/3 of the deck width at one time. For any area of deck repair that extends over a web and is more than 18 inches in length along the web, the concrete removal including removal with hydro demolition shall stop at the centerline of web and repair completed in this area. Prior to continuing work in this area, the concrete shall have attained a compressive strength of 3200 psi. No traffic shall be permitted over the web that is undergoing repair.


**13.17** When the full depth repair extends over a diaphragm or web and the deteriorated concrete extends into the diaphragm or web, all deteriorated concrete shall be removed and replaced as full depth repair. Concrete in webs shall not be removed below the slab haunch of the girder without prior review and approval from the engineer.

**13.20** Interior falsework installed by the contractor resting on the bottom slab shall be removed where entry access is available.

**13.21** If any single repair area does not exceed 9 square feet in size and the total repair area within a special repair zone does not exceed 27 square feet, the special repair zone may be repaired at the same time as an adjacent zone.

**13.22** Half-sole repair in the special repair zone, on either side of the intermediate bents, shall be to a depth that will not expose half the diameter of the longitudinal reinforcing bar. Full depth repair shall be made when removal of deteriorated concrete exposes half or more of the diameter of the longitudinal reinforcing bar.

DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 8
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	



# Hydro Demolition Case 2B:

Zoned Conventional Deck Repair Before Hydro Demolition and Non-Zoned Conventional Deck Repair After Hydro Demolition (Replacing Existing Wearing Surface)

STANDARD DRAWING GUIDANCE (do not show on plans):

Use for the following concrete wearing surfaces:

- 2 1/4" to 3" Low Slump
- 3/4" to 3" Polyester Polymer

If optional concrete wearing surface is specified and low slump or polyester polymer is an option follow guidance on Sheet RHB03c.

Estimated Quantities			
Item			Total
Total Surface Hydro Demolition	216-10.01	sq. yard	X
Removal of Concrete Wearing Surface	216-15.02	sq. foot	X
Removal of Existing Deck Repair	216-15.03	sq. foot	X
* Supplementary Wearing Surface Material	505-00.04	cu. yard	X
Low Slump Concrete Wearing Surface	505-10.00	sq. yard	X
Substructure Repair (Formed)	704-01.01	sq. foot	X
Substructure Repair (Unformed)	704-01.02	sq. foot	X
Superstructure Repair (Unformed)	704-01.03	sq. foot	X
Half-Sole Repair	704-01.04	sq. foot	X
Full Depth Repair	704-01.06	sq. foot	X
Slab Edge Repair (Bridges)	704-01.07	linear foot	X
Cleaning and Epoxy Coating	704-01.13	sq. foot	X

B3.8 \* Supplementary wearing surface material for monolithic deck repair will be paid for at the fixed unit price in accordance with Sec 109.  
B3.9 (If required)

## General Notes:

- A1.1 Design Specifications:  
2002 AASHTO LFD (17th Ed.) Standard Specifications  
Bridge Deck Rating =
- A1.2 Design Loading: Year and Military 24,000 lb Tandem Axle ( ) Year
- A1.3 Design Unit Stresses:  
Class B- Concrete (Half-Sole and Full Depth Repair) f'c = 4,000 psi
- Miscellaneous:
- I1.0.1 Roadway surfacing adjacent to bridge ends shall match new bridge wearing surface (roadway item).
- I1.0.2 All concrete repairs shall be in accordance with Sec 704, unless otherwise noted.
- I1.1 Outline of existing work is indicated by light dashed lines. Heavy lines indicate new work.
- I1.2 Contractor shall verify all dimensions in field before ordering new material.
- I1.10 In order to maintain grade and a minimum thickness of wearing surface as shown on plans it may be necessary to use additional quantities of wearing surface at various locations throughout the structure. The cost of furnishing and installing the wearing surface will be considered completely covered in the contract unit price, including all additional labor, materials or equipment for variations in thickness of wearing surface.
- A3.8 Traffic Handling:  
Structure to be closed during construction. Traffic to be maintained on during construction. See roadway plans for traffic control and Sheet No. for staged construction details.

REPAIRS TO BRIDGE: ROUTE \*  
OVER \*  
ROUTE \* FROM \* TO \*  
ABOUT \* MILES \* OF \*  
BEGINNING STATION ± (Match Existing)

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. 1 of


DESCRIPTION

--	--	--	--	--	--

DATE


--	--	--	--	--	--

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION



105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)


Five spans shown, detail for two spans is on sheet RHB03f. Detail for three spans is on sheet RHB03b. Detail for four spans is on sheet RHB03d.




PART PLAN OF SLAB SHOWING SPECIAL REPAIR ZONES

Remove if repair is not required.


Replace with Note 13.3 for structures with single column bents.



MONOLITHIC AND HALF-SOLE REPAIR




FULL DEPTH REPAIR




FULL DEPTH REPAIR WITH HALF-SOLE REPAIR


DECK REPAIR INSIDE SPECIAL REPAIR ZONES (BEFORE HYDRO DEMOLITION)



MONOLITHIC AND HALF-SOLE REPAIR




FULL DEPTH REPAIR




FULL DEPTH REPAIR WITH HALF-SOLE REPAIR


DECK REPAIR OUTSIDE SPECIAL REPAIR ZONES (AFTER HYDRO DEMOLITION)



DETAIL A



DETAIL B



DETAIL C

Monolithic deck repair shall be used when only half the diameter or less of the top bar is exposed.

Clearance around top bar and around bottom bar at the intersection of top bar shall be required when more than half the diameter of the top bar is exposed.

DECK REPAIR DETAILS

Deck Repair Notes:

- Order of Repair:
1. Remove existing wearing surface plus  $\textcircled{D}$  " of existing deck.
  2. Power wash deck to identify sound and unsound existing deck repair.
  3. Inside special repair zones, complete the following repairs:
    - a. Removal of existing deck repair
    - b. Half-sole repair
    - c. Full depth repair
  4. Outside special repair zones, remove existing deck repair.
  5. Complete total surface hydro demolition, removing  $\textcircled{E}$  " minimum of sound concrete inside special repair zones and removing  $\textcircled{E}$  " minimum of sound concrete and all deteriorated concrete outside special repair zones.
  6. Sound deck and if needed complete incidental concrete removal.
  7. Outside special repair zones, complete the following repairs:
    - a. Half-sole repair
    - b. Full depth repair
  8. Place new wearing surface including additional material for areas of monolithic deck repair.

13.2 Deck repair required in the areas designated as special repair zones shall be completed before hydro demolition in alphabetical sequence beginning with Zone A. Zones with the same letter designation may be repaired at the same time. Hydro demolition shall not move forward until the repairs in all special repair zones are completed and properly cured.

13.4 Any deck repair in areas not designated as a special repair zone shall be completed after hydro demolition.

13.5 Removal and deck repair shall be completed in one special repair zone and concrete shall have attained a compressive strength of 3200 psi before work can be started in the next special repair zone.

13.16 Total width of full depth repair shall not exceed 1/3 of the deck width at one time. For any area of deck repair that extends over a web and is more than 18 inches in length along the web, the concrete removal including removal with hydro demolition shall stop at the centerline of web and repair completed in this area. Prior to continuing work in this area, the concrete shall have attained a compressive strength of 3200 psi. No traffic shall be permitted over the web that is undergoing repair.

13.17 When the full depth repair extends over a diaphragm or web and the deteriorated concrete extends into the diaphragm or web, all deteriorated concrete shall be removed and replaced as full depth repair. Concrete in webs shall not be removed below the slab haunch of the girder without prior review and approval from the engineer.

13.20 Interior falsework installed by the contractor resting on the bottom slab shall be removed where entry access is available.


13.21 If any single repair area does not exceed 9 square feet in size and the total repair area within a special repair zone does not exceed 27 square feet, the special repair zone may be repaired at the same time as an adjacent zone.

13.22 Half-sole repair in the special repair zone, on either side of the intermediate bents, shall be to a depth that will not expose half the diameter of the longitudinal reinforcing bar. Full depth repair shall be made when removal of deteriorated concrete exposes half or more of the diameter of the longitudinal reinforcing bar.

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION



105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

Detailed  
Checked





Note: This drawing is not to scale. Follow dimensions.

Sheet No. of





Four spans shown, details for two and three spans are on the standard drawing guidance sheet. Detail for five spans is on sheet RHB03L.



Clearance around top bar and around bottom bar at the intersection of top bar shall be required when more than half the diameter of the top bar is exposed.

- (1) D "scarification of existing deck I
- (2) 1" vertical side shall be established outside the deteriorated area.
- (3) B "minimum \_\_\_\_\_ wearing surface
- (4) Original thickness of top slab

## DECK REPAIR DETAILS

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

### Deck Repair Notes:

Order of Repair:

1. Scarify existing deck.
2. Sound deck to identify areas in need of repair.
3. Outside special repair zones, complete the following repairs:
  - a. Half-sole repair
  - b. Full depth repair
4. Inside special repair zones, complete the following repairs:
  - a. Half-sole repair
  - b. Full depth repair
5. Place new wearing surface.

Special Repair Zones:

- 13.1 Any deck repair in areas not designated as a special repair zone shall be completed prior to work in Zone A.
- 13.2 Deck repair required in the areas designated as special repair zones shall be completed in alphabetical sequence beginning with Zone A. Zones with the same letter designation may be repaired at the same time.
- 13.5 Removal and deck repair shall be completed in one special repair zone and concrete shall have attained a compressive strength of 3200 psi before work can be started in the next special repair zone.
- 13.16 Total width of full depth repair shall not exceed 1/3 of the deck width at one time. For any area of deck repair that extends over a web and is more than 18 inches in length along the web, the concrete removal shall stop at the centerline of web and repair completed in this area. Prior to continuing work in this area, the concrete shall have attained a compressive strength of 3200 psi. No traffic shall be permitted over the web that is undergoing repair.
- 13.17 When the full depth repair extends over a diaphragm or web and the deteriorated concrete extends into the diaphragm or web, all deteriorated concrete shall be removed and replaced as full depth repair. Concrete in webs shall not be removed below the slab haunch of the girder without prior review and approval from the engineer.
- 13.20 Interior falsework installed by the contractor resting on the bottom slab shall be removed where entry access is available.
- 13.21 If any single repair area does not exceed 9 square feet in size and the total repair area within a special repair zone does not exceed 27 square feet, the special repair zone may be repaired at the same time as an adjacent zone.
- 13.22 Half-sole repair in the special repair zone, on either side of the intermediate bents, shall be to a depth that will not expose half the diameter of the longitudinal reinforcing bar. Full depth repair shall be made when removal of deteriorated concrete exposes half or more of the diameter of the longitudinal reinforcing bar.

SDG:

For seal coat, asphalt, UBAWS, epoxy polymer, or MMA polymer slurry wearing surfaces:


- Delete Dimension/Note (1) and renumber others
- Delete top existing line
- Adjust top of the original depth dimension to bottom of new wearing surface
- Adjust wearing surface thickness for thin wearing surfaces

For application of concrete crack filler:

- Delete Dimension/Note (1) and (3) and renumber others
- Delete top existing line & the wearing surface
- Adjust top of the original depth dimension to the remaining top line.
- Replace "Wearing Surface" with "Concrete Crack Filler" and adjust leader note to point to the remaining top line

U.I.P. AND REHABILITATE EXISTING (X'-X'-X') CONTINUOUS CONCRETE BOX GIRDER SPANS (SKEW: X)

SEC/SUR	*	TWP	*	RGE	*
---------	---	-----	---	-----	---



# Conventional Deck Repair Only

## (Case B)

(Replacing Existing Wearing Surface)

Estimated Quantities				
Item				Total
Removal of Concrete Wearing Surface	216-15.02	sq. foot		X
Latex Modified Concrete Wearing Surface	505-20.00	sq. yard		X
Substructure Repair (Formed)	704-01.01	sq. foot		X
Substructure Repair (Unformed)	704-01.02	sq. foot		X
Superstructure Repair (Unformed)	704-01.03	sq. foot		X
Half-Sole Repair	704-01.04	sq. foot		X
Full Depth Repair	704-01.06	sq. foot		X
Slab Edge Repair (Bridges)	704-01.07	linear foot		X
Cleaning and Epoxy Coating	704-01.13	sq. foot		X

STANDARD DRAWING GUIDANCE (do not show on plans):

May be used for all wearing surfaces:

Scarification not required with the following wearing surfaces:

- Seal Coat
- Asphalt
- UBAWS
- Epoxy Polymer
- MMA Polymer Slurry

- ② 2 1/4" to 3" Low Slump Concrete  
1 3/4" to 3" Latex Modified Concrete  
2 1/4" to 3" Silica Fume Concrete  
1 3/4" to 3" Latex Modified Very Early Strength Concrete  
1 3/4" to 3" CSA Cement Very Early Strength Concrete  
3" to 4" Steel Fiber Reinforced Concrete  
1/4" Epoxy Polymer  
3/4" to 3" Polyester Polymer Concrete  
3/8" MMA Polymer Slurry  
4" to 5" Reinforced Concrete Slab  
3/8" Chip Seal Grade A1  
1" to 3" Optional Asphaltic Concrete  
1/2" to 3/4" Optional Ultrathin Bonded Asphalt

General Notes:

- A1.1 Design Specifications:  
2002 AASHTO LFD (17th Ed.) Standard Specifications  
Bridge Deck Rating =
- A1.2 Design Loading:  
HS20-44 Modified ( ) and Military 24,000 lb Tandem Axle ( )
- A1.3 Design Unit Stresses:  
Class B-1 Concrete (Half-Sole and Full Depth Repair)  $f'c = 4,000$  psi  
Miscellaneous:
- 11.0.1 Roadway surfacing adjacent to bridge ends shall match new bridge wearing surface (roadway item).
- 11.0.2 All concrete repairs shall be in accordance with Sec 704, unless otherwise noted.
- 11.1 Outline of existing work is indicated by light dashed lines. Heavy lines indicate new work.
- 11.2 Contractor shall verify all dimensions in field before ordering new material.
- 11.10 In order to maintain grade and a minimum thickness of wearing surface as shown on plans it may be necessary to use additional quantities of wearing surface at various locations throughout the structure. The cost of furnishing and installing the wearing surface will be considered completely covered in the contract unit price, including all additional labor, materials or equipment for variations in thickness of wearing surface.
- Traffic Handling:
- A3.8 Structure to be closed during construction. Traffic to be maintained on during construction. See roadway plans for traffic control and Sheet No. for staged construction details.

REPAIRS TO BRIDGE: ROUTE \*  
OVER \*

```

ROUTE * FROM * TO *
ABOUT * MILES * OF *
BEGINNING STATION _____ ± (Match Existing)

```

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. 1 of

DATE PREPARED	
10/17/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	13
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	


DESCRIPTION

DATE \_\_\_\_\_


MISSOURI HIGHWAYS AND TRANSPORTATION




Five spans shown, details for two and three spans are on the standard drawing guidance sheet. Detail for four spans is on sheet RHB03j.



PART PLAN OF SLAB SHOWING SPECIAL REPAIR ZONES




HALF-SOLE REPAIR



FULL DEPTH REPAIR

FULL DEPTH REPAIR WITH HALF-SOLE REPAIR

DECK REPAIR



DETAIL A

- (1) Removal of existing  $\text{C} \pm$  wearing surface plus  $\text{D}$  of existing deck
- (2) 1" vertical side shall be established outside the deteriorated area.
- (3)  $\text{B}$  minimum wearing surface
- (4) Original thickness of top slab minus previous scarification

Clearance around top bar and around bottom bar at the intersection of top bar shall be required when more than half the diameter of the top bar is exposed.

Remove notes for repairs not required.

Deck Repair Notes:

- Order of Repair:
1. Remove existing wearing surface plus  $\text{D}$  of existing deck
  2. Sound deck to identify areas in need of repair.
  3. Outside special repair zones, complete the following repairs:
    - a. Half-sole repair
    - b. Full depth repair
  4. Inside special repair zones, complete the following repairs:
    - a. Half-sole repair
    - b. Full depth repair
  5. Place new wearing surface.

Special Repair Zones:

- 13.1 Any deck repair in areas not designated as a special repair zone shall be completed prior to work in Zone A.
- 13.2 Deck repair required in the areas designated as special repair zones shall be completed in alphabetical sequence beginning with Zone A. Zones with the same letter designation may be repaired at the same time.
- 13.5 Removal and deck repair shall be completed in one special repair zone and concrete shall have attained a compressive strength of 3200 psi before work can be started in the next special repair zone.
- 13.16 Total width of full depth repair shall not exceed 1/3 of the deck width at one time. For any area of deck repair that extends over a web and is more than 18 inches in length along the web, the concrete removal shall stop at the centerline of web and repair completed in this area. Prior to continuing work in this area, the concrete shall have attained a compressive strength of 3200 psi. No traffic shall be permitted over the web that is undergoing repair.
- 13.17 When the full depth repair extends over a diaphragm or web and the deteriorated concrete extends into the diaphragm or web, all deteriorated concrete shall be removed and replaced as full depth repair. Concrete in webs shall not be removed below the slab haunch of the girder without prior review and approval from the engineer.
- 13.20 Interior falsework installed by the contractor resting on the bottom slab shall be removed where entry access is available.
- 13.21 If any single repair area does not exceed 9 square feet in size and the total repair area within a special repair zone does not exceed 27 square feet, the special repair zone may be repaired at the same time as an adjacent zone.
- 13.22 Half-sole repair in the special repair zone, on either side of the intermediate bents, shall be to a depth that will not expose half the diameter of the longitudinal reinforcing bar. Full depth repair shall be made when removal of deteriorated concrete exposes half or more of the diameter of the longitudinal reinforcing bar.

SDG:

For seal coat, asphalt, UBAWS, epoxy polymer or MMA polymer slurry wearing surfaces:

- Delete existing line inside wearing surface
- Adjust top of the original depth dimension to bottom of new wearing surface
- Adjust depth for thin wearing surfaces

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

DECK REPAIR DETAILS

DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 14
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)



STANDARD DRAWING GUIDANCE (SDG) (do not show on plans)

Select the appropriate 1st and 2nd sheet. Draw typical section as required and scale to fit within attached border replacing the provided example. Modify other details and notes as required (match orientation of actual reinforcement).

Transverse repair zoning over intermediate bents is required for these structures. Longitudinal repair zoning in spans is required only when hydro demolition is required and is based on anticipated quantity of deck repair if not overlaid, confidence of anticipated quantity of deck repair if overlaid, deck rating (e.g. 6 or better may not need zoning), See EPG 751.40 (If only transverse zoning is required, Zones shall be called "Special Repair Zones").

Wearing surface thickness can vary according to grade elevation requirements and minimum barrier curb height requirements. Maximum thickness should be limited to 3" (Ref. Organizational Results Research Report ORO6.004, May 2006). Limit excludes reinforced concrete slab wearing surfaces.

Will need to adjust wearing surface thickness when detailing a thin wearing surface (1" or less), but it is a preferred detailing practice to show a discernable thickness on the plans. No thickness is shown for crack filler application.

- (A) Show difference as plus/minus X"±, see Bridge Memo or SPM. e.g. Match existing grade plus 2¼"±

(B) Identify new wearing surface (See Bridge Memo or SPM). Specify minimum thickness in deck details. Typically 1/4" thicker outside special repair zones for Hydro Case 1 & 2.

(C) Identify existing wearing surface and thickness, see Bridge Memo or existing plans.

(D) See Bridge Memo or SPM, typically 1/2". Use 1" if more than 30% of existing deck needs repair. Verify there will be a minimum of 1/2" of concrete above the top bars after scarification.

(E) See Bridge Memo or SPM, typically 1/4" inside special repair zones to avoid deeper penetration into newly repaired areas and 1/2" outside special repair zones.

(F) See existing plans.

(G) Use appropriate reference (☒ Structure, ☒ Roadway, ☒ Median, etc.)

(H) Two types of overhang rehabilitation are shown. Cleaning and epoxy coating is preferred because of the relative short life of slab edge repair and unformed repair especially when over traffic. However in urban regions repairing the overhang may be preferred. Consult with SPM or SLE.

(I) Scarification prior to adding first wearing surface or removing a portion of the deck when removing an existing wearing surface is not required for seal coat, asphalt, UBAWS, epoxy polymer or MMA polymer slurry wearing surfaces.

(J) Monolithic deck repair should only be allowed where longitudinal zoning is not required.



(K) May be used for aesthetics when there will be an extensive patchwork of repairs visible to the public.

(L) If deterioration is within 4 inches of edge then slab edge repair may be used instead of unformed superstructure repair.
- Slab Edge Repair \*\*


Limits of Slab Edge Repair 4"

L

Detach all unused Drawing Models & Sheet Models before requesting PDFs for sign and seal.




PART PLAN OF SLAB SHOWING SPECIAL REPAIR ZONES



PART PLAN OF SLAB SHOWING SPECIAL REPAIR ZONES

Two spans and three spans shown. These details can be used on Sheets RHB03j and RHB03L for conventional deck repair only projects.



# Hydro Demolition Case 1A:

Zoned Conventional Deck Repair Before Hydro Demolition and  
Non-Zoned Monolithic Deck Repair After Hydro Demolition

(Adding First Wearing Surface)

STANDARD DRAWING GUIDANCE (do not show on plans):

Use for the following concrete wearing surfaces:

- 1 3/4" to 3" Latex Modified
- 2 1/4" to 3" Silica Fume
- 1 3/4" to 3" Latex Modified Very Early Strength
- 1 3/4" to 3" CSA Cement Very Early Strength
- 3" to 4" Steel Fiber Reinforced

If optional concrete wearing surface is specified and low slump or polyester polymer is an option:

1. Add the allowed options in parentheses to the typical section title below and also to the RHB04e sheet title.
2. Add to this sheet the typical section from Sheet RHB04e with "(Low Slump Concrete)" added to the title.
3. Add "(Low Slump Concrete)" to the RHB04f sheet title and revise the sheet number from two to three. Sheet RHB04e will not be used.

Estimated Quantities			
Item			Total
Scarification of Bridge Deck	216-10.00	sq. yard	X
Total Surface Hydro Demolition	216-10.01	sq. yard	X
Removal of Existing Deck Repair	216-15.03	sq. foot	X
Supplementary Wearing Surface Material	505-00.04	cu. yard	X
Latex Modified Concrete Wearing Surface	505-20.00	sq. yard	X
Substructure Repair (Formed)	704-01.01	sq. foot	X
Substructure Repair (Unformed)	704-01.02	sq. foot	X
Superstructure Repair (Unformed)	704-01.03	sq. foot	X
Half-Sole Repair	704-01.04	sq. foot	X
Full Depth Repair	704-01.06	sq. foot	X
Slab Edge Repair (Bridges)	704-01.07	linear foot	X
Cleaning and Epoxy Coating	704-01.13	sq. foot	X

B3.8 \* Supplementary wearing surface material for monolithic deck repair will be paid for at the fixed unit price in accordance with Sec 109.

B3.9 if required

## General Notes:

A1.1 Design Specifications:

2002 AASHTO LFD (17th Ed.) Standard Specifications  
Bridge Deck Rating =

A1.2 Design Loading:

HS20-44 Modified ( ) and Military 24,000 lb Tandem Axle ( )

A1.3 Design Unit Stresses:

Class B-1 Concrete (Half-Sole and Full Depth Repair) f'c = 4,000 psi

Miscellaneous:

11.0.1 Roadway surfacing adjacent to bridge ends shall match new bridge wearing surface (roadway item).

11.0.3 if required

11.0.2 All concrete repairs shall be in accordance with Sec 704, unless otherwise noted.

11.1 Outline of existing work is indicated by light dashed lines. Heavy lines indicate new work.

11.2 Contractor shall verify all dimensions in field before ordering new material.

11.10 In order to maintain grade and a minimum thickness of wearing surface as shown on plans it may be necessary to use additional quantities of wearing surface at various locations throughout the structure. The cost of furnishing and installing the wearing surface will be considered completely covered in the contract unit price, including all additional labor, materials or equipment for variations in thickness of wearing surface.

Traffic Handling:

A3.8 Structure to be closed during construction. Traffic to be maintained on during construction. See roadway plans for traffic control and Sheet No. for staged construction details.

REPAIRS TO BRIDGE: ROUTE \*  
OVER \*


ROUTE \* FROM \* TO \*  
ABOUT \* MILES \* OF \*  
BEGINNING STATION ± (Match Existing)

Detailed  
Checked


Note: This drawing is not to scale. Follow dimensions.

Sheet No. 1 of


DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 15
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
MDOT	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MDOT (1-888-275-6636)	





PART PLAN OF SLAB SHOWING SPECIAL REPAIR ZONES



DECK REPAIR INSIDE SPECIAL REPAIR ZONES (BEFORE HYDRO DEMOLITION)



DECK REPAIR OUTSIDE SPECIAL REPAIR ZONES (AFTER HYDRO DEMOLITION)



DECK REPAIR DETAILS

Deck Repair Notes:

- Order of Repair:
1. Scarify existing deck **D**.
  2. Power wash deck to identify sound and unsound existing deck repair.
  3. Inside special repair zones, complete the following repairs:
    - a. Removal of existing deck repair
    - b. Half-sole repair
    - c. Deck repair with void tube replacement
    - d. Full depth repair
  4. Outside special repair zones, remove existing deck repair.
  5. Complete total surface hydro demolition, removing **E** minimum of sound concrete inside special repair zones and removing **E** minimum of sound concrete and all deteriorated concrete outside special repair zones.
  6. Sound deck and if needed complete incidental concrete removal.
  7. Outside special repair zones, complete the following repairs:
    - a. Deck repair with void tube replacement
    - b. Full depth repair
  8. Place new wearing surface including additional material for areas of monolithic deck repair.

**Special Repair Zones:**

13.2 Deck repair required in the areas designated as special repair zones shall be completed before hydro demolition in alphabetical sequence beginning with Zone A. Zones with the same letter designation may be repaired at the same time. Hydro demolition shall not move forward until the repairs in all special repair zones are completed and properly cured.

13.4 Any deck repair in areas not designated as a special repair zone shall be completed after hydro demolition.

13.5 Removal and deck repair shall be completed in one special repair zone and concrete shall have attained a compressive strength of 3200 psi before work can be started in the next special repair zone.

13.6 If any single repair area does not exceed 4 square feet in size and the total repair area within a special repair zone does not exceed 12 square feet, the special repair zone may be repaired at the same time as an adjacent zone.

**Void Repair:**


13.10 Any damage sustained to the void tube as a result of the contractor's operations shall be patched or replaced as required by the engineer at the contractor's expense.

13.11 An exposed void in the deck shall be patched as approved by the engineer in a manner that shall maintain the void area completely free of concrete. Cost of patching an exposed void will be considered completely covered by the contract unit price for Half-Sole Repair inside special repair zones and Monolithic Deck Repair outside special repair zones.

13.12 When a deteriorated portion of the void tube is beyond the point of patching as determined by the engineer, the portion of the deteriorated void tube shall be replaced. The void area shall be maintained completely free of concrete. Cutting of the longitudinal reinforcing steel will not be permitted. The fiber tubes for producing the voids shall have an outside diameter with the wall thickness the same as the existing tubes and anchored at not more than the original spacing. Cost of replacing the void tube will be considered completely covered by the contract unit price for Deck Repair with Void Tube Replacement. Measurement will be horizontal projection of the area of exposed tube in plan.

Remove if repair is not required.

DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 16
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	



# Hydro Demolition Case 1B:

Zoned Conventional Deck Repair Before Hydro Demolition and Non-Zoned Monolithic Deck Repair After Hydro Demolition

(Replacing Existing Wearing Surface)

STANDARD DRAWING GUIDANCE (do not show on plans):

Use for the following concrete wearing surfaces:

- 1 3/4" to 3" Latex Modified
- 2 1/4" to 3" Silica Fume
- 1 3/4" to 3" Latex Modified Very Early Strength
- 1 3/4" to 3" CSA Cement Very Early Strength
- 3" to 4" Steel Fiber Reinforced

If optional concrete wearing surface is specified and low slump or polyester polymer is an option:

1. Add the allowed options in parentheses to the typical section title below and also to the RHB04h sheet title.
2. Add to this sheet the typical section from Sheet RHB04g with "(Low Slump Concrete)" added to the title.
3. Add "(Low Slump Concrete)" to the RHB04h sheet title and revise the sheet number from two to three. Sheet RHB04g will not be used.

Estimated Quantities			
Item			Total
Total Surface Hydro Demolition	216-10.01	sq. yard	X
Removal of Concrete Wearing Surface	216-15.02	sq. foot	X
Removal of Existing Deck Repair	216-15.03	sq. foot	X
* Supplementary Wearing Surface Material	505-00.04	cu. yard	X
Latex Modified Concrete Wearing Surface	505-20.00	sq. yard	X
Substructure Repair (Formed)	704-01.01	sq. foot	X
Substructure Repair (Unformed)	704-01.02	sq. foot	X
Superstructure Repair (Unformed)	704-01.03	sq. foot	X
Half-Sole Repair	704-01.04	sq. foot	X
Full Depth Repair	704-01.06	sq. foot	X
Slab Edge Repair (Bridges)	704-01.07	linear foot	X
Cleaning and Epoxy Coating	704-01.13	sq. foot	X

B3.8 \* Supplementary wearing surface material for monolithic deck repair will be paid for at the fixed unit price in accordance with Sec 109.

Note B3.9 if required.

## General Notes:

- A1.1 Design Specifications:  
2002 AASHTO LFD (17th Ed.) Standard Specifications  
Bridge Deck Rating =
- A1.2 Design Loading:  
HS20-44 Modified ( ) and Military 24,000 lb Tandem Axle ( )
- A1.3 Design Unit Stresses:  
Class B-1 Concrete (Half-Sole and Full Depth Repair) f'c = 4,000 psi
- Miscellaneous:
- 11.0.1 Roadway surfacing adjacent to bridge ends shall match new bridge wearing surface (roadway item).
- 11.0.2 All concrete repairs shall be in accordance with Sec 704, unless otherwise noted.
- 11.1 Outline of existing work is indicated by light dashed lines. Heavy lines indicate new work.
- 11.2 Contractor shall verify all dimensions in field before ordering new material.
- 11.10 In order to maintain grade and a minimum thickness of wearing surface as shown on plans it may be necessary to use additional quantities of wearing surface at various locations throughout the structure. The cost of furnishing and installing the wearing surface will be considered completely covered in the contract unit price, including all additional labor, materials or equipment for variations in thickness of wearing surface.
- Traffic Handling:
- A3.8 Structure to be closed during construction. Traffic to be maintained on during construction. See roadway plans for traffic control and Sheet No. for staged construction details.

REPAIRS TO BRIDGE: ROUTE \* OVER \*

ROUTE \* FROM \* TO \*  
ABOUT \* MILES \* OF \*  
BEGINNING STATION ± (Match Existing)

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. 1 of

DATE PREPARED  
10/17/2023

ROUTE  
DISTRICT

STATE  
MO

SHEET NO.  
17

COUNTY

JOB NO.

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

DESCRIPTION

DATE


MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

MDOT

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MDOT (1-888-275-6636)




Five spans shown, detail for two spans is on sheet RHB04b. Detail for three spans is on RHB04f. Detail for four spans is on RHB04h.




PART PLAN OF SLAB SHOWING SPECIAL REPAIR ZONES

Remove notes for repairs not required, possibly entire steps.


Replace with Note 13.3 for structures with single column bents.




MONOLITHIC AND HALF-SOLE REPAIR




DECK REPAIR WITH VOID TUBE REPLACEMENT  
A = Half-Sole Repair  
B = Deck Repair with Void Tube Replacement




FULL DEPTH REPAIR



MONOLITHIC DECK REPAIR





DECK REPAIR WITH VOID TUBE REPLACEMENT  
A = Half-Sole Repair  
B = Deck Repair with Void Tube Replacement




FULL DEPTH REPAIR

DECK REPAIR OUTSIDE SPECIAL REPAIR ZONES (AFTER HYDRO DEMOLITION)



DETAIL A


- (1) Removal of existing **C** wearing surface plus **D** of existing deck
- (2) 1" vertical side shall be established outside the deteriorated area.
- (3) Total surface hydro demolition of sound concrete, measured to mortar line:
- E** " minimum inside special repair zones
  - E** " minimum outside special repair zones
- (4) **B** concrete wearing surface:
- E** " minimum inside special repair zones
  - E** " minimum outside special repair zones
- (5) Original depth minus previous scarification
- (6) Restore existing weep hole, if encountered.



DETAIL B

Monolithic deck repair shall be used when only half the diameter or less of the top bar is exposed.

Clearance around top bar and around bottom bar at the intersection of top bar shall be required when more than half the diameter of the top bar is exposed.



FIBER VOID TUBE REPLACEMENT

Fiber tubes for producing voids shall have an approximate outside diameter of x inches and a wall thickness of 1/4 inch and shall be anchored to joists carrying the floor form at not more than 4-foot centers.

One 3/4"Ø weep hole shall be provided at 2 inches from each end of each new void.

Deck Repair Notes:

- Order of Repair:
1. Remove existing wearing surface plus **D** of existing deck.
  2. Power wash deck to identify sound and unsound existing deck repair.
  3. Inside special repair zones, complete the following repairs:
    - a. Removal of existing deck repair
    - b. Half-sole repair
    - c. Deck repair with void tube replacement
    - d. Full depth repair
  4. Outside special repair zones, remove existing deck repair.
  5. Complete total surface hydro demolition, removing **E** minimum of sound concrete inside special repair zones and removing **E** minimum of sound concrete and all deteriorated concrete outside special repair zones.
  6. Sound deck and if needed complete incidental concrete removal.
  7. Outside special repair zones, complete the following repairs:
    - a. Deck repair with void tube replacement
    - b. Full depth repair
  8. Place new wearing surface including additional material for areas of monolithic deck repair.

Special Repair Zones:

- 13.2 Deck repair required in the areas designated as special repair zones shall be completed before hydro demolition in alphabetical sequence beginning with Zone A. Zones with the same letter designation may be repaired at the same time. Hydro demolition shall not move forward until the repairs in all special repair zones are completed and properly cured.
- 13.4 Any deck repair in areas not designated as a special repair zone shall be completed after hydro demolition.
- 13.5 Removal and deck repair shall be completed in one special repair zone and concrete shall have attained a compressive strength of 3200 psi before work can be started in the next special repair zone.
- 13.6 If any single repair area does not exceed 4 square feet in size and the total repair area within a special repair zone does not exceed 12 square feet, the special repair zone may be repaired at the same time as an adjacent zone.
- Void Repair:
- 13.10 Any damage sustained to the void tube as a result of the contractor's operations shall be patched or replaced as required by the engineer at the contractor's expense.
- 13.11 An exposed void in the deck shall be patched as approved by the engineer in a manner that shall maintain the void area completely free of concrete. Cost of patching an exposed void will be considered completely covered by the contract unit price for Half-Sole Repair inside special repair zones and Monolithic Deck Repair outside special repair zones.
- 13.12 When a deteriorated portion of the void tube is beyond the point of patching as determined by the engineer, the portion of the deteriorated void tube shall be replaced. The void area shall be maintained completely free of concrete. Cutting of the longitudinal reinforcing steel will not be permitted. The fiber tubes for producing the voids shall have an outside diameter with the wall thickness the same as the existing tubes and anchored at not more than the original spacing. Cost of replacing the void tube will be considered completely covered by the contract unit price for Deck Repair with Void Tube Replacement. Measurement will be horizontal projection of the area of exposed tube in plan.


Remove if repair is not required.

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 18
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	



# Hydro Demolition Case 2A:

Zoned Conventional Deck Repair Before Hydro Demolition and  
Non-Zoned Conventional Deck Repair After Hydro Demolition  
(Adding First Wearing Surface)

## STANDARD DRAWING GUIDANCE (do not show on plans):

(B) May be used with the following concrete wearing surfaces:  
2 1/4" to 3" Low Slump  
3/4" to 3" Polyester Polymer

If optional concrete wearing surface is specified and low slump or polyester polymer is an option follow guidance on Sheet RHB04a.

Estimated Quantities			
Item			Total
Scarification of Bridge Deck	216-10.00	sq. yard	X
Total Surface Hydro Demolition	216-10.01	sq. yard	X
Removal of Existing Deck Repair	216-15.03	sq. foot	X
Supplementary Wearing Surface Material	505-00.04	cu. yard	X
Latex Modified Concrete Wearing Surface	505-20.00	sq. yard	X
Substructure Repair (Formed)	704-01.01	sq. foot	X
Substructure Repair (Unformed)	704-01.02	sq. foot	X
Superstructure Repair (Unformed)	704-01.03	sq. foot	X
Half-Sole Repair	704-01.04	sq. foot	X
Full Depth Repair	704-01.06	sq. foot	X
Slab Edge Repair (Bridges)	704-01.07	linear foot	X
Deck Repair with Void Tube Replacement	704-01.12	sq. foot	X
Cleaning and Epoxy Coating	704-01.13	sq. foot	X

- B3.8 \* Supplementary wearing surface material for monolithic deck repair will be paid for at the fixed unit price in accordance with Sec 109.
- B3.9 if required →
- General Notes:**
- A1.1 Design Specifications:  
2002 AASHTO LFD (17th Ed.) Standard Specifications  
Bridge Deck Rating =
- A1.2 Design Loading:  
HS20-44 Modified ( ) and Military 24,000 lb Tandem Axle ( )
- A1.3 Design Unit Stresses:  
Class B-1 Concrete (Half-Sole and Full Depth Repair and Deck Repair with Void Tube Replacement) f'c = 4,000 psi
- Miscellaneous:
- 11.0.1 Roadway surfacing adjacent to bridge ends shall match new bridge wearing surface (roadway item).
- 11.0.2 All concrete repairs shall be in accordance with Sec 704, unless otherwise noted.
- 11.1 Outline of existing work is indicated by light dashed lines. Heavy lines indicate new work.
- 11.2 Contractor shall verify all dimensions in field before ordering new material.
- 11.10 In order to maintain grade and a minimum thickness of wearing surface as shown on plans it may be necessary to use additional quantities of wearing surface at various locations throughout the structure. The cost of furnishing and installing the wearing surface will be considered completely covered in the contract unit price, including all additional labor, materials or equipment for variations in thickness of wearing surface.
- Traffic Handling:
- A3.8 Structure to be closed during construction. Traffic to be maintained on during construction. See roadway plans for traffic control and Sheet No. for staged construction details.

REPAIRS TO BRIDGE: ROUTE \*  
OVER \*  
ROUTE \* FROM \* TO \*  
ABOUT \* MILES \* OF \*  
BEGINNING STATION ± (Match Existing)

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. 1 of

DATE PREPARED  
10/17/2023

ROUTE  
STATE  
DISTRICT  
SHEET NO.  
19

COUNTY

JOB NO.

CONTRACT ID.

PROJECT NO.


BRIDGE NO.

DESCRIPTION


DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)




PART PLAN OF SLAB SHOWING SPECIAL REPAIR ZONES



DECK REPAIR INSIDE SPECIAL REPAIR ZONES (BEFORE HYDRO DEMOLITION)

DECK REPAIR OUTSIDE SPECIAL REPAIR ZONES (AFTER HYDRO DEMOLITION)



DETAIL B  
Monolithic deck repair shall be used when only half the diameter or less of the top bar is exposed.

Clearance around top bar and around bottom bar at the intersection of top bar shall be required when more than half the diameter of the top bar is exposed.

Note: This drawing is not to scale. Follow dimensions.

DECK REPAIR DETAILS

Sheet No. of

Deck Repair Notes:

- Order of Repair:
1. Scarify existing deck **(D)**.
  2. Power wash deck to identify sound and unsound existing deck repair.
  3. Inside special repair zones, complete the following repairs:
    - a. Removal of existing deck repair
    - b. Half-sole repair
    - c. Deck repair with void tube replacement
    - d. Full depth repair
  4. Outside special repair zones, remove existing deck repair.
  5. Complete total surface hydro demolition, removing **(E)** minimum of sound concrete inside special repair zones and removing **(A)** minimum of sound concrete and all deteriorated concrete outside special repair zones.
  6. Sound deck and if needed complete incidental concrete removal.
  7. Outside special repair zones, complete the following repairs:
    - a. Half-sole repair
    - b. Deck repair with void tube replacement
    - c. Full depth repair
  8. Place new wearing surface including additional material for areas of monolithic deck repair.

Special Repair Zones:

13.2 Deck repair required in the areas designated as special repair zones shall be completed before hydro demolition in alphabetical sequence beginning with Zone A. Zones with the same letter designation may be repaired at the same time. Hydro demolition shall not move forward until the repairs in all special repair zones are completed and properly cured.

13.4 Any deck repair in areas not designated as a special repair zone shall be completed after hydro demolition.

13.5 Removal and deck repair shall be completed in one special repair zone and concrete shall have attained a compressive strength of 3200 psi before work can be started in the next special repair zone.

13.6 If any single repair area does not exceed 4 square feet in size and the total repair area within a special repair zone does not exceed 12 square feet, the special repair zone may be repaired at the same time as an adjacent zone.

Void Repair:

13.10 Any damage sustained to the void tube as a result of the contractor's operations shall be patched or replaced as required by the engineer at the contractor's expense.

13.11 An exposed void in the deck shall be patched as approved by the engineer in a manner that shall maintain the void area completely free of concrete. Cost of patching an exposed void will be considered completely covered by the contract unit price for Half-Sole Repair.

13.12 When a deteriorated portion of the void tube is beyond the point of patching as determined by the engineer, the portion of the deteriorated void tube shall be replaced. The void area shall be maintained completely free of concrete. Cutting of the longitudinal reinforcing steel will not be permitted. The fiber tubes for producing the voids shall have an outside diameter with the wall thickness the same as the existing tubes and anchored at not more than the original spacing. Cost of replacing the void tube will be considered completely covered by the contract unit price for Deck Repair with Void Tube Replacement. Measurement will be horizontal projection of the area of exposed tube in plan.

Remove if repair is not required.


Detailed  
Checked

DATE PREPARED	10/17/2023		
	ROUTE	STATE	MO
DISTRICT	SHEET NO. 20		
COUNTY			
JOB NO.			
CONTRACT ID.			
PROJECT NO.			
BRIDGE NO.			
DESCRIPTION			
DATE			

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)





# Hydro Demolition Case 2B:

Zoned Conventional Deck Repair Before Hydro Demolition and  
Non-Zoned Conventional Deck Repair After Hydro Demolition  
(Replacing Existing Wearing Surface)

Estimated Quantities			
Item			Total
Total Surface Hydro Demolition	216-10.01	sq. yard	X
Removal of Concrete Wearing Surface	216-15.02	sq. foot	X
Removal of Existing Deck Repair	216-15.03	sq. foot	X
Supplementary Wearing Surface Material	505-00.04	cu. yard	X
Latex Modified Concrete Wearing Surface	505-20.00	sq. yard	X
Substructure Repair (Formed)	704-01.01	sq. foot	X
Substructure Repair (Unformed)	704-01.02	sq. foot	X
Superstructure Repair (Unformed)	704-01.03	sq. foot	X
Half-Sole Repair	704-01.04	sq. foot	X
Full Depth Repair	704-01.06	sq. foot	X
Slab Edge Repair (Bridges)	704-01.07	linear foot	X
Deck Repair with Void Tube Replacement	704-01.12	sq. foot	X
Cleaning and Epoxy Coating	704-01.13	sq. foot	X

- B3.8 \* Supplementary wearing surface material for monolithic deck repair will be paid for at the fixed unit price in accordance with Sec 109.
- B3.9 if required →
- General Notes:**
- A1.1 Design Specifications:  
2002 AASHTO LFD (17th Ed.) Standard Specifications  
Bridge Deck Rating =
- A1.2 Design Loading:  
HS20-44 Modified ( ) and Military 24,000 lb Tandem Axle ( )
- A1.3 Design Unit Stresses:  
Class B-1 Concrete (Half-Sole and Full Depth Repair and Deck Repair with Void Tube Replacement) f'c = 4,000 psi
- Miscellaneous:
- 11.0.1 Roadway surfacing adjacent to bridge ends shall match new bridge wearing surface (roadway item).
- 11.0.2 All concrete repairs shall be in accordance with Sec 704, unless otherwise noted.
- 11.1 Outline of existing work is indicated by light dashed lines. Heavy lines indicate new work.
- 11.2 Contractor shall verify all dimensions in field before ordering new material.
- 11.10 In order to maintain grade and a minimum thickness of wearing surface as shown on plans it may be necessary to use additional quantities of wearing surface at various locations throughout the structure. The cost of furnishing and installing the wearing surface will be considered completely covered in the contract unit price, including all additional labor, materials or equipment for variations in thickness of wearing surface.
- Traffic Handling:
- A3.8 Structure to be closed during construction. Traffic to be maintained on during construction. See roadway plans for traffic control and Sheet No. for staged construction details.

- STANDARD DRAWING GUIDANCE (do not show on plans):
- (B) May be used with the following concrete wearing surfaces:  
2 1/4" to 3" Low Slump  
3/4" to 3" Polyester Polymer
- If optional concrete wearing surface is specified and low slump or polyester polymer is an option follow guidance on Sheet RHB04c.

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. 1 of

REPAIRS TO BRIDGE: ROUTE \*  
OVER \*  
ROUTE \* FROM \* TO \*  
ABOUT \* MILES \* OF \*  
BEGINNING STATION ± (Match Existing)

DATE PREPARED  
10/17/2023

ROUTE STATE  
DISTRICT SHEET NO.  
21

COUNTY

JOB NO.

CONTRACT ID.

PROJECT NO.

BRIDGE NO.


DESCRIPTION

DATE




MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

MDOT




105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MDOT (1-888-275-6636)




PART PLAN OF SLAB SHOWING SPECIAL REPAIR ZONES





DECK REPAIR INSIDE SPECIAL REPAIR ZONES (BEFORE HYDRO DEMOLITION)



DECK REPAIR OUTSIDE SPECIAL REPAIR ZONES (AFTER HYDRO DEMOLITION)



- (1) Removal of existing  $\frac{1}{4}$ " of existing deck wearing surface plus  $\frac{1}{4}$ " of existing deck
- (2) 1" vertical side shall be established outside the deteriorated area.
- (3) Total surface hydro demolition of sound concrete, measured to mortar line:
- $\frac{1}{4}$ " minimum inside special repair zones
- $\frac{1}{4}$ " minimum outside special repair zones
- (4)  $\frac{1}{4}$ " concrete wearing surface:
- $\frac{1}{4}$ " minimum inside special repair zones
- $\frac{1}{4}$ " minimum outside special repair zones
- (5) Original depth minus previous scarification
- (6) Restore existing weep hole, if encountered.



DECK REPAIR DETAILS

Deck Repair Notes:

- Order of Repair:
1. Remove existing wearing surface plus  $\frac{1}{4}$ " of existing deck.
  2. Power wash deck to identify sound and unsound existing deck repair.
  3. Inside special repair zones, complete the following repairs:
    - a. Removal of existing deck repair
    - b. Half-sole repair
    - c. Deck repair with void tube replacement
    - d. Full depth repair
  4. Outside special repair zones, remove existing deck repair.
  5. Complete total surface hydro demolition, removing  $\frac{1}{4}$ " minimum of sound concrete inside special repair zones and removing  $\frac{1}{4}$ " minimum of sound concrete and all deteriorated concrete outside special repair zones.
  6. Sound deck and if needed complete incidental concrete removal.
  7. Outside special repair zones, complete the following repairs:
    - a. Half-sole repair
    - b. Deck repair with void tube replacement
    - c. Full depth repair
  8. Place new wearing surface including additional material for areas of monolithic deck repair.

13.2 Deck repair required in the areas designated as special repair zones shall be completed before hydro demolition in alphabetical sequence beginning with Zone A. Zones with the same letter designation may be repaired at the same time. Hydro demolition shall not move forward until the repairs in all special repair zones are completed and properly cured.

13.4 Any deck repair in areas not designated as a special repair zone shall be completed after hydro demolition.

13.5 Removal and deck repair shall be completed in one special repair zone and concrete shall have attained a compressive strength of 3200 psi before work can be started in the next special repair zone.

13.6 If any single repair area does not exceed 4 square feet in size and the total repair area within a special repair zone does not exceed 12 square feet, the special repair zone may be repaired at the same time as an adjacent zone.

Void Repair:

13.10 Any damage sustained to the void tube as a result of the contractor's operations shall be patched or replaced as required by the engineer at the contractor's expense.

13.11 An exposed void in the deck shall be patched as approved by the engineer in a manner that shall maintain the void area completely free of concrete. Cost of patching an exposed void will be considered completely covered by the contract unit price for Half-Sole Repair.

13.12 When a deteriorated portion of the void tube is beyond the point of patching as determined by the engineer, the portion of the deteriorated void tube shall be replaced. The void area shall be maintained completely free of concrete. Cutting of the longitudinal reinforcing steel will not be permitted. The fiber tubes for producing the voids shall have an outside diameter with the wall thickness the same as the existing tubes and anchored at not more than the original spacing. Cost of replacing the void tube will be considered completely covered by the contract unit price for Deck Repair with Void Tube Replacement. Measurement will be horizontal projection of the area of exposed tube in plan.


Remove if repair is not required.

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

DATE PREPARED		10/17/2023
ROUTE	STATE	MO
DISTRICT	SHEET NO.	22
COUNTY		
JOB NO.		
CONTRACT ID.		
PROJECT NO.		
BRIDGE NO.		
DESCRIPTION		
DATE		
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION		
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)		



# Conventional Deck Repair Only (Case A)

(Adding First Wearing Surface or  
Applying Concrete Crack Filler)

STANDARD DRAWING GUIDANCE (do not show on plans):  
May be used for all wearing surfaces and when applying concrete crack filler:  
Scarification not required when applying concrete crack filler or with the following wearing surfaces:  
Seal Coat  
Asphalt  
UBAWS  
Epoxy Polymer  
MMA Polymer Slurry

- (B) 2 1/4" to 3" Low Slump Concrete
- 1 3/4" to 3" Latex Modified Concrete
- 2 1/4" to 3" Silica Fume Concrete
- 1 3/4" to 3" Latex Modified Very Early Strength Concrete
- 1 3/4" to 3" CSA Cement Very Early Strength Concrete
- 3" to 4" Steel Fiber Reinforced Concrete
- 1/4" Epoxy Polymer
- 3/4" to 3" Polyester Polymer Concrete
- 3/8" MMA Polymer Slurry
- 4" to 5" Reinforced Concrete Slab
- 3/8" Chip Seal Grade A1
- 1" to 3" Optional Asphaltic Concrete
- 1/2" to 3/4" Optional Ultrathin Bonded Asphalt

Replace as  
required

Estimated Quantities			
Item			Total
Scarification of Bridge Deck	216-10.00	sq. yard	X
Latex Modified Concrete Wearing Surface	505-20.00	sq. yard	X
Substructure Repair (Formed)	704-01.01	sq. foot	X
Substructure Repair (Unformed)	704-01.02	sq. foot	X
Superstructure Repair (Unformed)	704-01.03	sq. foot	X
Half-Sole Repair	704-01.04	sq. foot	X
Full Depth Repair	704-01.06	sq. foot	X
Slab Edge Repair (Bridges)	704-01.07	linear foot	X
Deck Repair with Void Tube Replacement	704-01.12	sq. foot	X
Cleaning and Epoxy Coating	704-01.13	sq. foot	X

## General Notes:

- A1.1 Design Specifications:  
2002 AASHTO LFD (17th Ed.) Standard Specifications  
Bridge Deck Rating =
- A1.2 Design Loading:  
HS20-44 Modified ( ) and Military 24,000 lb Tandem Axle ( )
- A1.3 Design Unit Stresses:  
Class B-1 Concrete (Half-Sole and Full Depth Repair and Deck Repair with Void Tube Replacement) f'c = 4,000 psi
- Miscellaneous:  
11.0.1 Roadway surfacing adjacent to bridge ends shall match new bridge wearing surface (roadway item).
- 11.0.2 All concrete repairs shall be in accordance with Sec 704, unless otherwise noted.
- 11.1 Outline of existing work is indicated by light dashed lines. Heavy lines indicate new work.
- 11.2 Contractor shall verify all dimensions in field before ordering new material.
- 11.10 In order to maintain grade and a minimum thickness of wearing surface as shown on plans it may be necessary to use additional quantities of wearing surface at various locations throughout the structure. The cost of furnishing and installing the wearing surface will be considered completely covered in the contract unit price, including all additional labor, materials or equipment for variations in thickness of wearing surface.
- Traffic Handling:  
A3.8 Structure to be closed during construction. Traffic to be maintained on during construction. See roadway plans for traffic control and Sheet No. for staged construction details.

REPAIRS TO BRIDGE: ROUTE \*  
OVER \*  
ROUTE \* FROM \* TO \*  
ABOUT \* MILES \* OF \*  
BEGINNING STATION ± (Match Existing)








Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. 1 of

DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 23
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	

Three spans shown, details for two spans and five spans are on the standard drawing guidance sheet. Detail for four spans is on RHB04L.



Clearance around top bar and around bottom bar at the intersection of top bar shall be required when more than half the diameter of the top bar is exposed.

- (1) D "scarification of existing deck ①
- (2) 1" vertical side shall be established outside the deteriorated area.
- (3) B " minimum \_\_\_\_\_ wearing surface
- (4) Original depth
- (5) Restore existing weep hole, if encountered.

### Deck Repair Notes:

Order of Repair:

1. Scarify existing deck
2. Sound deck to identify areas in need of repair.
3. Outside special repair zones, complete the following repairs:
  - a. Half-sole repair
  - b. Deck repair with void tube replacement
  - c. Full depth repair
4. Inside special repair zones, complete the following repairs:
  - a. Half-sole repair
  - b. Deck repair with void tube replacement
  - c. Full depth repair
5. Place new wearing surface.

Special Repair Zones:

- 13.1 Any deck repair in areas not designated as a special repair zone shall be completed prior to work in Zone A.
- 13.2 Deck repair required in the areas designated as special repair zones shall be completed in alphabetical sequence beginning with Zone A. Zones with the same letter designation may be repaired at the same time.

13.5 Removal and deck repair shall be completed in one special repair zone and concrete shall have attained a compressive strength of 3200 psi before work can be started in the next special repair zone.

- 13.6 If any single repair area does not exceed 4 square feet in size and the total repair area within a special repair zone does not exceed 12 square feet, the special repair zone may be repaired at the same time as an adjacent zone.

Void Repair:

- 13.10** Any damage sustained to the void tube as a result of the contractor's operations shall be patched or replaced as required by the engineer at the contractor's expense.
- 13.11** An exposed void in the deck shall be patched as approved by the engineer in a manner that shall maintain the void area completely free of concrete. Cost of patching an exposed void will be considered completely covered by the contract unit price for Half-Sole Repair.

- 13.12 When a deteriorated portion of the void tube is beyond the point of patching as determined by the engineer, the portion of the deteriorated void tube shall be replaced. The void area shall be maintained completely free of corrosion. Cutting of the void tube and reinforcing steel will not be permitted. The fiber tubes for producing the voids shall have an outside diameter with the wall thickness the same as the existing tubes and anchored at not more than the original spacing. Cost of replacing the void tube will be considered completely covered by the contract unit price for Deck Repair with Void Tube Replacement. Measurement will be horizontal projection of the area of exposed tube in plan.

SDG:

For seal coat, asphalt, UBAWS, epoxy polymer, or MMA polymer slurry wearing surfaces:

- Delete Dimension/Note (1) and renumber others
- Delete top existing line
- Adjust top of the original depth dimension to bottom of new wearing surface
- Adjust wearing surface thickness for thin wearing surfaces

For application of concrete crack filler:


- Delete Dimension/Note (1) and (3) and renumber others
- Delete top existing line & the wearing surface
- Adjust top of the original depth dimension to the remaining top line.
- Replace "Wearing Surface" with "Concrete Crack Filler" and adjust leader note to point to the remaining top line

DATE PREPARED	
10/17/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	24

JOB NO.
CONTRACT ID.
PROJECT NO.
BRIDGE NO.

[illegible]MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION





# Conventional Deck Repair Only (Case B)

(Replacing Existing Wearing Surface)

STANDARD DRAWING GUIDANCE (do not show on plans):

May be used for all wearing surfaces:

Scarification not required with the following wearing surfaces:

- Seal Coat
- Asphalt
- UBAWS
- Epoxy Polymer
- MMA Polymer Slurry

- 2 1/4" to 3" Low Slump Concrete
- 1 3/4" to 3" Latex Modified Concrete
- 2 1/4" to 3" Silica Fume Concrete
- 1 3/4" to 3" Latex Modified Very Early Strength Concrete
- 1 3/4" to 3" CSA Cement Very Early Strength Concrete
- 3" to 4" Steel Fiber Reinforced Concrete
- 1/4" Epoxy Polymer
- 3/4" to 3" Polyester Polymer Concrete
- 3/8" MMA Polymer Slurry
- 4" to 5" Reinforced Concrete Slab
- 3/8" Chip Seal Grade A1
- 1" to 3" Optional Asphaltic Concrete
- 1/2" to 3/4" Optional Ultrathin Bonded Asphalt

Replace as required

Estimated Quantities			
Item			Total
Removal of Concrete Wearing Surface	216-15.02	sq. foot	X
Latex Modified Concrete Wearing Surface	505-20.00	sq. yard	X
Substructure Repair (Formed)	704-01.01	sq. foot	X
Substructure Repair (Unformed)	704-01.02	sq. foot	X
Superstructure Repair (Unformed)	704-01.03	sq. foot	X
Half-Sole Repair	704-01.04	sq. foot	X
Full Depth Repair	704-01.06	sq. foot	X
Slab Edge Repair (Bridges)	704-01.07	linear foot	X
Deck Repair with Void Tube Replacement	704-01.12	sq. foot	X
Cleaning and Epoxy Coating	704-01.13	sq. foot	X

## General Notes:

- A1.1 Design Specifications:**  
2002 AASHTO LFD (17th Ed.) Standard Specifications  
Bridge Deck Rating =
- A1.2 Design Loading:**  
HS20-44 Modified ( ) and Military 24,000 lb Tandem Axle ( )
- A1.3 Design Unit Stresses:**  
Class B-1 Concrete (Half-Sole and Full Depth Repair and Deck Repair with Void Tube Replacement) f'c = 4,000 psi
- Miscellaneous:**
  - 11.0.1** Roadway surfacing adjacent to bridge ends shall match new bridge wearing surface (roadway item).
  - 11.0.2** All concrete repairs shall be in accordance with Sec 704, unless otherwise noted.
  - 11.1** Outline of existing work is indicated by light dashed lines. Heavy lines indicate new work.
  - 11.2** Contractor shall verify all dimensions in field before ordering new material.
  - 11.10** In order to maintain grade and a minimum thickness of wearing surface as shown on plans it may be necessary to use additional quantities of wearing surface at various locations throughout the structure. The cost of furnishing and installing the wearing surface will be considered completely covered in the contract unit price, including all additional labor, materials or equipment for variations in thickness of wearing surface.
- Traffic Handling:**
  - A3.8** Structure to be closed during construction. Traffic to be maintained on during construction. See roadway plans for traffic control and Sheet No. for staged construction details.

REPAIRS TO BRIDGE: ROUTE \*  
OVER \*  
ROUTE \* FROM \* TO \*  
ABOUT \* MILES \* OF \*  
BEGINNING STATION ± (Match Existing)


Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.


Sheet No. 1 of

DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 25
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	


Four spans shown, details for two spans and five spans are on the standard drawing guidance sheet. Detail for three spans is on RHB04j.



PART PLAN OF SLAB SHOWING SPECIAL REPAIR ZONES





HALF-SOLE REPAIR




DECK REPAIR


- (1) Removal of existing  $\text{C} \pm$  wearing surface plus  $\text{D}$  of existing deck  $\text{I}$
- (2) 1" vertical side shall be established outside the deteriorated area.
- (3)  $\text{B}$  " minimum wearing surface
- (4) Original depth minus previous scarification
- (5) Restore existing weep hole, if encountered.



DETAIL A



FULL DEPTH REPAIR



FIBER VOID TUBE REPLACEMENT

Fiber tubes for producing voids shall have an approximate outside diameter of inches and a wall thickness of 1/4 inch and shall be anchored to joists carrying the floor form at not more than 4-foot centers.

One 3/4"Ø weep hole shall be provided at 2 inches from each end of each new void.

Deck Repair Notes:

- Order of Repair:
1. Remove existing wearing surface plus  $\text{D}$  of existing deck  $\text{I}$
  2. Sound deck to identify areas in need of repair.
  3. Outside special repair zones, complete the following repairs:
    - a. Half-sole repair
    - b. Deck repair with void tube replacement
    - c. Full depth repair
  4. Inside special repair zones, complete the following repairs:
    - a. Half-sole repair
    - b. Deck repair with void tube replacement
    - c. Full depth repair
  5. Place new wearing surface.

Special Repair Zones:

- 13.1 Any deck repair in areas not designated as a special repair zone shall be completed prior to work in Zone A.
- 13.2 Deck repair required in the areas designated as special repair zones shall be completed in alphabetical sequence beginning with Zone A. Zones with the same letter designation may be repaired at the same time.

13.5 Removal and deck repair shall be completed in one special repair zone and concrete shall have attained a compressive strength of 3200 psi before work can be started in the next special repair zone.

13.6 If any single repair area does not exceed 4 square feet in size and the total repair area within a special repair zone does not exceed 12 square feet, the special repair zone may be repaired at the same time as an adjacent zone.

Void Repair:

- 13.10 Any damage sustained to the void tube as a result of the contractor's operations shall be patched or replaced as required by the engineer at the contractor's expense.
- 13.11 An exposed void in the deck shall be patched as approved by the engineer in a manner that shall maintain the void area completely free of concrete. Cost of patching an exposed void will be considered completely covered by the contract unit price for Half-Sole Repair.

13.12 When a deteriorated portion of the void tube is beyond the point of patching as determined by the engineer, the portion of the deteriorated void tube shall be replaced. The void area shall be maintained completely free of concrete. Cutting of the longitudinal reinforcing steel will not be permitted. The fiber tubes for producing the voids shall have an outside diameter with the wall thickness the same as the existing tubes and anchored at not more than the original spacing. Cost of replacing the void tube will be considered completely covered by the contract unit price for Deck Repair with Void Tube Replacement. Measurement will be horizontal projection of the area of exposed tube in plan.

Remove if repair is not required.

SDG:

For seal coat, asphalt, UBAWS, epoxy polymer or MMA polymer slurry wearing surfaces:

- Delete existing line inside wearing surface
- Adjust top of the original depth dimension to bottom of new wearing surface
- Adjust depth for thin wearing surfaces

Detailed  
Checked

DECK REPAIR DETAILS

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

DATE PREPARED	
10/17/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	26

COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	

DESCRIPTION	DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	

RHB04\_CIP\_VS\_or\_SS\_Slab      Guidance & Alternate Details

Detach all unused Drawing Models & Sheet Models before requesting PDFs for sign and seal.

STANDARD DRAWING GUIDANCE (SDG) (do not show on plans)

Select the appropriate 1st and 2nd sheet. Draw typical section as required and scale to fit within attached border replacing the provided example. Modify other details and notes as required (match orientation of actual reinforcement).

For solid slabs, all details shall be modified by removing voids and all notes pertaining to void repair.



District/SPM typically estimates the percentage of void tube replacement.

Transverse repair zoning over intermediate bents is required for these structures. Longitudinal repair zoning in spans is required only when hydro demolition is required and is based on anticipated quantity of deck repair if not overlaid, confidence of anticipated quantity of deck repair if overlaid, deck rating (e.g. 6 or better may not need zoning). See EPG 751.40 (If only transverse zoning is required, Zones shall be called "Special Repair Zones").

Wearing surface thickness can vary according to grade elevation requirements and minimum barrier curb height requirements. Maximum thickness should be limited to 3" (Ref. Organizational Results Research Report ORO6.004, May 2006). Limit excludes reinforced concrete slab wearing surfaces.

Will need to adjust wearing surface thickness when detailing a thin wearing surface (1" or less), but it is a preferred detailing practice to show a discernable thickness on the plans. No thickness is shown for crack filler application.

- (A) Show difference as **plus/minus X"±**, see Bridge Memo or SPM. e.g. **Match existing grade plus 2¼"±**
- (B) Identify new wearing surface, see Bridge Memo or SPM. Specify minimum thickness in deck details, typically 1/4" thicker outside special repair zones for hydro Case 1 & 2.
- (C) Identify existing wearing surface and thickness, see Bridge Memo or existing plans.
- (D) See Bridge Memo or SPM, typically 1/2". Use 1" if more than 30% of existing deck needs repair. Verify there will be a minimum of 1/2" of concrete above top bars to allow for this much scarification.
- (E) See Bridge Memo or SPM, typically 1/4" inside special repair zones to avoid deeper penetration into newly repaired areas and 1/2" outside special repair zones.
- (F) See existing plans.
- (G) Use appropriate reference (☑ Structure, ☑ Roadway, ☑ Median, etc.)
- (H) Two types of overhang rehabilitation are shown. Cleaning and epoxy coating is preferred because of the relative short life of slab edge repair and unformed repair especially when over traffic. However in urban regions repairing the overhang may be preferred. Consult with SPM or SLE.
- (I) Scarification prior to adding first wearing surface or removing a portion of the deck when removing an existing wearing surface is not required for seal coat, asphalt, UBAWS, epoxy polymer or MMA polymer slurry wearing surfaces.
- (J) Monolithic deck repair should only be allowed where longitudinal zoning is not required.
- (K) May be used for aesthetics with extensive patchwork of repairs visible to public.



Two spans and five spans shown. These details can be used on Sheets RHB04j and RHB04L for conventional deck repair only projects.




SEC/SUR \* TWP \* RGE \*


U.I.P., STRENGTHEN AND REHABILITATE EXISTING (X', X', X') WIDE FLANGE BEAM SPANS (SKEW: X)

STANDARD DETAILING GUIDANCE  
(do not show on plans):  
Use for adding welded cover plates  
and applying a jacking load to  
increase capacity.


A "no jack" option may be used by  
designer in lieu of "jacking" option.  
Welding in both cases should not be  
performed under live load, especially  
direct live load.



TYPICAL ELEVATION OF BEAM  
Span ( - ) and ( - )



SECTION THRU BEAM



DETAIL OF FLANGE PLATE

Estimated Quantities		
Item	Lump Sum	Total
Strengthening Existing Beams		1

**General Notes:**

**Design Specifications:**

2002 AASHTO LFD (17th Ed.) Standard Specifications

**Design Loading:**

1993 Missouri Posting Loads (H20 & 3S2)  
No Future Wearing Surface

**Design Unit Stresses:**

Structural Carbon Steel Fy= 36,000 psi (New Steel)  
Existing Steel Fy =       psi  
Working Stress Design = 68% of Fy (Existing)

**Paint:**

Calcium Sulfonate (2 coats)

**Beam Support:**

All existing beams in the span being strengthened shall be raised simultaneously Dimension H at jacking point and supported during welding of new steel plates.

The temporary supports must be capable of safely supporting a service load of approximately Load J tons per beam (factor of safety not included). See special provisions.

**Traffic Handling:**

One lane of traffic shall be maintained on structure during construction. See roadway plans for traffic control.

**Miscellaneous:**

Outline of existing work is indicated by light dashed lines.  
Heavy lines indicate new work.

Longitudinal dimensions are based on the original design plans.

Table of Variables									
Beam Location		Dimensions							
		A	B	C	D	E	F	G	H

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. 1 of


REPAIRS TO BRIDGE: ROUTE \*  
OVER \*  
ROUTE \* FROM \* TO \*  
ABOUT \* MILES \* OF \*  
STA. \_\_\_\_\_± (Match Existing)

DESCRIPTION


DATE


MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)



TYPICAL PART SECTION SHOWING OPTIONAL  
SLAB CANTILEVER REPLACEMENT

OPTIONAL SLAB CANTILEVER REPLACEMENT

MoDOT Construction personnel will indicate the method used:

- ☐ Optional replacement method was used.  
☐ Optional replacement method was not used.


Notes:

\* Minimum distance required for mechanical bar splice. All existing transverse slab reinforcement in this area shall be cleanly stripped.

With the optional slab cantilever replacement, the contractor shall use a mechanical bar splice for the existing exposed transverse slab reinforcement. The length of the new #6 reinforcing bars used with the mechanical bar splice shall be determined by the contractor based on the style of mechanical bar splice used and other considerations. Mechanical bars splices shall be in accordance with Sec 706 except that there will be no separate pay item for mechanical bar splices. The mechanical bar splices and accompanying new #6 reinforcing bars will be considered completely covered by contract unit price for other items included in the contract.

For spacing of longitudinal reinforcing steel, see Sheet No. .

For details of barrier, see Sheets No. & .



TYPICAL PART SECTION SHOWING OPTIONAL  
SLAB CANTILEVER REPLACEMENT

ALTERNATE DETAIL SHOWING  
SAFETY BARRIER CURB


(Use only to match existing if only some portions of barrier are being replaced.)

DETAILS OF OPTIONAL SLAB CANTILEVER REPLACEMENT

Detailed  
Checked


Note: This drawing is not to scale. Follow dimensions.

Sheet No. of


DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 28
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	



Standard Drawing Guidance  
(do not show on plans):  
Modify standard drawing details as required.  
① Compute factored Design Force  
Use pay item Fiber Reinforced Polymer Wrap, \_\_sq. foot.  
Add the following note to Expansion Bent Details.  
Protective Coating - Concrete Bents and Piers (Epoxy or Urethane) shall not be applied on the FRP system.



PART PLAN




PART ELEVATION


FRP WRAP AT INT. BENT NO.

Notes:  
Design Force is the factored shear force at any cross section in each design region that shall be resisted entirely by the FRP reinforcement.  
See special provisions.

BENT CAP SHEAR STRENGTHENING USING FRP WRAP

Detailed  
Checked

DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 30
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	



**General Notes:**

**Design Specifications:**  
2002 AASHTO LFD (17th Ed.) Standard Specifications

Fabricated structural steel shall be ASTM A709 Grade 36 or 50.

Field connections shall be made with 3/4-inch diameter ASTM F3125 Grade A325 Type 1 bolts and 13/16-inch diameter holes.

Only one pile shall be repaired at a time.

**Instructions for Pile Plating:**

(1) Number of 3" spaces shall be determined in the field to extend past the extents of the deteriorated area.

(2) Plate length shall be determined in the field.

(3) Extents of deteriorated area will be determined by the engineer.

(4) Use plates as templates for field drilling holes in existing pile. Place bolts snug tight as drilled per each. High-strength tightening shall begin after all bolts are installed per flange or web.

**General Notes:**

Contact surfaces shall be in accordance with Sec 1081 for surface preparation.

All new or existing structural steel shall be coated with a minimum of two coats of inorganic zinc primer (5 mils minimum).

Cost of furnishing and installing structural steel, all steel coatings and any other incidental material or labor to complete pile repair, complete in place, will be considered completely covered by the contract unit price for Steel Pile Repair. Variations may be encountered in the estimated quantities but the variations can not be used for an adjustment in the contract unit price.

Cost of all excavation will be considered completely covered by the contract lump sum price for Class 2 Excavation.


Cost of dewatering will be considered completely covered by the contract lump sum price for Dewatering. See special provisions.

For details of pile encasement, see Sheet No. .

PILE PLATING ①

PILE REPAIR

All exposed surfaces of the existing structural steel piles and sway bracing shall be recoated with one 6-mil thickness of aluminum gray epoxy-mastic primer applied over an SSPC-SP3 surface preparation in accordance with Sec 1081. The bituminous coating shall be applied one foot above and below the existing ground line and in accordance with Sec 702. These protective coatings will not be required below the normal low water line. The cost of surface preparation will be considered completely covered by the contract lump sum price for Surface Preparation for Applying Epoxy-Mastic Primer. The cost of the aluminum gray epoxy-mastic primer and bituminous coating will be considered completely covered by the contract lump sum price for Aluminum Gray Epoxy-Mastic Primer. ③ (Add to either method)



PART ELEVATION SHOWING PARTIAL PILE REPLACEMENT

**General Notes:**

New steel pile section shall be the same grade as, or greater than, the existing pile (ASTM A709 Grade 36 or 50).

New steel pile section shall be coated in accordance with Sec 702. ④

Only one pile shall be repaired at a time. Repair shall be a continuous operation from removal through splicing.

(1) Length and location of pile replacement will be determined by the engineer.

Cost of furnishing and installing structural steel pile, all steel coatings and any other incidental material or labor to complete pile repair, complete in place, will be considered completely covered by the contract unit price for Steel Pile Repair. Variations may be encountered in the estimated quantities but the variations can not be used for an adjustment in the contract unit price.

Cost of all excavation will be considered completely covered by the contract lump sum price for Class 2 Excavation.

Cost of dewatering will be considered completely covered by the contract lump sum price for Dewatering. See special provisions.

See Supplemental Details of HP10x42 Pile Encasement With Pile Repair Sheet.

PARTIAL PILE REPLACEMENT ②

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions. Sheet No. of

Standard Drawing Guidance  
(do not show on plans):

Show only pile repair method required. Delete all other details. If used in combination, specify associated pile(s) by method.


- ①

Based on similar percentage of section loss, pile plating may be more attractive than partial pile replacement. Details can be modified if only the web or flanges need to be plated. If only the web is plated, plates on each side of the web are required. If only a flange is to be plated, both flanges and plates on each side of the flanges are required. Overall symmetry of the section shall be maintained.
- ②

Based on additional factors other than just percent of section loss, partial pile replacement may be considered. Minimizing or eliminating traffic loading, adding falsework, or just having support conditions such as integral bents can help to determine the repair method. Pile replacement shall not be used if multiple piles need repair and falsework is not provided.
- ③

Use this note for coating any remaining piles or pile sections, and sway bracing not being repaired. Use this note on Front Sheet or Notes Sheet when no repair or no encasement is required. Include standard pay items "Surface Preparation for Applying Epoxy-Mastic Primer" and either "Aluminum Epoxy-Mastic Primer" or "Gray Epoxy-Mastic Primer".  
  
"Aluminum" is preferred because it acts as both a barrier and corrosion protection where "Gray" only acts as a barrier. If for any reason coated pile is embedded in fresh concrete or "Gray" is being used elsewhere, "Aluminum" shall not be used.
- ④

If galvanizing is preferred, add splice detail and replace note with:  
New steel pile section shall be galvanized. See special provisions.




See EPG 751.40.1.2.1 for guidance on when coating, encasement or jacketing, and plating or partial replacement should be considered.

Show Quantity Table on sheet. (Possible items given)

Quantity Table		
Item		Quantity
Class 2 Excavation	Lump sum	x
Dewatering	Lump sum	x
Surface Preparation for Applying Epoxy-Mastic Primer	Lump sum	x
Aluminum Epoxy-Mastic Primer	Lump sum	x
Gray Epoxy-Mastic Primer	Lump sum	x
Steel Pile Repair	Linear foot	x
Pile Encasement	Linear foot	x

These quantities are included in the Estimated Quantities table on Sheet No. .







Standard Drawing Guidance  
(do not show on plans):




① This sheet is supplemental to Details of Pile Repair Sheet. Use details that match the selected pile repair method. Delete all other details. Use general notes and bill of reinforcing steel for either method.


See EPG 751.40.1.2.1 for guidance on when coating, encasement or jacketing, and plating or partial replacement should be considered.

② Delete note if there is not any existing sway bracing.

Existing sway bracing may need to be removed and replaced or reattached if it is located in the area of pile to be replaced or plated.

③ Shear connectors are only used for partial pile replacement.



BILL OF REINFORCING STEEL - EACH PILE				
NO.	SIZE & MARK	ACTUAL LENGTH	SHAPE	BENDING DIAGRAM
Varies	4 P1	10'-0"	16	 SHAPE 16
8	5 V1	Varies	20	

Notes:

All dimensions are out to out.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

Actual lengths are measured along centerline of bar to the nearest inch.

All bars shall be epoxy coated.

All exposed surfaces of the existing structural steel piles and sway bracing shall be recoated with one 6-mil thickness of aluminum gray epoxy-mastic primer applied over an SSPC-SP3 surface preparation in accordance with Sec 1081. The bituminous coating shall be applied one foot above and below the existing ground line and in accordance with Sec 702. These protective coatings will not be required below the normal low water line. The cost of surface preparation will be considered completely covered by the contract lump sum price for Surface Preparation for Applying Epoxy-Mastic Primer. The cost of the aluminum gray epoxy-mastic primer and bituminous coating will be considered completely covered by the contract lump sum price for Aluminum Gray Epoxy-Mastic Primer. ①

General Notes:

All concrete for pile encasement shall be Class B ( $f'c = 3000$  psi).

The reinforcing steel shall be epoxy coated Grade 60 with  $f_y = 60,000$  psi


Minimum clearance to reinforcing steel shall be 1 1/2", unless otherwise shown.

The exposed and accessible surfaces of the existing structural steel that will be encased in concrete shall be cleaned with a minimum of SSPC-SP-3 surface preparation and coated with a minimum of one coat of gray epoxy-mastic primer (non-aluminum) in accordance with Sec 1081 to produce a dry film thickness of not less than 3 mils before concrete is poured. The surface preparation and coating for piles shall extend a minimum of one foot outside the face of the pile encasement.

Cost of all concrete, reinforcement, shear connectors, surface preparation, coatings, excavation, dewatering and any other incidental material or labor to complete pile encasement, complete in place, will be considered completely covered by the contract unit price for Pile Encasement.


A FRP pile jacketing system may be used in lieu of pile encasement at the contractor's option. No additional payment will be made for this substitution. See special provisions.

Shear connectors shall be in accordance with Sec 712, 1037 and 1080.



PART ELEVATION SHOWING PILE ENCASEMENT

Note: Existing sway bracing not shown for clarity. Shift reinforcing steel in the field to clear existing sway bracing. ②



SECTION SHOWING PILE ENCASEMENT

PILE ENCASEMENT

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 33
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	DATE
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
MDOT	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	


Standard Drawing Guidance  
(do not show on plans):


- ① Use this note for coating any remaining piles or pile sections, and sway bracing not being repaired. Use this note on Front Sheet or Notes Sheet when no repair or no encasement is required. Include standard pay items "Surface Preparation for Applying Epoxy-Mastic Primer" and either "Aluminum Epoxy-Mastic Primer" or "Gray Epoxy-Mastic Primer".

"Aluminum" is preferred because it acts as both a barrier and corrosion protection where "Gray" only acts as a barrier. If for any reason coated pile is embedded in fresh concrete or "Gray" is being used elsewhere, "Aluminum" shall not be used.)

See EPG 751.40.1.2.1 for guidance on when coating, encasement or jacketing, and plating or partial replacement should be considered.

- ② Delete note if there is not any existing sway bracing.





General Notes:

Design Specifications:  
2002 AASHTO LFD (17th Ed.) Standard Specifications

Fabricated structural steel shall be ASTM A709 Grade 36 or 50.

Field connections shall be made with 3/4-inch diameter ASTM F3125 Grade A325 Type 1 bolts and 13/16-inch diameter holes.

Only one pile shall be repaired at a time.

Instructions for Pile Plating:

(1) Number of 3" spaces shall be determined in the field to extend past the extents of the deteriorated area.

(2) Plate length shall be determined in the field.

(3) Extents of deteriorated area will be determined by the engineer.

(4) Use plates as templates for field drilling holes in existing pile. Place bolts snug tight as drilled per each. High-strength tightening shall begin after all bolts are installed per flange or web.

General Notes:

Contact surfaces shall be in accordance with Sec 1081 for surface preparation.

All new or existing structural steel shall be coated with a minimum of two coats of inorganic zinc primer (5 mils minimum).

Cost of furnishing and installing structural steel, all steel coatings and any other incidental material or labor to complete pile repair, complete in place, will be considered completely covered by the contract unit price for Steel Pile Repair. Variations may be encountered in the estimated quantities but the variations can not be used for an adjustment in the contract unit price.


Cost of all excavation will be considered completely covered by the contract lump sum price for Class 2 Excavation.

Cost of dewatering will be considered completely covered by the contract lump sum price for Dewatering. See special provisions.

For details of pile encasement, see Sheet No. .

## PILE PLATING ①

All exposed surfaces of the existing structural steel piles and sway bracing shall be recoated with one 6-mil thickness of aluminum gray epoxy-mastic primer applied over an SSPC-SP3 surface preparation in accordance with Sec 1081. The bituminous coating shall be applied one foot above and below the existing ground line and in accordance with Sec 702. These protective coatings will not be required below the normal low water line. The cost of surface preparation will be considered completely covered by the contract lump sum price for Surface Preparation for Applying Epoxy-Mastic Primer. The cost of the aluminum gray epoxy-mastic primer and bituminous coating will be considered completely covered by the contract lump sum price for Aluminum Gray Epoxy-Mastic Primer. ③ (Add to either method)



General Notes:

New steel pile section shall be the same grade as, or greater than, the existing pile (ASTM A709 Grade 36 or 50).

New steel pile section shall be coated in accordance with Sec 702. (4)

Only one pile shall be repaired at a time. Repair shall be a continuous operation from removal through splicing.

(1) Length and location of pile replacement will be determined by the engineer.


Cost of furnishing and installing structural steel pile, all steel coatings and any other incidental material or labor to complete pile repair, complete in place, will be considered completely covered by the contract unit price for Steel Pile Repair. Variations may be encountered in the estimated quantities but the variations can not be used for an adjustment in the contract unit price.

Cost of all excavation will be considered completely covered by the contract lump sum price for Class 2 Excavation.

Cost of dewatering will be considered completely covered by the contract lump sum price for Dewatering. See special provisions.

See Supplemental Details of HP12x53 Pile Encasement With Pile Repair Sheet.

## PARTIAL PILE REPLACEMENT ②

DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 34
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DATE	DESCRIPTION
<div> <div>MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION</div> <div>  <div> 105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636) </div> </div> </div>	

RHB12\_12x53PileRepair

Guidance & Alternate Details

Standard Drawing Guidance  
(do not show on plans):

Show only pile repair method required. Delete all other details. If used in combination, specify associated pile(s) by method.

- ①


Based on similar percentage of section loss, pile plating may be more attractive than partial pile replacement. Details can be modified if only the web or flanges need to be plated. If only the web is plated, plates on each side of the web are required. If only a flange is to be plated, both flanges and plates on each side of the flanges are required. Overall symmetry of the section shall be maintained.
- ②

Based on additional factors other than just percent of section loss, partial pile replacement may be considered. Minimizing or eliminating traffic loading, adding falsework, or just having support conditions such as integral bents can help to determine the repair method. Pile replacement shall not be used if multiple piles need repair and falsework is not provided.
- ③

Use this note for coating any remaining piles or pile sections, and sway bracing not being repaired. Use this note on Front Sheet or Notes Sheet when no repair or no encasement is required. Include standard pay items "Surface Preparation for Applying Epoxy-Mastic Primer" and either "Aluminum Epoxy-Mastic Primer" or "Gray Epoxy-Mastic Primer".  
  
"Aluminum" is preferred because it acts as both a barrier and corrosion protection where "Gray" only acts as a barrier. If for any reason coated pile is embedded in fresh concrete or "Gray" is being used elsewhere, "Aluminum" shall not be used.

- ④

If galvanizing is preferred, add splice detail and replace note with:  
  
New steel pile section shall be galvanized. See special provisions.



STEEL PILE SPLICE


\* Galvanizing material shall be omitted or removed 1 inch clear of weld locations. See Special Provisions.


See EPG 751.40.1.2.1 for guidance on when coating, encasement or jacketing, and plating or partial replacement should be considered.

Show Quantity Table on sheet. (Possible items given)

Quantity Table		
Item		Quantity
Class 2 Excavation	lump sum	x
Dewatering	lump sum	x
Surface Preparation for Applying Epoxy-Mastic Primer	lump sum	x
Aluminum Epoxy-Mastic Primer	lump sum	x
Gray Epoxy-Mastic Primer	lump sum	x
Steel Pile Repair	linear foot	x
Pile Encasement	linear foot	x

These quantities are included in the Estimated Quantities table on Sheet No. .



BILL OF REINFORCING STEEL - EACH PILE				
NO.	SIZE & MARK	ACTUAL LENGTH	SHAPE	BENDING DIAGRAM
Varies	4 P1	10'-0"	16	
8	5 V1	Varies	20	

Notes:

All dimensions are out to out.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

Actual lengths are measured along centerline of bar to the nearest inch.

All bars shall be epoxy coated.

General Notes:

All concrete for pile encasement shall be Class B ( $f'c = 3000$  psi).

The reinforcing steel shall be epoxy coated Grade 60 with  $f_y = 60,000$  psi

Minimum clearance to reinforcing steel shall be 1 1/2", unless otherwise shown.


The exposed and accessible surfaces of the existing structural steel that will be encased in concrete shall be cleaned with a minimum of SSPC-SP-3 surface preparation and coated with a minimum of one coat of gray epoxy-mastic primer (non-aluminum) in accordance with Sec 1081 to produce a dry film thickness of not less than 3 mils before concrete is poured. The surface preparation and coating for piles shall extend a minimum of one foot outside the face of the pile encasement.

Cost of all concrete, reinforcement, shear connectors, surface preparation, coatings and any other incidental material or labor to complete pile encasement, complete in place, will be considered completely covered by the contract unit price for Pile Encasement. ③

A FRP pile jacketing system may be used in lieu of pile encasement at the contractor's option. No additional payment will be made for this substitution. See special provisions.


Shear connectors shall be in accordance with Sec 712, 1037 and 1080. ③

For details of pile plating, see Sheet No. .




PART ELEVATION SHOWING PILE ENCASEMENT ①

Note: Existing sway bracing not shown for clarity. Shift reinforcing steel in the field to clear existing sway bracing. ②




SECTION SHOWING PILE ENCASEMENT WITH PILE PLATING ①



PART ELEVATION SHOWING PILE ENCASEMENT ①

Note: Existing sway bracing not shown for clarity. Shift reinforcing steel in the field to clear existing sway bracing. ②



SECTION SHOWING PILE ENCASEMENT WITH PARTIAL PILE REPLACEMENT ①

PILE ENCASEMENT WITH PILE REPAIR

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 35
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	DATE
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	



Standard Drawing Guidance  
(do not show on plans):


① This sheet is supplemental to Details of Pile Repair Sheet. Use details that match the selected pile repair method. Delete all other details. Use general notes and bill of reinforcing steel for either method.


See EPG 751.40.1.2.1 for guidance on when coating, encasement or jacketing, and plating or partial replacement should be considered.

② Delete note if there is not any existing sway bracing.

Existing sway bracing may need to be removed and replaced or reattached if it is located in the area of pile to be replaced or plated.

③ Shear connectors are only used for partial pile replacement.



BILL OF REINFORCING STEEL - EACH PILE				
NO.	SIZE & MARK	ACTUAL LENGTH	SHAPE	BENDING DIAGRAM
Varies	4 P1	10'-0"	16	 SHAPE 16
8	5 V1	Varies	20	

Notes:

All dimensions are out to out.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

Actual lengths are measured along centerline of bar to the nearest inch.

All bars shall be epoxy coated.

All exposed surfaces of the existing structural steel piles and sway bracing shall be recoated with one 6-mil thickness of aluminum gray epoxy-mastic primer applied over an SSPC-SP3 surface preparation in accordance with Sec 1081. The bituminous coating shall be applied one foot above and below the existing ground line and in accordance with Sec 702. These protective coatings will not be required below the normal low water line. The cost of surface preparation will be considered completely covered by the contract lump sum price for Surface Preparation for Applying Epoxy-Mastic Primer. The cost of the aluminum gray epoxy-mastic primer and bituminous coating will be considered completely covered by the contract lump sum price for Aluminum Gray Epoxy-Mastic Primer.①

General Notes:

All concrete for pile encasement shall be Class B ( $f'c = 3000$  psi).

The reinforcing steel shall be epoxy coated Grade 60 with  $f_y = 60,000$  psi

Minimum clearance to reinforcing steel shall be 1 1/2", unless otherwise shown.

The exposed and accessible surfaces of the existing structural steel that will be encased in concrete shall be cleaned with a minimum of SSPC-SP-3 surface preparation and coated with a minimum of one coat of gray epoxy-mastic primer (non-aluminum) in accordance with Sec 1081 to produce a dry film thickness of not less than 3 mils before concrete is poured. The surface preparation and coating for piles shall extend a minimum of one foot outside the face of the pile encasement.


Cost of all concrete, reinforcement, shear connectors, surface preparation, coatings and any other incidental material or labor to complete pile encasement, complete in place, will be considered completely covered by the contract unit price for Pile Encasement.

Cost of all excavation will be considered completely covered by the contract lump sum price for Class 2 Excavation.

Cost of dewatering will be considered completely covered by the contract lump sum price for Dewatering. See special provisions.


A FRP pile jacketing system may be used in lieu of pile encasement at the contractor's option. No additional payment will be made for this substitution. See special provisions.

Shear connectors shall be in accordance with Sec 712, 1037 and 1080.



PART ELEVATION SHOWING PILE ENCASEMENT

Note: Existing sway bracing not shown for clarity. Shift reinforcing steel in the field to clear existing sway bracing.②



SECTION SHOWING PILE ENCASEMENT

PILE ENCASEMENT

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of


DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 36
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	DATE
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	


Standard Drawing Guidance  
(do not show on plans):

- ① Use this note for coating any remaining piles or pile sections, and sway bracing not being repaired. Use this note on Front Sheet or Notes Sheet when no repair or no encasement is required. Include standard pay items "Surface Preparation for Applying Epoxy-Mastic Primer" and either "Aluminum Epoxy-Mastic Primer" or "Gray Epoxy-Mastic Primer".
- "Aluminum" is preferred because it acts as both a barrier and corrosion protection where "Gray" only acts as a barrier. If for any reason coated pile is embedded in fresh concrete or "Gray" is being used elsewhere, "Aluminum" shall not be used.)

See EPG 751.40.1.2.1 for guidance on when coating, encasement or jacketing, and plating or partial replacement should be considered.

- ② Delete note if there is not any existing sway bracing.





General Notes:

Design Specifications:  
2002 AASHTO LFD (17th Ed.) Standard Specifications

Fabricated structural steel shall be ASTM A709 Grade 36 or 50.

Field connections shall be made with 3/4-inch diameter ASTM F3125 Grade A325 Type 1 bolts and 13/16-inch diameter holes.

Only one pile shall be repaired at a time.

Instructions for Pile Plating:

(1) Number of 1 1/2" staggered spaces and 3" spaces shall be determined in the field to extend past the extents of the deteriorated area.

(2) Plate length shall be determined in the field.

(3) Extents of deteriorated area will be determined by the engineer.

(4) Use plates as templates for field drilling holes in existing pile. Place bolts snug tight as drilled per each. High-strength tightening shall begin after all bolts are installed per flange or web.

General Notes:

Contact surfaces shall be in accordance with Sec 1081 for surface preparation.

All new or existing structural steel shall be coated with a minimum of two coats of inorganic zinc primer (5 mils minimum).

Cost of furnishing and installing structural steel, all steel coatings and any other incidental material or labor to complete pile repair, complete in place, will be considered completely covered by the contract unit price for Steel Pile Repair. Variations may be encountered in the estimated quantities but the variations can not be used for an adjustment in the contract unit price.

Cost of all excavation will be considered completely covered by the contract lump sum price for Class 2 Excavation.


Cost of dewatering will be considered completely covered by the contract lump sum price for Dewatering. See special provisions.

For details of pile encasement, see Sheet No. ---.

PILE PLATING ①

PILE REPAIR

All exposed surfaces of the existing structural steel piles and sway bracing shall be recoated with one 6-mil thickness of aluminum gray epoxy-mastic primer applied over an SSPC-SP3 surface preparation in accordance with Sec 1081. The bituminous coating shall be applied one foot above and below the existing ground line and in accordance with Sec 702. These protective coatings will not be required below the normal low water line. The cost of surface preparation will be considered completely covered by the contract lump sum price for Surface Preparation for Applying Epoxy-Mastic Primer. The cost of the aluminum gray epoxy-mastic primer and bituminous coating will be considered completely covered by the contract lump sum price for Aluminum Gray Epoxy-Mastic Primer. ③ (Add to either method)



PART ELEVATION SHOWING PARTIAL PILE REPLACEMENT

General Notes:

New steel pile section shall be the same grade as, or greater than, the existing pile (ASTM A709 Grade 36 or 50).

New steel pile section shall be coated in accordance with Sec 702. ④

Only one pile shall be repaired at a time. Repair shall be a continuous operation from removal through splicing.

(1) Length and location of pile replacement will be determined by the engineer.

Cost of furnishing and installing structural steel pile, all steel coatings and any other incidental material or labor to complete pile repair, complete in place, will be considered completely covered by the contract unit price for Steel Pile Repair. Variations may be encountered in the estimated quantities but the variations can not be used for an adjustment in the contract unit price.

Cost of all excavation will be considered completely covered by the contract lump sum price for Class 2 Excavation.

Cost of dewatering will be considered completely covered by the contract lump sum price for Dewatering. See special provisions.

See Supplemental Details of HP14x73 Pile Encasement With Pile Repair Sheet.

PARTIAL PILE REPLACEMENT ②

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

RHB15\_14x73PileRepair

Guidance & Alternate Details

Standard Drawing Guidance  
(do not show on plans):

- Show only pile repair method required. Delete all other details. If used in combination, specify associated pile(s) by method.
- ①

Based on similar percentage of section loss, pile plating may be more attractive than partial pile replacement. Details can be modified if only the web or flanges need to be plated. If only the web is plated, plates on each side of the web are required. If only a flange is to be plated, both flanges and plates on each side of the flanges are required. Overall symmetry of the section shall be maintained.
- ②


Based on additional factors other than just percent of section loss, partial pile replacement may be considered. Minimizing or eliminating traffic loading, adding falsework, or just having support conditions such as integral bents can help to determine the repair method. Pile replacement shall not be used if multiple piles need repair and falsework is not provided.
- ③

Use this note for coating any remaining piles or pile sections, and sway bracing not being repaired. Use this note on Front Sheet or Notes Sheet when no repair or no encasement is required. Include standard pay items "Surface Preparation for Applying Epoxy-Mastic Primer" and either "Aluminum Epoxy-Mastic Primer" or "Gray Epoxy-Mastic Primer".

"Aluminum" is preferred because it acts as both a barrier and corrosion protection where "Gray" only acts as a barrier. If for any reason coated pile is embedded in fresh concrete or "Gray" is being used elsewhere, "Aluminum" shall not be used.
- ④

If galvanizing is preferred, add splice detail and replace note with:

New steel pile section shall be galvanized. See special provisions.





See EPG 751.40.1.2.1 for guidance on when coating, encasement or jacketing, and plating or partial replacement should be considered.

Show Quantity Table on sheet. (Possible items given)

Quantity Table		
Item		Quantity
Class 2 Excavation	lump sum	x
Dewatering	lump sum	x
Surface Preparation for Applying Epoxy-Mastic Primer	lump sum	x
Aluminum Epoxy-Mastic Primer	lump sum	x
Gray Epoxy-Mastic Primer	lump sum	x
Steel Pile Repair	linear foot	x
Pile Encasement	linear foot	x

These quantities are included in the Estimated Quantities table on Sheet No. .



BILL OF REINFORCING STEEL - EACH PILE				
NO.	SIZE & MARK	ACTUAL LENGTH	SHAPE	BENDING DIAGRAM
Varies	4 P1	10'-0"	16	
8	5 V1	Varies	20	

Notes:

All dimensions are out to out.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

Actual lengths are measured along centerline of bar to the nearest inch.

All bars shall be epoxy coated.

General Notes:

All concrete for pile encasement shall be Class B ( $f'_c = 3000$  psi).

The reinforcing steel shall be epoxy coated Grade 60 with  $f_y = 60,000$  psi

Minimum clearance to reinforcing steel shall be 1 1/2", unless otherwise shown.


The exposed and accessible surfaces of the existing structural steel that will be encased in concrete shall be cleaned with a minimum of SSPC-SP-3 surface preparation and coated with a minimum of one coat of gray epoxy-mastic primer (non-aluminum) in accordance with Sec 1081 to produce a dry film thickness of not less than 3 mils before concrete is poured. The surface preparation and coating for piles shall extend a minimum of one foot outside the face of the pile encasement.

Cost of all concrete, reinforcement, shear connectors, surface preparation, coatings and any other incidental material or labor to complete pile encasement, complete in place, will be considered completely covered by the contract unit price for Pile Encasement. ③

A FRP pile jacketing system may be used in lieu of pile encasement at the contractor's option. No additional payment will be made for this substitution. See special provisions.


Shear connectors shall be in accordance with Sec 712, 1037 and 1080. ③

For details of pile plating, see Sheet No. \_\_.




PART ELEVATION SHOWING PILE ENCASEMENT ①

Note: Existing sway bracing not shown for clarity. Shift reinforcing steel in the field to clear existing sway bracing. ②




SECTION SHOWING PILE ENCASEMENT WITH PILE PLATING ①




PART ELEVATION SHOWING PILE ENCASEMENT ①

Note: Existing sway bracing not shown for clarity. Shift reinforcing steel in the field to clear existing sway bracing. ②



SECTION SHOWING PILE ENCASEMENT WITH PARTIAL PILE REPLACEMENT ①

PILE ENCASEMENT WITH PILE REPAIR

DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 38
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	DATE
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	

RHB16\_14x73PileRepairEncased

Guidance & Alternate Details

Standard Drawing Guidance  
(do not show on plans):


- ①

This sheet is supplemental to Details of Pile Repair Sheet. Use details that match the selected pile repair method. Delete all other details. Use general notes and bill of reinforcing steel for either method.
- See EPG 751.40.1.2.1 for guidance on when coating, encasement or jacketing, and plating or partial replacement should be considered.
- ②

Delete note if there is not any existing sway bracing.

Existing sway bracing may need to be removed and replaced or reattached if it is located in the area of pile to be replaced or plated.
- ③

Shear connectors are only used for partial pile replacement.








Standard Drawing Guidance  
(do not show on plans):


- ① Use this note for coating any remaining piles or pile sections, and sway bracing not being repaired. Use this note on Front Sheet or Notes Sheet when no repair or no encasement is required. Include standard pay items "Surface Preparation for Applying Epoxy-Mastic Primer" and either "Aluminum Epoxy-Mastic Primer" or "Gray Epoxy-Mastic Primer".

"Aluminum" is preferred because it acts as both a barrier and corrosion protection where "Gray" only acts as a barrier. If for any reason coated pile is embedded in fresh concrete or "Gray" is being used elsewhere, "Aluminum" shall not be used.)

See EPG 751.40.1.2.1 for guidance on when coating, encasement or jacketing, and plating or partial replacement should be considered.

- ② Delete note if there is not any existing sway bracing.






Detailed  
Checked


Note: This drawing is not to scale. Follow dimensions.

Sheet No. of




PART SECTION NEAR DRAIN


(1) Use backer rod around drain @ bottom of slab and epoxy inject from the top.




PART SECTION SHOWING BRACKET ASSEMBLY




PART PLAN OF SLAB AT DRAIN



ELEVATION OF DRAIN



PLAN OF DRAIN




PLAN OF OPTIONAL FRP DRAIN

ANCHOR TO EXISTING SLAB, STEEL GIRDER

(Based on A02015 & A46301)

## RHB18\_Cored\_Slab\_Drains Alternate Details Sh. 1 of 2




PART SECTION SHOWING  
BRACKET ASSEMBLY

PRESTRESSED GIRDER,  
EXISTING  
CURB BLOCKOUT


(1) Use backer rod around drain @ bottom of slab and epoxy inject from the top.

PART SECTION NEAR DRAIN




PART PLAN SHOWING CORED SLAB DRAIN LOCATIONS


## EXAMPLE PLAN




PLAN OF SLAB SHOWING SLAB DRAIN LOCATIONS



PART SECTION NEAR DRAIN




PART SECTION SHOWING BRACKET ASSEMBLY




PART PLAN OF SLAB AT DRAIN


SLAB DRAINS



ELEVATION OF DRAIN



PLAN OF STEEL DRAIN OPTION



PLAN OF FRP DRAIN OPTION

General Notes:

Contractor shall have the option to construct either steel or FRP slab drains. All drains shall be of same type.

Slab drain bracket assembly shall be ASTM A709 Grade 36 steel.

Locate drains in slab by dimensions shown in Part Section Near Drain.

Reinforcing steel shall be shifted to clear drains.

The coil inserts and bracket assembly shall be galvanized in accordance with ASTM A123.

All bolts, hardened washers, lock washers and nuts shall be galvanized in accordance with AASHTO M 232 (ASTM A153), Class C.

All 1/2"Ø bolts shall be ASTM A307.

Shop drawings will not be required for the slab drains and the bracket assembly.

The coil insert required for the bracket assembly attachment shall be located on the prestressed girder shop drawings.

Coil inserts shall have a concrete pull-out strength (ultimate load) of at least 2,500 pounds in 5,000 psi concrete.

The bolt required to attach the slab drain bracket assembly to the prestressed girder web shall be supplied by the prestressed girder fabricator.

Notes for Steel Drain:

Slab drains may be fabricated of either 1/4" welded sheets of ASTM A709 Grade 36 steel or from 1/4" structural steel tubing ASTM A500 or A501.

Outside dimensions of drains are 8" x 4".

The drains shall be galvanized in accordance with ASTM A123.

Notes for FRP Drain:

Drains shall be machine filament-wound thermosetting resin tubing meeting the requirements of ASTM D2996 with the following exceptions:

Shape of drains shall be rectangular with outside nominal dimensions of 8" x 4".

Minimum reinforced wall thickness shall be 1/4 inch.

The resin used shall be ultraviolet (UV) resistant and/or have UV inhibitors mixed throughout. Drains may have an exterior coating for additional UV resistance.

The color of the slab drain shall be gray (Federal Standard 26373). The color shall be uniform throughout the resin and any coating used.

The combination of materials used in the manufacture of the drains shall be tested for UV resistance in accordance with ASTM D4329 Cycle A. The representative material shall withstand at least 500 hours of testing with only minor discoloration and without any physical deterioration. The contractor shall furnish the results of the required ultraviolet testing prior to acceptance of the slab drains.

At the contractor's option, drains may be field cut. The method of cutting FRP slab drain shall be as recommended by the manufacturer to ensure a smooth, chip free cut.

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

DATE PREPARED	
10/17/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	1

COUNTY
JOB NO.
CONTRACT ID.
PROJECT NO.
BRIDGE NO.

DESCRIPTION
DATE


MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-273-6636)





Alternate details for Type B barrier (SBC):

Standard Drawing Guidance (do not show on plans):

- ① Replace example Plan of Slab Showing Slab Drain Locations with actual plan.
- ② Details shown inside the sheet border are for drains transverse to roadway requiring a cantilever 4 feet or more. Use the below details for drains parallel to roadway requiring a cantilever 3'-8" or more.
- ③ Delete panels for CIP slab.
- ④ Total drain length is equal to 9" + maximum girder and haunch + slab thickness, rounded UP to the next whole inch.




PART PLAN OF SLAB AT DRAIN




PART PLAN OF SLAB AT DRAIN


②




PART SECTION SHOWING BRACKET ASSEMBLY




PART PLAN OF SLAB AT DRAIN



ELEVATION OF DRAIN




### PLAN OF STEEL DRAIN OPTION



PLAN OF FRP DRAIN OPTION





General Notes:

Contractor shall have the option to construct either steel or FRP slab drains. All drains shall be of same type.

Slab drain bracket assembly shall be ASTM A709 Grade 36 steel.

Locate drains in slab by dimensions shown in Part Section Near Drain.

Reinforcing steel shall be shifted to clear drains.

The coil inserts and bracket assembly shall be galvanized in accordance with ASTM A123.

All bolts, hardened washers, lock washers and nuts shall be galvanized in accordance with AASHTO M 232 (ASTM A153), Class C.

All 1/2"Ø bolts shall be ASTM A307.

Shop drawings will not be required for the slab drains and the bracket assembly.

The coil insert required for the bracket assembly attachment shall be located on the prestressed girder shop drawings.

Coil inserts shall have a concrete pull-out strength (ultimate load) of at least 2,500 pounds in 5,000 psi concrete.

The bolt required to attach the slab drain bracket assembly to the prestressed girder web shall be supplied by the prestressed girder fabricator.

Notes for Steel Drain:

Slab drains may be fabricated of either 1/4" welded sheets of ASTM A709 Grade 36 steel or from 1/4" structural steel tubing ASTM A500 or A501.

Outside dimensions of drains are 8" x 4".

The drains shall be galvanized in accordance with ASTM A123.

Notes for FRP Drain:

Drains shall be machine filament-wound thermosetting resin tubing meeting the requirements of ASTM D2996 with the following exceptions:

Shape of drains shall be rectangular with outside nominal dimensions of 8" x 4".

Minimum reinforced wall thickness shall be 1/4 inch.




The resin used shall be ultraviolet (UV) resistant and/or have UV inhibitors mixed throughout. Drains may have an exterior coating for additional UV resistance.

The color of the slab drain shall be gray (Federal Standard 26373). The color shall be uniform throughout the resin and any coating used.




The combination of materials used in the manufacture of the drains shall be tested for ultraviolet resistance in accordance with ASTM D4329 Cycle A. The representative material shall withstand at least 500 hours of testing with only minor discoloration and without any physical deterioration. The contractor shall furnish the results of the required ultraviolet testing prior to acceptance of the slab drains.

At the contractor's option, drains may be field cut. The method of cutting FRP slab drain shall be as recommended by the manufacturer to ensure a smooth, chip free cut.

Both upper and lower drain pieces shall be rigidly connected to each other. Drain flow shall not be obstructed. Approval of the engineer is required.





## SLAB DRAINS








[illegible]

Standard Drawing Guidance (do not show on plans):

- ① Replace example Plan of Slab Showing Slab Drain Locations with actual plan.
- ② Details shown inside the sheet border are for drains transverse to roadway requiring a cantilever 4 feet or more. Use the below details for drains parallel to roadway requiring a cantilever 3'-8" or more.
- ③ Delete panels for CIP slab.
- ④ Total drain length is equal to 9" + maximum girder and haunch + slab thickness, rounded UP to the next whole inch.

Alternate details for Type B barrier (SBC):





General Notes:

Contractor shall have the option to construct either steel or FRP slab drains. All drains shall be of same type.

Slab drain bracket assembly shall be ASTM A709 Grade 36 steel.

Locate drains in slab by dimensions shown in Part Section Near Drain.

Reinforcing steel shall be shifted to clear drains.

The bracket assembly shall be galvanized in accordance with ASTM A123.

All bolts, hardened washers, lock washers and nuts shall be galvanized in accordance with AASHTO M 232 (ASTM A153), Class C, except as shown. ④

All 1/2-inch diameter bolts shall be ASTM A307, except as shown.

Shop drawings will not be required for the slab drains and the bracket assembly.

The bolt hole for the bracket assembly attachment shall be located on the plate girder shop drawings.

The galvanized surfaces of drain support brackets shall be prepared according to the coating manufacturer's recommendation and field coated with a gray epoxy-mastic primer (non-aluminum) within a distance of 6 inches from the point of connection to the weathering steel structure.

Notes for Steel Drain:

Slab drains may be fabricated of either 1/4-inch welded sheets of ASTM A709 Grade 36 steel or from 1/4-inch structural steel tubing ASTM A500 or A501.

Outside dimensions of drains are 8" x 4".

The drains shall be galvanized in accordance with ASTM A123.

Notes for FRP Drain:

Drains shall be machine filament-wound thermosetting resin tubing meeting the requirements of ASTM D2996 with the following exceptions:

Shape of drains shall be rectangular with outside nominal dimensions of 8" x 4".

Minimum reinforced wall thickness shall be 1/4 inch.

The resin used shall be ultraviolet (UV) resistant and/or have UV inhibitors mixed throughout. Drains may have an exterior coating for additional UV resistance.


The color of the slab drain shall be gray (Federal Standard 26373). The color shall be uniform throughout the resin and any coating used.

The combination of materials used in the manufacture of the drains shall be tested for Ultraviolet resistance in accordance with ASTM D4329 Cycle A. The representative material shall withstand at least 500 hours of testing with only minor discoloration and without any physical deterioration. The contractor shall furnish the results of the required ultraviolet testing prior to acceptance of the slab drains.

At the contractor's option, drains may be field cut. The method of cutting FRP slab drain shall be as recommended by the manufacturer to ensure a smooth, chip free cut.

DATE PREPARED 10/17/2023					
ROUTE			STATE <b>MO</b>		
DISTRICT			SHEET NO. <b>1</b>		
COUNTY					
JOB NO.					
CONTRACT ID.					
PROJECT NO.					
BRIDGE NO.					
DESCRIPTION					
DATE					

MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION





**MoDOT**


105 WEST CAPITOL  
JEFFERSON CITY, MO 65102

Standard Drawing Guidance (do not show on plans):


- ① Replace example Plan of Slab Showing Slab Drain Locations with actual plan.
- ② Details shown inside the sheet border are for drains transverse to roadway.  
Use the below details for drains parallel to roadway.
- ③ Use 1/6 of web depth.
- ④ Use with weathering steel. Delete for painted or galvanized steel.
- ⑤ Type 3 for weathering steel; Type 1 for painted or galvanized steel.
- ⑥ Delete panel for CIP slab.
- ⑦ Total drain length is equal to 9" + maximum girder and haunch + slab thickness, rounded UP to the next whole inch.

Alternate details for Type B barrier (SBC):







### PLAN OF SLAB SHOWING SLAB DRAIN LOCATIONS




PART SECTION NEAR DRAIN




ELEVATION OF DRAIN



PART PLAN OF SLAB AT DRAIN



### PLAN OF STEEL DRAIN OPTION



PLAN OF FRP DRAIN OPTION

General Notes:

Contractor shall have the option to construct either steel or FRP slab drains. All drains shall be of same type.

Locate drains in slab by dimensions shown in Part Section Near Drain.

Reinforcing steel shall be shifted to clear drains.

Shop drawings will not be required for the slab drains.

Notes for Steel Drain:

Slab drains may be fabricated of either 1/4" welded sheets of ASTM A709 Grade 36 steel or from 1/4" structural steel tubing ASTM A500 or A501.

Outside dimensions of drains are 8" x 4".

The drains shall be galvanized in accordance with ASTM A123.

Notes for FRP Drain:

Drains shall be machine filament-wound thermosetting resin tubing meeting the requirements of ASTM D2996 with the following exceptions:

Shape of drains shall be rectangular with outside nominal dimensions of 8" x 4".


Minimum reinforced wall thickness shall be 1/4 inch.

The resin used shall be ultraviolet (UV) resistant and/or have UV inhibitors mixed throughout. Drains may have an exterior coating for additional UV resistance.

The color of the slab drain shall be gray (Federal Standard 26373). The color shall be uniform throughout the resin and any coating used.

The combination of materials used in the manufacture of the drains shall be tested for UV resistance in accordance with ASTM D4329 Cycle A. The representative material shall withstand at least 500 hours of testing with only minor discoloration and without any physical deterioration. The contractor shall furnish the results of the required ultraviolet testing prior to acceptance of the slab drains.


At the contractor's option, drains may be field cut. The method of cutting FRP slab drain shall be as recommended by the manufacturer to ensure a smooth, chip free cut.

<div>  <div> <div>MISSOURI HIGHWAYS AND TRANSPORTATION</div> <div>COMMISSION</div> </div> <div> <div>105 WEST CAPITAL</div> <div>JEFFERSON CITY, MO 65102</div> <div>1-888-ASK-MODOT (1-888-275-6636)</div> </div> </div>		DATE	DESCRIPTION
<div> <div>DATE PREPARED</div> <div>10/17/2023</div> </div>			
<div> <div>ROUTE</div> <div>STATE</div> </div>			
<div> <div>DISTRICT</div> <div>SHEET NO.</div> </div>			
<div>COUNTY</div>			
<div>JOB NO.</div>			
<div>CONTRACT ID.</div>			
<div>PROJECT NO.</div>			
<div>BRIDGE NO.</div>			


Standard Drawing Guidance (do not show on plans):

- ① Replace example Plan of Slab Showing Slab Drain Locations with actual plan.
- ② Details shown inside the sheet border are for drains transverse to roadway. Use the below details for drains parallel to roadway.


Alternate details for Type B barrier (SBC):




PART PLAN OF SLAB AT DRAIN




PART PLAN OF SLAB AT DRAIN




ELEVATION OF DRAIN




PLAN OF STEEL DRAIN OPTION




PART PLAN OF SLAB AT DRAIN




PLAN OF FRP DRAIN OPTION




PLAN OF SLAB SHOWING SLAB DRAIN LOCATIONS



PART SECTION NEAR DRAIN




PART SECTION SHOWING BRACKET ASSEMBLY




PART PLAN OF SLAB AT DRAIN


SLAB DRAINS



ELEVATION OF DRAIN



PLAN OF STEEL DRAIN OPTION



PLAN OF FRP DRAIN OPTION

General Notes:

Contractor shall have the option to construct either steel or FRP slab drains. All drains shall be of same type.

Slab drain bracket assembly shall be ASTM A709 Grade 36 steel.

Locate drains in slab by dimensions shown in Part Section Near Drain.

Reinforcing steel shall be shifted to clear drains.

The coil inserts and bracket assembly shall be galvanized in accordance with ASTM A123.

All bolts, hardened washers, lock washers and nuts shall be galvanized in accordance with AASHTO M 232 (ASTM A153), Class C.

All 1/2"Ø bolts shall be ASTM A307.

Shop drawings will not be required for the slab drains and the bracket assembly.

The coil insert required for the bracket assembly attachment shall be located on the prestressed girder shop drawings.

Coil inserts shall have a concrete pull-out strength (ultimate load) of at least 2,500 pounds in 5,000 psi concrete.

The bolt required to attach the slab drain bracket assembly to the prestressed girder web shall be supplied by the prestressed girder fabricator.

Notes for Steel Drain:

Slab drains may be fabricated of either 1/4" welded sheets of ASTM A709 Grade 36 steel or from 1/4" structural steel tubing ASTM A500 or A501.

Outside dimensions of drains are 8" x 4".

The drains shall be galvanized in accordance with ASTM A123.

Notes for FRP Drain:

Drains shall be machine filament-wound thermosetting resin tubing meeting the requirements of ASTM D2996 with the following exceptions:

Shape of drains shall be rectangular with outside nominal dimensions of 8" x 4".

Minimum reinforced wall thickness shall be 1/4 inch.

The resin used shall be ultraviolet (UV) resistant and/or have UV inhibitors mixed throughout. Drains may have an exterior coating for additional UV resistance.

The color of the slab drain shall be gray (Federal Standard 26373). The color shall be uniform throughout the resin and any coating used.

The combination of materials used in the manufacture of the drains shall be tested for UV resistance in accordance with ASTM D4329 Cycle A. The representative material shall withstand at least 500 hours of testing with only minor discoloration and without any physical deterioration. The contractor shall furnish the results of the required ultraviolet testing prior to acceptance of the slab drains.

At the contractor's option, drains may be field cut. The method of cutting FRP slab drain shall be as recommended by the manufacturer to ensure a smooth, chip free cut.

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 5

COUNTY
JOB NO.
CONTRACT ID.
PROJECT NO.
BRIDGE NO.

DESCRIPTION
DATE


MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)













Standard Drawing Guidance (do not show on plans):

- ① Replace example Plan of Slab Showing Slab Drain Locations with actual plan.
- ② Details shown inside the sheet border are for drains transverse to roadway requiring a cantilever of at least 2'-9 1/2" for Type 2, 3 & 4 and at least 3'-3" for Type 6. Use the below details for drains parallel to roadway requiring a cantilever of at least 2'-5 1/2" for Type 2, 3 & 4 and at least 2'-11" for Type 6.
- ③ Details shown inside the sheet border are for Type 2, 3 & 4 girders. Use the below left details for Type 6 girders.
- ④ Delete panel for CIP slab.
- ⑤ Total drain length is equal to 9" + maximum girder and haunch + slab thickness, rounded UP to the next whole inch.




### Alternate details for Type B barrier (SBC):







### PLAN OF SLAB SHOWING SLAB DRAIN LOCATIONS




PART SECTION NEAR DRAIN




PART SECTION SHOWING BRACKET ASSEMBLY




PART PLAN OF SLAB AT DRAIN



ELEVATION OF DRAIN



### PLAN OF STEEL DRAIN OPTION



PLAN OF FRP DRAIN OPTION

General Notes:

Contractor shall have the option to construct either steel or FRP slab drains. All drains shall be of same type.

Slab drain bracket assembly shall be ASTM A709 Grade 36 steel.

Locate drains in slab by dimensions shown in Part Section Near Drain.

Reinforcing steel shall be shifted to clear drains.

The coil inserts and bracket assembly shall be galvanized in accordance with ASTM A123.

All bolts, hardened washers, lock washers and nuts shall be galvanized in accordance with AASHTO M 232 (ASTM A153), Class C.

All 1/2"Ø bolts shall be ASTM A307.

Shop drawings will not be required for the slab drains and the bracket assembly.

The coil insert required for the bracket assembly attachment shall be located on the prestressed girder shop drawings.

Coil inserts shall have a concrete pull-out strength (ultimate load) of at least 2,500 pounds in 5,000 psi concrete.

The bolt required to attach the slab drain bracket assembly to the prestressed girder web shall be supplied by the prestressed girder fabricator.

Notes for Steel Drain:

Slab drains may be fabricated of either 1/4" welded sheets of ASTM A709 Grade 36 steel or from 1/4" structural steel tubing ASTM A500 or A501.

Outside dimensions of drains are 8" x 4".

The drains shall be galvanized in accordance with ASTM A123.

Notes for FRP Drain:

Drains shall be machine filament-wound thermosetting resin tubing meeting the requirements of ASTM D2996 with the following exceptions:

Shape of drains shall be rectangular with outside nominal dimensions of 8" x 4".


Minimum reinforced wall thickness shall be 1/4 inch.

The resin used shall be ultraviolet (UV) resistant and/or have UV inhibitors mixed throughout. Drains may have an exterior coating for additional UV resistance.

The color of the slab drain shall be gray (Federal Standard 26373). The color shall be uniform throughout the resin and any coating used.

The combination of materials used in the manufacture of the drains shall be tested for resistance in accordance with ASTM D4329 Type A. The representative material shall withstand at least 500 hours of testing with only minor discoloration and without any physical deterioration. The contractor shall furnish the results of the required ultraviolet testing prior to acceptance of the slab drains.


At the contractor's option, drains may be field cut. The method of cutting FRP slab drain shall be as recommended by the manufacturer to ensure a smooth, chip free cut.

DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 6
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
 <p>105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)</p>	


Standard Drawing Guidance (do not show on plans):

- ① Replace example Plan of Slab Showing Slab Drain Locations with actual plan.
- ② Details shown inside the sheet border are for drains transverse to roadway requiring a cantilever 4 feet or more. Use the below details for drains parallel to roadway requiring a cantilever 3'-8" or more.
- ③ Delete panels for CIP slab.
- ④ Total drain length is equal to 9" + maximum girder and haunch + slab thickness, rounded UP to the next whole inch.

Alternate details for Type B barrier (SBC):



PART PLAN OF SLAB AT DRAIN



PART PLAN OF SLAB AT DRAIN

Angle (1/4" min. - 1/2" max. thickness) (3" min. legs) x 2" long

9/16"Ø Holes for 1/2"Ø bolt with lock washer and nut (Typ.)

Drain

Bent Strip 10 Gage (Min.) x 2"

L2x2x1/4"

9/16" Slot in L2x2x1/4"

1/2" (Min.)

9/16"Ø Hole in angle for 1/2"Ø bolt with 2 hardened washers, lock washer, and nut

Prestressed Girder Web

Coil Insert & 9/16"Ø Hole for 1/2"Ø bolt with lock washer

PART SECTION SHOWING BRACKET ASSEMBLY

4"

4 1/2"

1 1/2"

Bottom of Roadway Slab

4"

ELEVATION OF DRAIN

8"

4"

1/2"Ø x 3" Rod (ASTM A709 Grade 36) or 1/2"Ø x 3"± Shear Connector (Typ.)

PLAN OF STEEL DRAIN OPTION

8" (Nom.)

4" (Nom.)

1/2"Ø x 3" Galv. Carriage Bolt with Hex Nut and Lock Washer (Typ.)

PLAN OF FRP DRAIN OPTION


2"

Drain


Inside Face of Barrier

Roadway Traffic


PART PLAN OF SLAB AT DRAIN




### PLAN OF SLAB SHOWING SLAB DRAIN LOCATIONS




PART SECTION NEAR DRAIN




PART SECTION SHOWING BRACKET ASSEMBLY




PART PLAN OF SLAB AT DRAIN



ELEVATION OF DRAIN



### PLAN OF STEEL DRAIN OPTION



PLAN OF FRP DRAIN OPTION

General Notes:

Contractor shall have the option to construct either steel or FRP slab drains. All drains shall be of same type.

Slab drain bracket assembly shall be ASTM A709 Grade 36 steel.

Locate drains in slab by dimensions shown in Part Section Near Drain.

Reinforcing steel shall be shifted to clear drains.

The coil inserts and bracket assembly shall be galvanized in accordance with ASTM A123.

All bolts, hardened washers, lock washers and nuts shall be galvanized in accordance with AASHTO M 232 (ASTM A153), Class C.

All 1/2"Ø bolts shall be ASTM A307.

Shop drawings will not be required for the slab drains and the bracket assembly.

The coil insert required for the bracket assembly attachment shall be located on the prestressed girder shop drawings.

Coil inserts shall have a concrete pull-out strength (ultimate load) of at least 2,500 pounds in 5,000 psi concrete.

The bolt required to attach the slab drain bracket assembly to the prestressed girder web shall be supplied by the prestressed girder fabricator.

Notes for Steel Drain:

Slab drains may be fabricated of either 1/4" welded sheets of ASTM A709 Grade 36 steel or from 1/4" structural steel tubing ASTM A500 or A501.

Outside dimensions of drains are 8" x 4".

The drains shall be galvanized in accordance with ASTM A123.

Notes for FRP Drain:

Drains shall be machine filament-wound thermosetting resin tubing meeting the requirements of ASTM D2996 with the following exceptions:

Shape of drains shall be rectangular with outside nominal dimensions of 8" x 4".

Minimum reinforced wall thickness shall be 1/4 inch.

The resin used shall be ultraviolet (UV) resistant and/or have UV inhibitors mixed throughout. Drains may have an exterior coating for additional UV resistance.

The color of the slab drain shall be gray (Federal Standard 26373). The color shall be uniform throughout the resin and any coating used.

The combination of materials used in the manufacture of the drains shall be tested for UV resistance in accordance with ASTM D4329 Cycle A. The representative material shall withstand at least 500 hours of testing with only minor discoloration and without any physical deterioration. The contractor shall furnish the results of the required ultraviolet testing prior to acceptance of the slab drains.

At the contractor's option, drains may be field cut. The method of cutting FRP slab drain shall be as recommended by the manufacturer to ensure a smooth, chip free cut.

Both upper and lower drain pieces shall be rigidly connected to each other. Drain flow shall not be obstructed. Approval of the engineer is required.

DATE PREPARED	
10/17/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	7
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	


[illegible]MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)



Alternate details for Type B barrier (SBC):

Standard Drawing Guidance (do not show on plans):

- ① Replace example Plan of Slab Showing Slab Drain Locations with actual plan.
- ② Details shown inside the sheet border are for drains transverse to roadway requiring a cantilever 3'-9 1/2" or more. Use the below details for drains parallel to roadway requiring a cantilever 3'-3 3/4" or more.
- ③ Delete panel for CIP slab.
- ④ Total drain length is equal to 9" + maximum girder and haunch + slab thickness, rounded UP to the next whole inch.



PART PLAN OF SLAB AT DRAIN



PART PLAN OF SLAB AT DRAIN

Angle (1/4" min. - 1/2" max. thickness) (3" min. legs) x 2" long

⌀ 9/16"Ø Holes for 1/2"Ø bolt with lock washer and nut (Typ.)

Drain

Bent Strip 10 Gage (Min.) x 2"

L2x2x1/4"

9/16" Slot in L2x2x1/4"

1/2" (Min.)

⌀ 9/16"Ø Hole in angle for 1/2"Ø bolt with 2 hardened washers, lock washer, and nut

Prestressed Girder Web

⌀ Coil Insert & 9/16"Ø Hole for 1/2"Ø bolt with lock washer

PART SECTION SHOWING BRACKET ASSEMBLY

5 5/8"

1 1/2"

4 1/2"

9"

⌀ Drain

4"

60°

1

1

X'-X"

④

ELEVATION OF DRAIN

Typ.

1/2"Ø x 3" Rod (ASTM A709 Grade 36) or 1/2"Ø x 3"± Shear Connector (Typ.)

8"

4"

5 5/8"

PLAN OF STEEL DRAIN OPTION

Lower Piece

1/2"Ø x 3" Galv. Carriage Bolt with Hex Nut and Lock Washer (Typ.)

Upper Piece


8" (Nom.)

4" (Nom.)


5 5/8" (Nom.)

PLAN OF FRP DRAIN OPTION


②




PART PLAN OF SLAB AT DRAIN




### PLAN OF SLAB SHOWING SLAB DRAIN LOCATIONS




PART SECTION NEAR DRAIN




PART SECTION SHOWING BRACKET ASSEMBLY




PART PLAN OF SLAB AT DRAIN



ELEVATION OF DRAIN



### PLAN OF STEEL DRAIN OPTION



### PLAN OF FRP DRAIN OPTION

General Notes:

Contractor shall have the option to construct either steel or FRP slab drains. All drains shall be of same type.

Slab drain bracket assembly shall be ASTM A709 Grade 36 steel.

Locate drains in slab by dimensions shown in Part Section Near Drain.

Reinforcing steel shall be shifted to clear drains.

The coil inserts and bracket assembly shall be galvanized in accordance with ASTM A123.

All bolts, hardened washers, lock washers and nuts shall be galvanized in accordance with AASHTO M 232 (ASTM A153), Class C.

All 1/2"Ø bolts shall be ASTM A307.

Shop drawings will not be required for the slab drains and the bracket assembly.

The coil inserts required for the bracket assembly attachment shall be located on the prestressed beam shop drawings.

Coil inserts shall have a concrete pull-out strength (ultimate load) of at least 2,500 pounds in 5,000 psi concrete.

The bolts required to attach the slab drain bracket assembly to the prestressed beam shall be supplied by the prestressed beam fabricator.

Notes for Steel Drain:

Slab drains may be fabricated of either 1/4" welded sheets of ASTM A709 Grade 36 steel or from 1/4" structural steel tubing ASTM A500 or A501.

Outside dimensions of drains are 8" x 4".

The drains shall be galvanized in accordance with ASTM A123.

Notes for FRP Drain:

Drains shall be machine filament-wound thermosetting resin tubing meeting the requirements of ASTM D2996 with the following exceptions:

Shape of drains shall be rectangular with outside nominal dimensions of 8" x 4".

Minimum reinforced wall thickness shall be 1/4 inch.


The resin used shall be ultraviolet (UV) resistant and/or have UV inhibitors mixed throughout. Drains may have an exterior coating for additional UV resistance.

The color of the slab drain shall be gray (Federal Standard 26373). The color shall be uniform throughout the resin and any coating used.

The combination of materials used in the manufacture of the drains shall be tested for UV resistance in accordance with ASTM D4329 Cycle A. The representative material shall withstand at least 500 hours of testing with only minor discoloration and without any physical deterioration. The contractor shall furnish the results of the required ultraviolet testing prior to acceptance of the slab drains.

At the contractor's option, drains may be field cut. The method of cutting FRP slab drain shall be as recommended by the manufacturer to ensure a smooth, chip free cut.

DATE PREPARED	
10/17/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	8
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	

[illegible]


MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)


Standard Drawing Guidance (do not show on plans):

- ① Replace example Plan of Slab Showing Slab Drain Locations with actual plan.  
Verify slab drain does not block vent pipe in box beam.
- ② Details shown inside the sheet border are for drains transverse to roadway requiring a cantilever 4'-3" or more. Use the below details for drains parallel to roadway requiring a cantilever 3'-11" or more.
- ③ Use half of the beam depth.
- ④ Beam manufacturer determines required distance between inserts with coordination between contractor and drain supplier.


Alternate details for Type B barrier (SBC):




PART PLAN OF SLAB AT DRAIN




PART PLAN OF SLAB AT DRAIN




PART SECTION SHOWING BRACKET ASSEMBLY




PART PLAN OF SLAB AT DRAIN



ELEVATION OF DRAIN




### PLAN OF STEEL DRAIN OPTION




PLAN OF FRP DRAIN OPTION







PLAN OF SLAB SHOWING SLAB DRAIN LOCATIONS



PART SECTION NEAR DRAIN




PART SECTION SHOWING BRACKET ASSEMBLY




PART PLAN OF SLAB AT DRAIN


SLAB DRAINS



ELEVATION OF DRAIN



PLAN OF STEEL DRAIN OPTION



PLAN OF FRP DRAIN OPTION

General Notes:

Contractor shall have the option to construct either steel or FRP slab drains. All drains shall be of same type.

Slab drain bracket assembly shall be ASTM A709 Grade 36 steel.

Locate drains in slab by dimensions shown in Part Section Near Drain.

Reinforcing steel shall be shifted to clear drains.

The coil inserts and bracket assembly shall be galvanized in accordance with ASTM A123.

All bolts, hardened washers, lock washers and nuts shall be galvanized in accordance with AASHTO M 232 (ASTM A153), Class C.

All 1/2"Ø bolts shall be ASTM A307.

Shop drawings will not be required for the slab drains and the bracket assembly.

The coil inserts required for the bracket assembly attachment shall be located on the prestressed beam shop drawings.

Coil inserts shall have a concrete pull-out strength (ultimate load) of at least 2,500 pounds in 5,000 psi concrete.

The bolts required to attach the slab drain bracket assembly to the prestressed beam shall be supplied by the prestressed beam fabricator.

Notes for Steel Drain:

Slab drains may be fabricated of either 1/4" welded sheets of ASTM A709 Grade 36 steel or from 1/4" structural steel tubing ASTM A500 or A501.

Outside dimensions of drains are 8" x 4".

The drains shall be galvanized in accordance with ASTM A123.

Notes for FRP Drain:

Drains shall be machine filament-wound thermosetting resin tubing meeting the requirements of ASTM D2996 with the following exceptions:

Shape of drains shall be rectangular with outside nominal dimensions of 8" x 4".

Minimum reinforced wall thickness shall be 1/4 inch.

The resin used shall be ultraviolet (UV) resistant and/or have UV inhibitors mixed throughout. Drains may have an exterior coating for additional UV resistance.

The color of the slab drain shall be gray (Federal Standard 26373). The color shall be uniform throughout the resin and any coating used.

The combination of materials used in the manufacture of the drains shall be tested for UV resistance in accordance with ASTM D4329 Cycle A. The representative material shall withstand at least 500 hours of testing with only minor discoloration and without any physical deterioration. The contractor shall furnish the results of the required ultraviolet testing prior to acceptance of the slab drains.

At the contractor's option, drains may be field cut. The method of cutting FRP slab drain shall be as recommended by the manufacturer to ensure a smooth, chip free cut.

Both upper and lower drain pieces shall be rigidly connected to each other. Drain flow shall not be obstructed. Approval of the engineer is required.

DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 9

COUNTY
JOB NO.
CONTRACT ID.
PROJECT NO.
BRIDGE NO.

DESCRIPTION
DATE


MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)




Standard Drawing Guidance (do not show on plans):

- ① Replace example Plan of Slab Showing Slab Drain Locations with actual plan.  
Verify slab drain does not block vent pipe in box beam.
- ② Details shown inside the sheet border are for drains transverse to roadway requiring a cantilever 3'-9 3/8" or more. Use the below details for drains parallel to roadway requiring a cantilever 3'-3 5/8" or more.
- ③ Use half of the beam depth.
- ④ Beam manufacturer determines required distance between inserts with coordination between contractor and drain supplier.


Alternate details for Type B barrier (SBC):




PART PLAN OF SLAB AT DRAIN




PART PLAN OF SLAB AT DRAIN







PLAN OF SLAB SHOWING SLAB DRAIN LOCATIONS




PART SECTION NEAR DRAIN




PART SECTION SHOWING BRACKET ASSEMBLY




PART PLAN OF SLAB AT DRAIN



ELEVATION OF DRAIN



### PLAN OF STEEL DRAIN OPTION



PLAN OF FRP DRAIN OPTION

General Notes:

Contractor shall have the option to construct either steel or FRP slab drains. All drains shall be of same type.

Slab drain bracket assembly shall be ASTM A709 Grade 36 steel.

Locate drains in slab by dimensions shown in Part Section Near Drain.

Reinforcing steel shall be shifted to clear drains.

The bracket assembly shall be galvanized in accordance with ASTM A123.

All bolts, hardened washers, lock washers and nuts shall be galvanized in accordance with AASHTO M 232 (ASTM A153), Class C, except as shown. (E)

All 1/2"Ø bolts shall be ASTM A307, except as shown.

Shop drawings will not be required for the slab drains and the bracket assembly.

The bolt hole for the bracket assembly attachment shall be shifted to the minimum extent necessary to field drill in the existing web.

(1) See front sheet for slab thickness.

The galvanized surfaces of drain support brackets shall be prepared according to the coating manufacturer's recommendation and field coated with a gray epoxy-mastic primer (non-aluminum) within a distance of 6 inches from the point of connection to the weathering steel structure.

Notes for Steel Drain:

Slab drains may be fabricated of either 1/4" welded sheets of ASTM A709 Grade 36 steel or from 1/4" structural steel tubing ASTM A500 or A501.

Outside dimensions of drains are 8" x 4".

The drains shall be galvanized in accordance with ASTM A123.

Notes for FRP Drain:

Drains shall be machine filament-wound thermosetting resin tubing meeting the requirements of ASTM D2996 with the following exceptions:

Shape of drains shall be rectangular with outside nominal dimensions of 8" x 4".

Minimum reinforced wall thickness shall be 1/4 inch.

The resin used shall be ultraviolet (UV) resistant and/or have UV inhibitors mixed throughout. Drains may have an exterior coating for additional UV resistance.

The color of the slab drain shall be gray (Federal Standard 26373). The color shall be uniform throughout the resin and any coating used.

The combination of materials used in the manufacture of the drains shall be tested for ultraviolet resistance in accordance with ASTM D4329 Cycle A. The representative material shall withstand at least 500 hours of testing with only minor discoloration and without any physical deterioration. The contractor shall furnish the results of the required ultraviolet testing prior to acceptance of the slab drains.


At the contractor's option, drains may be field cut. The method of cutting FRP slab drain shall be recommended by the manufacturer to ensure a smooth, chip free cut.

[illegible]



Standard Drawing Guidance (do not show on plans):

- ① Replace example Plan of Slab Showing Slab Drain Locations with actual plan.
- ② Details shown inside the sheet border are for drains transverse to roadway. Use the below details for drains parallel to roadway.
- ③ Use  $\frac{1}{6}$  of web depth.
- ④ For slab thickness less than  $7 \frac{3}{4}$ ", revise dimension to be equal to the slab thickness minus  $3 \frac{1}{4}$ ".
- ⑤ Type 3 for weathering steel; Type 1 for painted or galvanized steel.
- ⑥ Use with weathering steel. Delete for painted or galvanized steel.
- ⑦ Total drain length is equal to  $9"$  + maximum girder and haunch + slab thickness, rounded UP to the next whole inch.


### Alternate details for Type B barrier (SBC):



PART PLAN OF SLAB AT DRAIN




PART PLAN OF SLAB AT DRAIN




PART SECTION SHOWING BRACKET ASSEMBLY


\* See Sec 1080.4 (6)




PART PLAN OF SLAB AT DRAIN




ELEVATION OF DRAIN



### PLAN OF STEEL DRAIN OPTION




PLAN OF FRP DRAIN OPTION




1




5



DETAIL A



DETAIL B



SLAB CONSTRUCTION JOINT

Notes:

7 For details of precast prestressed panels, see Sheet No. .

For reinforcement of barrier not shown, see Sheet No. .

For Theoretical Bottom of Slab Elevations, Girder Camber Diagram and Theoretical Slab Haunching Diagram, see Sheet No. .


For Plan of Slab Showing Reinforcement, see Sheet No. .

SLAB DETAILS

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 000
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-273-6636)	

Standard Drawing Guidance  
(do not show on plans):

- ① Remove if not required.
- ② Use the following values for clearance to top longitudinal bars:

3<sup>1</sup>/<sub>8</sub>" for #5 bars

3" for #6 bars

2<sup>7</sup>/<sub>8</sub>" for #7 bars

2<sup>3</sup>/<sub>4</sub>" for #8 bars

Use a triple asterisk when there are different size top bars and add below the single asterisk note the following (modified as needed)(this will be the only astrisk note for CIP decks):

\*\*\* 3<sup>1</sup>/<sub>8</sub>" (#5)


3" (#6)

2<sup>7</sup>/<sub>8</sub>" (#7)


2<sup>3</sup>/<sub>4</sub>" (#8)

Clearance values based on the #6 top transverse bar used for this standard slab. Values will need to be revised for other size transverse bars.

- ③ The larger negative moment reinforcement shown is grouped and can be deleted if the negative moment steel is the same size as the distribution reinforcement. A set of bars the same size as the distribution bars exist behind the larger bars shown, and will become visible when the larger bars are deleted. (No need to resize)
- ④ The subheadings and negative moment bars are grouped and can be deleted for single span bridges.  
<Ctrl> U to ungroup
- ⑤ Place appropriate slab pouring sequence cell and modify as required.
- ⑥ Use alternate detail for CIP decks:




OPTIONAL SHIFTING  
TOP BARS AT BARRIER



Alternate detail for  
Type H barrier

For 8" thick slabs, change top dimension to 3 1/4" and center dimension to 2 1/2".



SLAB CONSTRUCTION JOINT

- ⑦ Remove for CIP deck


Girder spacing and reinforcement size & spacing shown are not necessarily standard. Follow design.

SLAB01\_24ft\_symm


Guidance & Alternate Details (2 of 3)

4-Beam Panel Deck



Plate Girder





4-Beam CIP Deck



Type 2,3,4



Type 6






SLAB01\_24ft\_symm      Guidance & Alternate Details (3 of 3)  
3-Beam Panel Deck


Bulb-Tee

NU


Box




\* Alternate bar shape available, see barrier sheet.




SECTION THRU SLAB




\* Alternate bar shape available, see barrier sheet.




SECTION THRU SLAB




\* Alternate bar shape available, see barrier sheet.




SECTION THRU SLAB




OPTIONAL SHIFTING  
TOP BARS AT BARRIER




DETAIL A



DETAIL B



FULL DEPTH SLAB



SLAB ON PANELS

SLAB CONSTRUCTION JOINT

Notes:

For details of precast prestressed panels, see Sheet No. .

For reinforcement of barrier not shown, see Sheet No. .

For Theoretical Bottom of Slab Elevations, Girder Camber Diagram and Theoretical Slab Haunching Diagram, see Sheet No. .

For Plan of Slab Showing Reinforcement, see Sheet No. .

## SLAB DETAILS

Sheet No.      of

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

DATE PREPARED	
10/17/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	2
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	

[illegible]MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

SLAB02\_26ft\_symm

Guidance & Alternate Details (1 of 3)

Standard Drawing Guidance  
(do not show on plans):

- ① Remove if not required.
- ② Use the following values for clearance to top longitudinal bars:

3 1⁄8" for #5 bars

3" for #6 bars

2 7⁄8" for #7 bars


2 3⁄4" for #8 bars

Use a triple asterisk when there are different size top bars and add below the single asterisk note the following (modified as needed)(this will be the only astrisk note for CIP decks):


\*\*\* 3 1⁄8" (#5)  
3" (#6)  
2 7⁄8" (#7)  
2 3⁄4" (#8)

Clearance values based on the #6 top transverse bar used for this standard slab. Values will need to be revised for other size transverse bars.

- ③ The larger negative moment reinforcement shown is grouped and can be deleted if the negative moment steel is the same size as the distribution reinforcement. A set of bars the same size as the distribution bars exist behind the larger bars shown, and will become visible when the larger bars are deleted. (No need to resize)
- ④ The subheadings and negative moment bars are grouped and can be deleted for single span bridges. <Ctrl> U to ungroup
- ⑤ Place appropriate slab pouring sequence cell and modify as required.
- ⑥ Use alternate detail for CIP decks:




OPTIONAL SHIFTING  
TOP BARS AT BARRIER



Alternate detail for  
Type H barrier

For 8" thick slabs, change top dimension to 3 1/4" and center dimension to 2 1/2".




SLAB CONSTRUCTION JOINT

- ⑦ Remove for CIP deck


Girder spacing and reinforcement size & spacing shown are not necessarily standard. Follow design.

## Plate Girder




\* Alternate bar shape available, see barrier sheet.

Type 2, 3, 4




\* Alternate bar shape available, see barrier sheet.

Type 6




\* Alternate bar shape available, see barrier sheet.


## 4-Beam CIP Deck



SECTION THRU SLAB





SECTION THRU SLAB





SECTION THRU SLAB


Bulb-Tee





NU




Box






DETAIL A



DETAIL B



SLAB CONSTRUCTION JOINT

Notes:

7 For details of precast prestressed panels, see Sheet No. .

For reinforcement of barrier not shown, see Sheet No. .

For Theoretical Bottom of Slab Elevations, Girder Camber Diagram and Theoretical Slab Haunching Diagram, see Sheet No. .

For Plan of Slab Showing Reinforcement, see Sheet No. .

SLAB DETAILS

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

DATE PREPARED		10/17/2023	
ROUTE	STATE	MO	
DISTRICT	SHEET NO.	3	
COUNTY			
JOB NO.			
CONTRACT ID.			
PROJECT NO.			
BRIDGE NO.			
DESCRIPTION			
DATE			
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION		105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-273-6636)	

SLAB03\_28ft\_symm

Guidance & Alternate Details (1 of 4)

Standard Drawing Guidance  
(do not show on plans):

- ① Remove if not required.
- ② Use the following values for clearance to top longitudinal bars:

3<sup>1</sup>/<sub>8</sub>" for #5 bars

3" for #6 bars

2<sup>7</sup>/<sub>8</sub>" for #7 bars


2<sup>3</sup>/<sub>4</sub>" for #8 bars

Use a triple asterisk when there are different size top bars and add below the single asterisk note the following (modified as needed)(this will be the only astrisk note for CIP decks):


\*\*\* 3<sup>1</sup>/<sub>8</sub>" (#5)  
3" (#6)  
2<sup>7</sup>/<sub>8</sub>" (#7)  
2<sup>3</sup>/<sub>4</sub>" (#8)

Clearance values based on the #6 top transverse bar used for this standard slab. Values will need to be revised for other size transverse bars.

- ③ The larger negative moment reinforcement shown is grouped and can be deleted if the negative moment steel is the same size as the distribution reinforcement. A set of bars the same size as the distribution bars exist behind the larger bars shown, and will become visible when the larger bars are deleted. (No need to resize)
- ④ The subheadings and negative moment bars are grouped and can be deleted for single span bridges. <Ctrl> U to ungroup
- ⑤ Place appropriate slab pouring sequence cell and modify as required.
- ⑥ Use alternate detail for CIP decks:




OPTIONAL SHIFTING  
TOP BARS AT BARRIER



Alternate detail for  
Type H barrier

For 8" thick slabs, change top dimension to 3 1/4" and center dimension to 2 1/2".



SLAB CONSTRUCTION JOINT


- ⑦ Remove for CIP deck

Girder spacing and reinforcement size & spacing shown are not necessarily standard. Follow design.




SLAB03\_28ft\_symm      Guidance & Alternate Details (2 of 4)  
4-Beam Panel Deck



Plate Girder





4-Beam CIP Deck



Type 2,3,4




Type 6




SLAB03_28ft_symm		Guidance & Alternate Details (3 of 4)	
		4-Beam Panel Deck	
Bulb-TEE			
NU			
Box			


SLAB03_28ft_symm		Guidance & Alternate Details (4 of 4)	
		3-Beam Panel Deck	
Bulb-Tee			
NU			
Box			




OPTIONAL SHIFTING  
TOP BARS AT BARRIER



DETAIL A



DETAIL B



## SLAB CONSTRUCTION JOINT

Notes:

For details of precast prestressed panels, see Sheet No.

For reinforcement of barrier not shown, see Sheet No. .

For Theoretical Bottom of Slab Elevations, Girder Camber Diagram and Theoretical Slab Haunching Diagram, see Sheet No. .

For Plan of Slab Showing Reinforcement, see Sheet No. .

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

## SLAB DETAILS

Sheet No.      of

DATE PREPARED	
10/17/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	4
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	

[illegible]MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

Standard Drawing Guidance  
(do not show on plans):

- ① Remove if not required.
- ② Use the following values for clearance to top longitudinal bars:

3<sup>1</sup>/<sub>8</sub>" for #5 bars

3" for #6 bars

2<sup>7</sup>/<sub>8</sub>" for #7 bars


2<sup>3</sup>/<sub>4</sub>" for #8 bars

Use a triple asterisk when there are different size top bars and add below the single asterisk note the following (modified as needed)(this will be the only astrisk note for CIP decks):


\*\*\* 3<sup>1</sup>/<sub>8</sub>" (#5)  
3" (#6)  
2<sup>7</sup>/<sub>8</sub>" (#7)  
2<sup>3</sup>/<sub>4</sub>" (#8)

Clearance values based on the #6 top transverse bar used for this standard slab. Values will need to be revised for other size transverse bars.

- ③ The larger negative moment reinforcement shown is grouped and can be deleted if the negative moment steel is the same size as the distribution reinforcement. A set of bars the same size as the distribution bars exist behind the larger bars shown, and will become visible when the larger bars are deleted. (No need to resize)
- ④ The subheadings and negative moment bars are grouped and can be deleted for single span bridges. <Ctrl> U to ungroup
- ⑤ Place appropriate slab pouring sequence cell and modify as required.
- ⑥ Use alternate detail for CIP decks:




OPTIONAL SHIFTING TOP BARS AT BARRIER



Alternate detail for Type H barrier

For 8" thick slabs, change top dimension to 3 1/4" and center dimension to 2 1/2".




SLAB CONSTRUCTION JOINT

- ⑦ Remove for CIP deck


Girder spacing and reinforcement size & spacing shown are not necessarily standard. Follow design.

SLAB04\_30ft\_symm      Guidance & Alternate Details (2 of 3)  
4-Beam Panel Deck



Plate Girder





4-Beam CIP Deck



Type 2,3,4




Type 6






SLAB04\_30ft\_symm      Guidance & Alternate Details (3 of 3)  
4-Beam Panel Deck



Bulb-Tee





4-Beam CIP Deck




NU



Box








DETAIL A

DETAIL B

Contractor may shift or swap bars as needed to tie R3 bar in barrier (4" min. bar spacing)

Contractor may shift bar as needed to tie R2 bar in barrier

OPTIONAL SHIFTING  
TOP BARS AT BARRIER



## SLAB CONSTRUCTION JOINT

Notes :

For details of precast prestressed panels, see Sheet No.

For reinforcement of barrier not shown, see Sheet No. .

For Theoretical Bottom of Slab Elevations, Girder Camber Diagram and Theoretical Slab Haunching Diagram, see Sheet No. .

For Plan of Slab Showing Reinforcement, see Sheet No. .

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

## SLAB DETAILS

Sheet No.      of

DATE PREPARED	
10/17/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	5

JOB NO.

CONTRACT ID.

PROJECT NO.

BRIDGE NO.

[illegible]MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

Standard Drawing Guidance  
(do not show on plans):

- ① Remove if not required.
- ② Use the following values for clearance to top longitudinal bars:

3<sup>1</sup>/<sub>8</sub>" for #5 bars

3" for #6 bars

2<sup>7</sup>/<sub>8</sub>" for #7 bars


2<sup>3</sup>/<sub>4</sub>" for #8 bars

Use a triple asterisk when there are different size top bars and add below the single asterisk note the following (modified as needed)(this will be the only astrisk note for CIP decks):


\*\*\* 3<sup>1</sup>/<sub>8</sub>" (#5)  
3" (#6)  
2<sup>7</sup>/<sub>8</sub>" (#7)  
2<sup>3</sup>/<sub>4</sub>" (#8)

Clearance values based on the #6 top transverse bar used for this standard slab. Values will need to be revised for other size transverse bars.

- ③ The larger negative moment reinforcement shown is grouped and can be deleted if the negative moment steel is the same size as the distribution reinforcement. A set of bars the same size as the distribution bars exist behind the larger bars shown, and will become visible when the larger bars are deleted. (No need to resize)
- ④ The subheadings and negative moment bars are grouped and can be deleted for single span bridges. <Ctrl> U to ungroup
- ⑤ Place appropriate slab pouring sequence cell and modify as required.
- ⑥ Use alternate detail for CIP decks:




OPTIONAL SHIFTING  
TOP BARS AT BARRIER



Alternate detail for  
Type H barrier

For 8" thick slabs, change top dimension to 3 1/4" and center dimension to 2 1/2".




SLAB CONSTRUCTION JOINT

- ⑦ Remove for CIP deck


Girder spacing and reinforcement size & spacing shown are not necessarily standard. Follow design.

SLAB05\_32ft\_symm      Guidance & Alternate Details (2 of 3)  
4-Beam Panel Deck



Plate Girder





4-Beam CIP Deck



Type 2,3,4









Type 6



SLAB05\_32ft\_symm

Guidance & Alternate Details (3 of 3)

4-Beam Panel Deck





Standard Drawing Guidance  
(do not show on plans):

- ① Remove if not required.
- ② Use the following values for clearance to top longitudinal bars:

3<sup>1</sup>/<sub>8</sub>" for #5 bars

3" for #6 bars

2<sup>7</sup>/<sub>8</sub>" for #7 bars


2<sup>3</sup>/<sub>4</sub>" for #8 bars

Use a triple asterisk when there are different size top bars and add below the single asterisk note the following (modified as needed)(this will be the only astrisk note for CIP decks):


\*\*\* 3<sup>1</sup>/<sub>8</sub>" (#5)  
3" (#6)  
2<sup>7</sup>/<sub>8</sub>" (#7)  
2<sup>3</sup>/<sub>4</sub>" (#8)

Clearance values based on the #6 top transverse bar used for this standard slab. Values will need to be revised for other size transverse bars.

- ③ The larger negative moment reinforcement shown is grouped and can be deleted if the negative moment steel is the same size as the distribution reinforcement. A set of bars the same size as the distribution bars exist behind the larger bars shown, and will become visible when the larger bars are deleted. (No need to resize)
- ④ The subheadings and negative moment bars are grouped and can be deleted for single span bridges. <Ctrl> U to ungroup
- ⑤ Place appropriate slab pouring sequence cell and modify as required.
- ⑥ Use alternate detail for CIP decks:



OPTIONAL SHIFTING  
TOP BARS AT BARRIER



Alternate detail for  
Type H barrier

For 8" thick slabs, change top dimension to 3 1/4" and center dimension to 2 1/2".

Finish each side of joint with 1/4" radius edging tool


Key to extend full width of slab

Const. Jt.

SLAB CONSTRUCTION JOINT


- ⑦ Remove for CIP deck

Girder spacing and reinforcement size & spacing shown are not necessarily standard. Follow design.








Bulb-Tee





CIP Deck




NU



Box






Contractor may shift or swap bars as needed to tie R3 bar in barrier (4" min. bar spacing)

Contractor may shift bar as needed to tie R2 bar in barrier

### OPTIONAL SHIFTING TOP BARS AT BARRIER



Notes:

For details of precast prestressed panels, see Sheet No. .

For reinforcement of barrier not shown, see Sheet No. .

For Theoretical Bottom of Slab Elevations, Girder Camber Diagram and Theoretical Slab Haunching Diagram, see Sheet No. .

For Plan of Slab Showing Reinforcement, see Sheet No. .


## SLAB DETAILS

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No.      of

DATE PREPARED	
10/17/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	7
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	

[illegible]

MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

Standard Drawing Guidance  
(do not show on plans):

- ① Remove if not required.
- ② Use the following values for clearance to top longitudinal bars:

3<sup>1</sup>/<sub>8</sub>" for #5 bars

3" for #6 bars

2<sup>7</sup>/<sub>8</sub>" for #7 bars

2<sup>3</sup>/<sub>4</sub>" for #8 bars

Use a triple asterisk when there are different size top bars and add below the single asterisk note the following (modified as needed)(this will be the only astrisk note for CIP decks):

\*\*\* 3<sup>1</sup>/<sub>8</sub>" (#5)

3" (#6)

2<sup>7</sup>/<sub>8</sub>" (#7)

2<sup>3</sup>/<sub>4</sub>" (#8)
- Clearance values based on the #6 top transverse bar used for this standard slab. Values will need to be revised for other size transverse bars.
- ③ The larger negative moment reinforcement shown is grouped and can be deleted if the negative moment steel is the same size as the distribution reinforcement. A set of bars the same size as the distribution bars exist behind the larger bars shown, and will become visible when the larger bars are deleted. (No need to resize)


④ The subheadings and negative moment bars are grouped and can be deleted for single span bridges. <Ctrl> U to ungroup

⑤ Place appropriate slab pouring sequence cell and modify as required.


⑥ Use alternate detail for CIP decks:
- 
- OPTIONAL SHIFTING  
TOP BARS AT BARRIER
- 
- Alternate detail for  
Type H barrier
- For 8" thick slabs, change top dimension to 3 1/4" and center dimension to 2 1/2".
- Finish each side of joint with 1/4" radius edging tool
- Key to extend full width of slab

Const. Jt.
- SLAB CONSTRUCTION JOINT
- ⑦ Remove for CIP deck
- Girder spacing and reinforcement size & spacing shown are not necessarily standard. Follow design.



Plate Girder





CIP Deck









Type 2,3,4



Type 6



Panel Deck





Standard Drawing Guidance  
(do not show on plans):

- ① Remove if not required.
- ② Use the following values for clearance to top longitudinal bars:

3<sup>1</sup>/<sub>8</sub>" for #5 bars

3" for #6 bars

2<sup>7</sup>/<sub>8</sub>" for #7 bars


2<sup>3</sup>/<sub>4</sub>" for #8 bars

Use a triple asterisk when there are different size top bars and add below the single asterisk note the following (modified as needed)(this will be the only astrisk note for CIP decks):


\*\*\* 3<sup>1</sup>/<sub>8</sub>" (#5)  
3" (#6)  
2<sup>7</sup>/<sub>8</sub>" (#7)  
2<sup>3</sup>/<sub>4</sub>" (#8)

Clearance values based on the #6 top transverse bar used for this standard slab. Values will need to be revised for other size transverse bars.

- ③ The larger negative moment reinforcement shown is grouped and can be deleted if the negative moment steel is the same size as the distribution reinforcement. A set of bars the same size as the distribution bars exist behind the larger bars shown, and will become visible when the larger bars are deleted. (No need to resize)
- ④ The subheadings and negative moment bars are grouped and can be deleted for single span bridges. <Ctrl> U to ungroup
- ⑤ Place appropriate slab pouring sequence cell and modify as required.
- ⑥ Use alternate detail for CIP decks:




OPTIONAL SHIFTING  
TOP BARS AT BARRIER



Alternate detail for  
Type H barrier

For 8" thick slabs, change top dimension to 3 1/4" and center dimension to 2 1/2".



SLAB CONSTRUCTION JOINT


- ⑦ Remove for CIP deck

Girder spacing and reinforcement size & spacing shown are not necessarily standard. Follow design.




Panel Deck



Plate Girder





CIP Deck



Type 2,3,4




Type 6




Panel Deck



Bulb-Tee





CIP Deck





NU




Box






DETAIL A



DETAIL B



Notes:

For details of precast prestressed panels, see Sheet No. .


For reinforcement of barrier not shown, see Sheet No. .

For Theoretical Bottom of Slab Elevations, Girder Camber Diagram and Theoretical Slab Haunching Diagram, see Sheet No. .

For Plan of Slab Showing Reinforcement, see Sheet No. .

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 9
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-273-6636)	

SLAB09\_40ft\_symm

Guidance & Alternate Details (1 of 3)

Standard Drawing Guidance  
(do not show on plans):

- ①

Remove if not required.
- ②

Use the following values for clearance to top longitudinal bars:  
3<sup>1</sup>/<sub>8</sub>" for #5 bars  
  
3" for #6 bars  
  
2<sup>7</sup>/<sub>8</sub>" for #7 bars  
  
2<sup>3</sup>/<sub>4</sub>" for #8 bars  
Use a triple asterisk when there are different size top bars and add below the single asterisk note the following (modified as needed)(this will be the only astrisk note for CIP decks):  

\*\*\*

3<sup>1</sup>/<sub>8</sub>" (#5)

3" (#6)

2<sup>7</sup>/<sub>8</sub>" (#7)


2<sup>3</sup>/<sub>4</sub>" (#8)
- ③

The larger negative moment reinforcement shown is grouped and can be deleted if the negative moment steel is the same size as the distribution reinforcement. A set of bars the same size as the distribution bars exist behind the larger bars shown, and will become visible when the larger bars are deleted. (No need to resize)
- ④


The subheadings and negative moment bars are grouped and can be deleted for single span bridges. <Ctrl> U to ungroup
- ⑤

Place appropriate slab pouring sequence cell and modify as required.
- ⑥

Use alternate detail for CIP decks:




OPTIONAL SHIFTING  
TOP BARS AT BARRIER



Alternate detail for  
Type H barrier

For 8" thick slabs, change top dimension to 3 1/4" and center dimension to 2 1/2".



SLAB CONSTRUCTION JOINT

- ⑦

Remove for CIP deck


Girder spacing and reinforcement size & spacing shown are not necessarily standard. Follow design.

SLAB09\_40ft\_symm


Guidance & Alternate Details (2 of 3)

Panel Deck



Plate Girder





CIP Deck



Type 2,3,4












Type 6



SLAB09\_40ft\_symm      Guidance & Alternate Details (3 of 3)

Panel Deck





Notes:

- ⑦ For details of precast prestressed panels, see Sheet No. .  
 For reinforcement of barrier not shown, see Sheet No. .  
 For Theoretical Bottom of Slab Elevations, Girder Camber Diagram and Theoretical Slab Haunching Diagram, see Sheet No. .  
 For Plan of Slab Showing Reinforcement, see Sheet No. .

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

SLAB DETAILS  
Sheet No.      of

[illegible]




Standard Drawing Guidance  
(do not show on plans):

- ① Remove if not required.
- ② Use the following values for clearance to top longitudinal bars:  
3 1⁄8" for #5 bars  
  
3" for #6 bars  
  
2 7⁄8" for #7 bars  
  
2 3⁄4" for #8 bars  
Use a triple asterisk when there are different size top bars and add below the single asterisk note the following (modified as needed)(this will be the only astrisk note for CIP decks):


\*\*\* 3 1⁄8" (#5)  
3" (#6)  
2 7⁄8" (#7)  
2 3⁄4" (#8)

Clearance values based on the #6 top transverse bar used for this standard slab. Values will need to be revised for other size transverse bars.

- ③ The larger negative moment reinforcement shown is grouped and can be deleted if the negative moment steel is the same size as the distribution reinforcement. A set of bars the same size as the distribution bars exist behind the larger bars shown, and will become visible when the larger bars are deleted. (No need to resize)
- ④ The subheadings and negative moment bars are grouped and can be deleted for single span bridges. <Ctrl> U to ungroup
- ⑤ Place appropriate slab pouring sequence cell and modify as required.
- ⑥ Use alternate detail for CIP decks:




OPTIONAL SHIFTING  
TOP BARS AT BARRIER



Alternate detail for  
Type H barrier

For 8" thick slabs, change top dimension to 3 1⁄4" and center dimension to 2 1⁄2".

Finish each side of joint with 1⁄4" radius edging tool



SLAB CONSTRUCTION JOINT


- ⑦ Remove for CIP deck

Girder spacing and reinforcement size & spacing shown are not necessarily standard. Follow design.


SLAB10_44ft_symm		Guidance & Alternate Details (2 of 3)	
		Panel Deck	
Plate Girder			
Type 2,3,4			
Type 6			

Panel Deck



Bulb-Tee





CIP Deck



NU



Box





STRIP01\_psi\_end      Guidance & Alternate Details

Standard Drawing Guidance (do not show on plans):

Modify drawing as necessary.

Remove non-applicable rows in table.


Ⓐ Piece angle length to center of first slotted hole.

Ⓑ Use squared, left advanced or right advanced Part Plan as needed.


Ⓒ = 3/4" (Min.) @ 60°. Verify only.

Ⓓ = Ⓐ @ 60° + 1/2" upper lips + 3/4" (Min.) Verify only.


Ⓔ Remove precast panel for CIP slab.



PART SECTION B-B




Alternate details  
for Type B barrier (SBC)



PART PLAN

Left Advanced



PART PLAN

Right Advanced




STRIP02\_psi\_int      Guidance & Alternate Details

Standard Drawing Guidance (do not show on plans):


Modify drawing as necessary.

Remove non-applicable rows in table.


- Ⓐ Piece angle length to center of first slotted hole.
- Ⓑ Use squared, left advanced or right advanced Part Plan as needed.
- Ⓒ = 3/4" (Min.) @ 60° Verify only.
- Ⓓ = ① @ 60°+ 1/2" upper lips + 3/4" (Min.) Verify only.
- Ⓔ Remove precast panel for CIP slab.



Alternate details  
for Type B barrier (SBC)



Left Advanced



Right Advanced






STRIP03\_stl\_end      Guidance & Alternate Details


Standard Drawing Guidance (do not show on plans):  
Modify drawing as necessary.  
Remove non-applicable rows in table.

- Ⓐ Dimension to clear bearing stiffener (1 1/2" Min.). For rehab bridge, dimension should be based on shop drawing or field check.
- Ⓑ Use 3". For rehab bridge, dimension should be based on shop drawing or field check.
- Ⓒ Use squared, left advanced or right advanced Part Plan as needed.
- Ⓓ = 3/4" (Min.) @ 60° Verify only.
- Ⓔ = ① @ 60° + 1/2" upper lips + 3/4" (Min.) Verify only.
- Ⓕ = Use 6" long angle. For rehab bridge, modify angle length based on shop drawing or field check.
- Ⓖ Delete precast panel for CIP slab.




PART SECTION THRU EXPANSION JOINT IN SLAB CANTILEVER

Include this detail on redecks & rehabs when slab thickness is less than 8".  
If slab thickness + haunch to bear is less than 8" within the girder bays, a shorter armor may be used.




PART SECTION B-B




PART ELEVATION OF BARRIER

Strip seal gland not shown for clarity.


Alternate details for Type B barrier (SBC)



PART PLAN  
Left Advanced




PART PLAN  
Right Advanced




SECTION A-A


Strip seal gland not shown for clarity.

PART ELEVATION  
OF BARRIER


Strip seal gland  
not shown for clarity.





PART SECTION B-B




### DETAIL OF JOINT ARMOR



DETAIL OF GLAND



DETAIL A



DETAIL B

## STRIP SEAL EXPANSION JOINT SYSTEM AT INTERMEDIATE BENT NO.

GENERAL NOTES:

Expansion joint system shall be fabricated in one section, except for staged construction and when the length is over 50 feet. A complete joint penetration groove welded splice shall be required. Welds shall be ground flush to provide a smooth surface. The expansion joint system shall be fabricated and installed to the crown and grade of the roadway.

The strip seal gland shall be installed in joints in one continuous piece without field splices. Factory splicing will be permitted for joints in excess of 53 feet.

Structural steel for the expansion joint system shall be ASTM A709 Grade 36 except the steel armor may be ASTM A709 Grade 50W. Anchors for the expansion joint system shall be in accordance with Sec 1037. Strip seal expansion joint system shall be in accordance with Sec 717.

Structural steel for the expansion joint system shall be coated with a minimum of two coats of inorganic zinc primer to provide a total dry film thickness of 4 mils minimum, 6 mils maximum, or galvanized in accordance with ASTM A123. Anchors need not be protected from overspray.

Longitudinal reinforcing steel shall be placed so that ends shall be 1" from the vertical leg of the steel armor at the expansion joint system.

Concrete shall be forced under and around steel armor and anchors. Proper consolidation of the concrete shall be achieved by localized internal vibration.

② The installation temperature shall be taken as the actual air temperature averaged over the 24-hour period immediately preceding installation.

③ MoDOT Construction personnel will indicate the strip seal expansion joint system installed.

Steel armor may also be referred to as extrusion or rail.


### Table of Allowed Transverse Strip Seal Expansion Joint System

[illegible]


STRIP04\_stl\_int      Guidance & Alternate Details

Standard Drawing Guidance (do not show on plans):  
Modify drawing as necessary.  
Remove non-applicable rows in table.


- Ⓐ Dimension to clear bearing stiffener (1 1/2" Min.). For rehab bridge, dimension should be based on shop drawing or field check.
- Ⓑ Use 3". For rehab bridge, dimension should be based on shop drawing or field check.
- Ⓒ Use squared, left advanced or right advanced Part Plan as needed.
- Ⓓ = 3/4" (Min.) @ 60° Verify only.
- Ⓔ = Ⓐ @ 60° + 1/2" upper lips + 3/4" (Min.) Verify only.
- Ⓕ = Use 6" long angle. For rehab bridge, modify angle length based on shop drawing or field check.
- Ⓖ Delete precast panel for CIP slab.




Alternate details  
for Type B barrier (SBC)



Left Advanced




Right Advanced




SECTION A-A

Strip seal gland not shown for clarity.


\* Dimension along C Girder




PART PLAN




DETAIL A




DETAIL B

PART ELEVATION  
OF BARRIER


Strip seal gland not shown for clarity.




PART SECTION B-B



DETAIL C



### DETAIL OF GLAND



### DETAIL OF JOINT ARMOR

GENERAL NOTES:

Expansion joint system shall be fabricated in one section, except for staged construction and when the length is over 50 feet. A complete joint penetration groove welded splice shall be required. Welds shall be ground flush to provide a smooth surface. The expansion joint system shall be fabricated and installed to the crown and grade of the roadway.

The strip seal gland shall be installed in joints in one continuous piece without field splices. Factory splicing will be permitted for joints in excess of 53 feet.

Structural steel for the expansion joint system shall be ASTM A709 Grade 36 except the steel armor may be ASTM A709 Grade 50W. Anchors for the expansion joint system shall be in accordance with Sec 1037. Strip seal expansion joint system shall be in accordance with Sec 717.

Structural steel for the expansion joint system shall be coated with a minimum of two coats of inorganic zinc primer to provide a total dry film thickness of 4 mils minimum, 6 mils maximum, or galvanized in accordance with ASTM A123. Anchors need not be protected from overspray.

Longitudinal reinforcing steel shall be placed so that ends shall be 1" from the vertical leg of the steel armor at the expansion joint system.

Concrete shall be forced under and around steel armor and anchors. Proper consolidation of the concrete shall be achieved by localized internal vibration.

② The installation temperature shall be taken as the actual air temperature averaged over the 24-hour period immediately preceding installation.

③ MoDOT Construction personnel will indicate the strip seal expansion joint system installed.

Steel armor may also be referred to as extrusion or rail.

Table of Allowed Transverse Strip Seal Expansion Joint System									
Manufacturer	Strip Seal System (Designated Name)	Movement Parallel to RDWY	Allowed Installation Gap ① Normal to Joint at RDWY Surface @ Air/Surface Temperature ②						③
			@ 40°F	@ 50°F	@ 60°F	@ 70°F	@ 80°F	@ 90°F	
D S Brown	Strip seal L2-400	XXX	XXX	XXX	XXX	XXX	XXX	XXX	<input type="checkbox"/>
D S Brown	Strip seal L2-500	XXX	XXX	XXX	XXX	XXX	XXX	XXX	<input type="checkbox"/>
Watson Bowman Acme (Wabo)	Strip seal SE-300	XXX	XXX	XXX	XXX	XXX	XXX	XXX	<input type="checkbox"/>
Watson Bowman Acme (Wabo)	Strip seal SE-400	XXX	XXX	XXX	XXX	XXX	XXX	XXX	<input type="checkbox"/>
Watson Bowman Acme (Wabo)	Strip seal SE-500	XXX	XXX	XXX	XXX	XXX	XXX	XXX	<input type="checkbox"/>




STRIP05\_stl-psi      Guidance & Alternate Details

Standard Drawing Guidance (do not show on plans):



Modify drawing as necessary.

Remove non-applicable rows in table.


- (A) Piece angle length to center of first slotted hole.
- (B) Dimension to clear bearing stiffener (1 1/2" Min.). For rehab bridge, dimension should be based on shop drawing or field check.
- (C) Use 3". For rehab bridge, dimension should be based on shop drawing or field check.
- (D) Use Square, Right Advanced or Left Advanced Part Plan as needed.
- (E) 3/4" (Min.) @ 60° Verify only.
- (F) ① @ 60°+ 1/2" upper lips + 2 x 3/4" (Min.) Verify only.
- (G) Use 6" long angle. For rehab bridge, modify angle length based on shop drawing or field check.
- (H) Delete precast panel for CIP slab.



Alternate details  
for Type B barrier (SBC)



( 4 @ 40' ) PREFABRICATED SIMPLE SEGMENTED WIDE FLANG BEAM SPANS



⊕ Indicates location of borings.

Notice and Disclaimer Regarding Boring Log Data

The locations of all subsurface borings for this structure are shown on the plan sheet(s) for this structure. The boring data for all locations indicated, as well as any other boring logs or other factual records of subsurface data and investigations performed by the department for the design of the project, are shown on Sheet(s) No. \_\_\_\_\_ and may be included in the Electronic Bridge Deliverables. They will also be available from the Project Contact upon written request. No greater significance or weight should be given to the boring data depicted on the plan sheets than is given to the subsurface data available from the district or elsewhere.

The Commission does not represent or warrant that any such boring data accurately depicts the conditions to be encountered in constructing this project. A contractor assumes all risks it may encounter in basing its bid prices, time or schedule of performance on the boring data depicted here or those available from the district, or on any other documentation not expressly warranted, which the contractor may obtain from the Commission.

Foundation Data						
Type	Design Data	Bent Number				
		1	2	3	4	5
Load Bearing Pile	Pile Type and Size	HP 14x73	HP 14x73	HP 14x73	HP 14x73	HP 14x73
	Number	7	4	4	4	7
	Approximate Length Per Each	ft	*	*	*	*
	Pile Driving Verification Method	DF	DF	DF	DF	DF
	Design Bearing	kip	22	38	38	38
	Min. Hammer Energy Required	ft-lb	*	*	*	*

All piling shall be driven to a minimum nominal axial compressive resistance equal to 3.5 times the Design Bearing as shown on the plans.

Estimated Quantities		
Item		Total
Structural Steel Pile (14 in.)	linear foot	X
* Fabricated Structural Carbon Steel (Misc.)	pound	1
Partial Furnishing of Superstructure	lump sum	1
Transporting and Erecting Superstructure	lump sum	1
Removing and Storing Superstructure	lump sum	1

\* Furnishing and installing sway bracing at intermediate bents.

Standard Drawing Guidance (do not show on plans: Remove the boring data notes if does not apply.

General Notes

Design Specifications:  
2002 AASHTO LFD (17th Ed.) Standard Specifications  
Seismic Performance Category =  
Acceleration Coefficient =

Design Loading:  
H20-44  
Earth 120 lb/cf, Equivalent Fluid Pressure 45 lb/cf (Min.)

Design Unit Stresses:  
Structural Steel (ASTM A709 Grade 50W) fy = 50,000 psi  
Structural Steel (ASTM A709 Grade 36) fy = 36,000 psi  
Steel Pile (ASTM A709 Grade 50) fy = 50,000 psi  
Structural Steel Tubing (ASTM A500) fy = 46,000 psi

Timber:  
All timber shall be standard rough sawn. At the contractor's option, timber may be untreated or protected with commercially applied timber preservatives. All timber shall have a minimum strength of 1500 psi and shall be either douglas fir in accordance with paragraph 123B (MC-19), 124B (MC-19) and 1308B of the current edition of Standard Grading Rules for West Coast Lumber, southern pine in accordance with paragraphs 312 (MC-19), 342 (MC-19) and 405.1 of the current edition of Southern Pine Inspection Bureau Grading Rules, or a satisfactory grade of sound native oak.

Bolts:  
All bolts shall be ASTM F3125 Grade A325 Type 3, except as noted.

All ASTM A307 bolts and their accompanying hex nuts and washers and all ASTM A449 Type 1 studs and their accompanying heavy hex nuts shall be galvanized in accordance with AASHTO M 232 (ASTM A153), Class C.

Structural Steel:  
All structural steel shall be ASTM A709 Grade 50W except piles, sway bracing, thrie beam rail assembly and structural tubing. Structural tubing coating shall be in accordance with Sec 718.

Substructure:  
All substructure items specified in Sec 718.3.1 except for the pile point reinforcement and sway bracing will be considered completely covered by the contract unit price for Structural Steel Piles (14 in.).

Miscellaneous:  
The superstructure only and cap beam units will be provided by the State and shall be transported from Maintenance Lot. The superstructure shall be returned and stored at the same location as designated by the engineer after Bridge No. is open to traffic.

Traffic Handling:  
Traffic to be maintained on existing structure during construction. See roadway plans for traffic control.

SEC/SUR \* TWP \* RGE \*

Hydrologic Data	
Drainage Area =	___ mi <sup>2</sup>
Design Flood Frequency =	___ years
Design Flood Discharge =	___ cfs
Design Flood (D.F.) Elevation =	_____
Base Flood (100-year)	
Base Flood Elevation =	_____
Base Flood Discharge =	___ cfs
Estimated Backwater =	__ ft
Average Velocity thru Opening =	__ ft/s
Freeboard (50-year)	
Freeboard =	__ ft
Roadway Overtopping	
Overtopping Flood Discharge =	___ cfs
Overtopping Flood Frequency =	___ years
_____ Flood Elevation =	_____

B.M.

BRIDGE: ROUTE \* OVER \*

ROUTE \* FROM \* TO \*  
ABOUT \* MILES \* OF \*  
BEGINNING STA. \_\_\_\_\_

Designed  
Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. 1 of

DESCRIPTION

DATE

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION





105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-273-6636)
















The size of base and bottom plate may be increased depending on which grid option is used.

See preceding sheet for post spacing.






- (1) Optional welding of the post to the base plate, in lieu of the weld shown, is a 5/16-inch fillet weld all around, including the edges of the post flanges.
- (2) Required on one side only, but may be provided on both sides of web at contractor's option.

- (2) Required on one side only, but may be provided on both sides of web at contractor's option.



Bottom plate shall be fabricated from ASTM A709 Grade 50W steel and shall be welded to two 5-inch floor bars. Bottom plate shall not be galvanized.



General Notes:

Design Specification: 2002 - AASHTO 17th Edition

Guardrail delineators shall be attached to the top of the bridge guardrail and shall similarly use the delineator details of Missouri Standard Plan 617.10, except that the delineator body shall be attached to the top of the cap rail using galvanized anchorage as shown on Missouri Standard Plan 606.00. Delineators on bridges with two-lane, two-way traffic shall have retroreflective sheeting on both sides. Cost of supplying and installing new delineators will be considered completely covered by other pay items. Delineators shall be stored with bridge guardrail after use.

Panel lengths of channel members shall be attached continuously to a minimum of four posts and a maximum of six posts (except at end bents).

All bolts, nuts, washers and plates will be considered completely covered by the contract unit price for other items.

All steel connecting bolts and fasteners for posts and railing, and all bolts, nuts, washers and plates shall be galvanized after fabrication except for bottom plate. Protective coating and material requirement of steel railing shall be in accordance with Sec 1040.

Rail posts shall be set perpendicular to roadway profile grade vertically in cross section and aligned in accordance with Sec 713 except that the rail posts shall be aligned by the use of 3 x 1 3/4-inch shims such that the post deviates not more than 1/2 inch from true horizontal alignment after final adjustment. The shims shall be placed between the post and the three beam rail. The thickness of the shims shall be determined by the contractor and verified by the engineer before ordering material for this work.

At the expansion slots in the three beam rails and channels, the bolts shall be tightened and backed off one-half turn and the threads shall be burred.

At the thrie beam connection to posts on wings, the bolts shall be tightened and backed off one-half turn and the threads shall be burred.

Minimum length of thrie beam sections is equal to one post space.

A 5/8-inch diameter button head, oval shoulder bolt with a minimum 3/8-inch thick hex nut shall be used at all slots.

Three beam guardrail on the bridge shall be 12 gage steel.

Posts, top plates, base plates, channels and channel splice plates shall be fabricated from ASTM A709 Grade 36 steel and galvanized.

Flat washers, 3 x 1 3/4 x 3/16-inch minimum, shall be used at all post bolts between the bolt head and beam. The washers shall be rectangular in shape with an 11/16 x 1-inch slot, or when necessary of such design as to fit the contour of the beam. Rectangular Washer, 3 x 1 3/4 x 5/8-inch, shall be used between the post and the thrie beam rail.

Special drilling of the thrie beam may be required at the splices. All drilling details shall be shown on the shop drawings.

Fabrication of structural steel shall be accordance with Sec 1080.

If Type A guardrail is not attached to ends of the temporary structure, flared ends shall be required. The existing thrie beam rails shall be modified to accept flared ends. Cost for furnishing and installing flared ends will be considered completely covered by the contract unit price for other items.

Contractor shall verify all dimensions in field before ordering materials.

At the bridge ends for head to head traffic, guardrail shall be used at all four corners and for single directional traffic, guardrail shall be used at the entrance ends only unless required at the exit.

DATE PREPARED	
10/17/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	4
COUNTY	

JOB NO.
CONTRACT ID.
PROJECT NO.
BRIDGE NO.

[illegible]MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION



105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)


















For Elevation C-C see Sheet No. \_\_\_\_.

See slab sheet for rail post spacing.

- (2) Required on one side of web only, but may be provided on both sides of web at the contractor's option.
- (3) Two Resin Anchor Systems each with a minimum ultimate pullout strength of 72 kip in  $f'c = 4,000$  psi concrete and each to include:
  - 1 1/8"Ø (Min.) Drilled Hole in slab or as recommended by manufacturer
  - 1 1/4"Ø Hole in post plate and inside post flange
  - 1"Ø ASTM A449 Type 1 Threaded Rod snug tight and embedded 12 inches in slab
  - Hex Nut and 2 1/2"Ø Hardened Locking Washer
- (4) Two Resin Anchor Systems each with a minimum ultimate pullout strength of 20.4 kip in  $f'c = 4,000$  psi concrete and each to include:
  - 7/8"Ø (Min.) Drilled Hole in slab or as recommended by manufacturer
  - 1"Ø Hole in post plate and inside post flange
  - 3/4"Ø ASTM A449 Type 1 Threaded Rod snug tight and embedded 8 inches in slab
  - Hex Nut and Hardened Locking Washer



See Missouri Standard Plan 606.00 for details not shown.



General Notes:

Design Specifications: 2002 AASHTO LFD (17th Ed.)  
Standard Specifications

Guardrail delineators shall be attached to the top of the guardrail and shall similarly use the delineator details of Missouri Standard Plan 617.10, except that the delineator body shall be attached to the top of the cap rail using galvanized anchorage as shown on Missouri Standard Plan 606.00. Delineators on bridges with two-lane, two-way traffic shall have retroreflective sheeting on both sides. Guardrail delineators will be considered completely covered by the contract unit price for Bridge Guardrail (Thrie Beam).

Panel lengths of channel members shall be attached continuously to a minimum of four posts and a maximum of six posts (except at end bents).

All bolts, nuts, washers and plates will be considered completely covered by the contract unit price for Bridge Guardrail (Thrie Beam).

All steel connecting bolts and fasteners for posts and railing, and all resin anchor bolts, nuts, washers and plates shall be galvanized after fabrication. Protective coating and material requirement of steel railing shall be in accordance with Sec 1040.

Rail posts shall be set perpendicular to roadway profile grade, vertically in cross section and aligned in accordance with Sec 713 except that the rail posts shall be aligned by the use of 3 x 1 3/4-inch shims such that the post deviates not more than 1/2 inch from true horizontal alignment after final adjustment. The shims shall be placed between the blockout and the thrie beam rail. The thickness of the shims shall be determined by the contractor and verified by the engineer before ordering material for this work.

At the expansion slots in the three beam rails and channels, the bolts shall be tightened and backed off one-half turn and the threads shall be burred.

At the thrie beam connection to blockout on wings, the bolts shall be tightened and backed off one-half turn and the threads shall be burred.

Minimum length of thrie beam sections is equal to one post space.

A 5/8-inch diameter button-head, oval shoulder bolt with a minimum 3/8-inch thick hex nut shall be used at all slots.

Three beam guardrail on the bridge shall be 12-gauge steel.

Posts, cap rail angles, post plates, blockouts, channels and channel splice plates shall be fabricated from ASTM A709 Grade 36 steel and galvanized.

Flat washers 3 x 1 3/4 x 3/16-inch minimum shall be used at all post bolts between the bolt head and beam. The washers shall be rectangular in shape with an 11/16 x 1-inch slot, or when necessary of such design as to fit the contour of the beam. Rectangular washers 3 x 1 3/4 x 5/8-inch shall be used between the blockout and the thrie beam rail.

Special drilling of the thrie beam may be required at the splices. All drilling details shall be shown on the shop drawings.

Fabrication of structural steel shall be in accordance with Sec 1080.

Expansion splices in the three beam rail shall be made at either the first or second post on either side of the joint and on structure at bridge ends. When the splice is made at the second post, an expansion slot shall be provided in the three beam rail for connection to the first post to allow for movement.

In addition to the expansion provisions at the expansion joints, expansion splices in the three beam rail and the channel shall be provided at other locations so that the maximum length without expansion provisions does not exceed 200 feet.

Shim plates 6 x 6 x 1/16-inch may be used between the top of the post and the channel member as required for vertical alignment.

Shim plates shall be galvanized after fabrication.

Contractor shall verify all dimensions in field before ordering materials.

Outline of existing work is indicated by light dashed lines. Heavy lines indicate new work.

DATE PREPARED	
10/17/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	4
COUNTY	

	JOB NO.
--	---------

CONTRACT ID.
--------------

PROJECT NO.
-------------

BRIDGE NO.[illegible]MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)



THRIE2a\_system2\_rehab

Guidance

Standard Drawing Guidance (do not show on plans):


This system meets NCHRP 350 TL-3 bridge railing requirements.

Max. post spacing = 6'-3"


Design weight of 12-gauge thrie beam bridge rail equals 35 lb/lf.

- ① For 22 thru 31-inch voided slab depth, use 10 inches from top of original slab plus overlay depth. For 20-inch voided slab depth, reduce to 8 inches plus overlay depth.
- ② Remove and show total of 2'-6<sup>5</sup>/<sub>8</sub>" plus overlay depth; give total depth of slab plus overlay depth.





### ELEVATION OF THRIE BEAM RAIL




PART SECTION AT RAIL POST


For Section C-C see Sheet No. .

See slab sheet for rail post spacing.


- (1) Required on one side of web only, but may be provided on both sides of web at the contractor's option.
- (2) **POST-TO-BENT PLATE CONNECTION**
  - ☐ Two 1"Ø ASTM F3125 Grade A325 Type 1 Bolts with hardened washers and hex nuts
  - ☐ Two 1 1/16" x 1 1/2" Vertical Slotted Holes in both upper post flanges
  - ☐ Two 1 1/16"Ø Holes in washer plate, inside lower post flange and both bent plates
- (3) **BENT PLATE-TO-DECK CONNECTION**
  - ☐ Three 1 1/8"Ø Drilled Holes in slab
  - ☐ Three 1"Ø ASTM A307 Bolts with plate washer, hardened locking washers and hex nuts
  - ☐ Three 1 1/4"Ø Holes in both bent plates




### DETAIL A




DETAIL B



SECTION B-B



SECTION THRU THRIE BEAM RAIL



THREE BEAM RAIL SPLICE

General Notes:

Design Specifications: 2002 AASHTO LFD (17th Ed.)  
Standard Specifications

Guardrail delineators shall be attached to the top of the guardrail and shall similarly use the delineator details of Missouri Standard Plan 617.10, except that the delineator body shall be attached to the top of the cap rail using galvanized anchorage as shown on Missouri Standard Plan 606.00. Delineators on bridges with two-lane, two-way traffic shall have retroreflective sheeting on both sides. Guardrail delineators will be considered completely covered by the contract unit price for Bridge Guardrail (Thrie Beam).

Panel lengths of channel members shall be attached continuously to a minimum of four posts and a maximum of six posts (except at end bents).

All bolts, nuts, washers and plates will be considered completely covered by the contract unit price for Bridge Guardrail (Thrie Beam).

All steel connecting bolts and fasteners for posts and railing, and all bolts, nuts, washers and plates shall be galvanized after fabrication. Protective coating and material requirement of steel railing shall be in accordance with Sec 1040.

Rail posts shall be set perpendicular to roadway profile grade, vertically in cross section and aligned in accordance with Sec 713 except that the rail posts shall be aligned by the use of 3 x 1 3/4-inch shims such that the post deviates not more than 1/2 inch from true horizontal alignment after final adjustment. The shims shall be placed between the blockout and the three beam rail. The thickness of the shims shall be determined by the contractor and verified by the engineer before ordering material for this work.

At the expansion slots in the three beam rails and channels, the bolts shall be tightened and backed off one-half turn and the threads shall be burred.

At the thrie beam connection to blockout on wings,  
the bolts shall be tightened and backed off one-half  
turn and the threads shall be burred.

Minimum length of three beam sections is equal to one post space.

A 5/8-inch diameter button-head, oval shoulder bolt with a minimum 3/8-inch thick hex nut shall be used at all slots.

Thrie beam guardrail on the bridge shall be 12-guage steel.

Posts, cap rail angles, bent plates, blockouts, channels and channel splice plates shall be fabricated from ASTM A709 Grade 36 steel and galvanized.

Flat washers 3 x 1 3/4 x 3/16-inch minimum shall be used at all post bolts between the bolt head and beam. The washers shall be rectangular in shape with an 11/16 x 1-inch slot, or when necessary of such design as to fit the contour of the beam. Rectangular washers 3 x 1 3/4 x 5/8-inch shall be used between the blockout and the three beam rail.

Special drilling of the thrie beam may be required at the splices. All drilling details shall be shown on the shop drawings.

Fabrication of structural steel shall be in accordance with Sec 1080.

Expansion splices in the thrie beam rail shall be made at either the first or second post on either side of the joint and on structure at bridge ends. When the splice is made at the second post, an expansion slot shall be provided in the thrie beam rail for connection to the first post to allow for movement.

In addition to the expansion provisions at the expansion joints, expansion splices in the three beam rail and the channel shall be provided at other locations so that the maximum length without expansion provisions does not exceed 200 feet.

Shim plates 6 x 6 x 1/16-inch may be used between the top of the post and the channel member as required for vertical alignment.

Shim plates shall be galvanized after fabrication.

Contractor shall verify all dimensions in field before ordering materials.

Outline of existing work is indicated by light dashed lines. Heavy lines indicate new work.

DATE PREPARED	
10/17/2023	
ROUTE	STATE
DISTRICT	SHEET NO.
	6
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	

[illegible]

MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

**MODOT**

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275.6636)

100 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)












Standard Drawing Guidance (do not show on plans):  
This system meets NCHRP 350 TL-3 bridge railing requirements.  
Max. post spacing = 6'-3"  
Design weight of 12-gauge three beam bridge rail equals 35 lb/lf.

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No.      of





General Notes:

Design Specifications: 2002 AASHTO LFD (17th Ed.)  
Standard Specifications

Guardrail delineators shall be attached to the top of the guardrail and shall similarly use the delineator details of Missouri Standard Plan 617.10, except that the delineator body shall be attached to the top of the cap rail using galvanized anchorage as shown on Missouri Standard Plan 606.00. Delineators on bridges with two-lane, two-way traffic shall have retroreflective sheeting on both sides. Guardrail delineators will be considered completely covered by the contract unit price for Bridge Guardrail (Thrie Beam).

Panel lengths of channel members shall be attached continuously to a minimum of four posts and a maximum of six posts (except at end bents).

All bolts, nuts, washers and plates will be considered completely covered by the contract unit price for Bridge Guardrail (Thrie Beam).

All steel connecting bolts and fasteners for posts and railing, and all resin anchor bolts, nuts, washers and plates shall be galvanized after fabrication. Protective coating and material requirement of steel railing shall be in accordance with Sec 1040.

Rail posts shall be set perpendicular to roadway profile grade, vertically in cross section and aligned in accordance with Sec 713 except that the rail posts shall be aligned by the use of 3 x 1 3/4-inch shims such that the post deviates not more than 1/2 inch from true horizontal alignment after final adjustment. The shims shall be placed between the blockout and the three beam rail. The thickness of the shims shall be determined by the contractor and verified by the engineer before ordering material for this work.

At the expansion slots in the three beam rails and channels, the bolts shall be tightened and backed off one-half turn and the threads shall be burred.

At the thrie beam connection to blockout on wings, the bolts shall be tightened and backed off one-half turn and the threads shall be burred.

Minimum length of thrie beam sections is equal to one post space.

A 5/8-inch diameter button-head, oval shoulder bolt with a minimum 3/8-inch thick hex nut shall be used at all slots.

Thrie beam guardrail on the bridge shall be 12-guage steel

Posts, cap rail angles, bent plates, blockouts, channels and channel splice plates shall be fabricated from ASTM A709 Grade 36 steel and galvanized.

Flat washers 3 x 1 3/4 x 3/16-inch minimum shall be used at all post bolts between the bolt head and beam. The washers shall be rectangular in shape with an 11/16 x 1-inch slot, or when necessary of such design as to fit the contour of the beam. Rectangular washers 3 x 1 3/4 x 5/8-inch shall be used between the blockout and the thrie beam rail.

Special drilling of the thrie beam may be required at the splices. All drilling details shall be shown on the shop drawings.

Fabrication of structural steel shall be in accordance with Sec 1080.

Expansion splices in the three beam rail shall be made at either the first or second post on either side of the joint and on structure at bridge ends. When the splice is made at the second post, an expansion slot shall be provided in the three beam rail for connection to the first post to allow for movement.


In addition to the expansion provisions at the expansion joints, expansion splices in the three beam rail and the channel shall be provided at other locations so that the maximum length without expansion provisions does not exceed 200 feet.

Shim plates 6 x 6 x 1/16-inch may be used between the top of the post and the channel member as required for vertical alignment.

Shim plates shall be galvanized after fabrication.

Contractor shall verify all dimensions in field before ordering materials.

Outline of existing work is indicated by light dashed lines. Heavy lines indicate new work.

DATE PREPARED		10/17/2023	
ROUTE		STATE	
		MO	
DISTRICT		SHEET NO.	
		8	
COUNTY			
JOB NO.			
CONTRACT ID.			
PROJECT NO.			
BRIDGE NO.			
DESCRIPTION			
DATE			
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION		 <p>105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)</p>	

THRIE4a\_system4\_rehab

Guidance

Standard Drawing Guidance (do not show on plans):

This system meets NCHRP 350 TL-3 bridge railing requirements.

Max. post spacing = 6'-3"

- ① If slab cantilever length exceeds 6", consideration shall be given to:  
(with the result that anchorage into slab lies in the cantilever part of slab)
- (1) Anchorage into cantilever portion of slab provided original slab thickness allows for min. embedment & 1" cover (check negative moment in cantilever).

(2) Extending bent plate (within reason).

(3) Alternating method of attachment, i.e. System 1 or System 3 types and variations thereof, Consult Structural Project Manager.





THR IE4b\_system4\_details


Guidance

Standard Drawing Guidance (do not show on plans):


① Remove these details when this sheet is used in combination with drawing THR IE 4D, and use 15/16" for diameter of the bottom two holes in the Details of Post.

② Replace with below notes when this sheet is used in combination with drawing THR IE 4D.

- 1"Ø ASTM F3125 Grade A325 Type 1 Bolts with hex nuts and hardened loc washers
- 1 1/8"Ø Drilled Holes in slab
- 1 1/4"Ø Holes in bent plate and bearing plate



PART SECTION THRU PLATE



PLAN OF BENT PLATE


Bar supports shall be Beam Bolsters (BB-ref. CRSI) and shall be galvanized. See Sec 706.



Standard Drawing Guidance (do not show on plans):  
When a latex, low slump or silica fume concrete overlay is used, add these details.

Detailed  
Checked








Note: This drawing is not to scale. Follow dimensions.

Sheet No. of

DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 10
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-273-6636)	



- (1) Required on one side of web only, but may be provided on both sides of web at the contractor's option.
- (2)  $\frac{1}{2}$ " Bent Plate (Level with qualified special motor, see Sec 704)
- (3) Cantilever may vary.
- (4) POST-TO-BENT PLATE CONNECTION
  - $\varnothing$  Two 1"  $\varnothing$  ASTM F3125 Grade A325 Type 1 Bolts with hardened washers and hex nuts
  - $\varnothing$  Two 1  $\frac{1}{16}$ " x 1  $\frac{1}{2}$ " Vertical Slotted Holes in both post flanges
  - $\varnothing$  Two 1  $\frac{1}{16}$ "  $\varnothing$  Holes in washer plate & bent plate
- (5) BENT PLATE-TO-DECK CONNECTION
  - $\varnothing$  Three 1"  $\varnothing$  ASTM F3125 Grade A325 Type 1 Bolts with hex nuts and hardened locking washers
  - $\varnothing$  Three 1  $\frac{1}{4}$ "  $\varnothing$  Holes in bent plate and bearing plate
  - $\varnothing$  Three 1  $\frac{1}{8}$ "  $\varnothing$  (Min.) Drilled Holes in slab
- (6) POST-TO-TIE CONNECTION
  - $\varnothing$  Two 3/4"  $\varnothing$  ASTM F3125 Grade A325 Type 1 Bolts with hex nuts and hardened washers
  - $\varnothing$  Two 15/16"  $\varnothing$  Holes in inside post flange and end plate
- (7) TIE-TO-GIRDER CONNECTION
  - $\varnothing$  Two Resin Anchor Systems each to include:
    - 7/8"  $\varnothing$  (Min.) Drilled Hole in girder or as recommended by manufacturer
    - 1"  $\varnothing$  Hole in end plate
    - 3/4"  $\varnothing$  ASTM A449 Type 1 Threaded Rod snug tight and embedded 5 inches in girder
    - Hex Nut and Hardened Locking Washer



General Notes:

Design Specifications: 2002 AASHTO LFD (17th Ed.)  
Standard Specifications

Guardrail delineators shall be attached to the top of the guardrail and shall similarly use the delineator details of Missouri Standard Plan 617.10, except that the delineator body shall be attached to the top of the cap rail using galvanized anchorage as shown on Missouri Standard Plan 606.00. Delineators on bridges with two-lane, two-way traffic shall have retroreflective sheeting on both sides. Guardrail delineators will be considered completely covered by the contract unit price for Bridge Guardrail (Thrie Beam).

Panel lengths of channel members shall be attached continuously to a minimum of four posts and a maximum of six posts (except at end bents).

All bolts, nuts, washers and plates will be considered completely covered by the contract unit price for Bridge Guardrail (Thrie Beam).

All steel connecting bolts and fasteners for posts and railing, and all resin anchor bolts, nuts, washers and plates shall be galvanized after fabrication. Protective coating and material requirement of steel railing shall be in accordance with Sec 1040.

Rail posts shall be set perpendicular to roadway profile grade, vertically in cross section and aligned in accordance with Sec 713 except that the rail posts shall be aligned by the use of 3 x 1 3/4-inch shims such that the post deviates not more than 1/2 inch from true horizontal alignment after final adjustment. The shims shall be placed between the blockout and the three beam rail. The thickness of the shims shall be determined by the contractor and verified by the engineer before ordering material for this work.

At the expansion slots in the thrie beam rails and channels, the bolts shall be tightened and backed off one-half turn and the threads shall be burred.

At the thrie beam connection to blockout on wings,  
the bolts shall be tightened and backed off one-half  
turn and the threads shall be burred.

Minimum length of thrie beam sections is equal to one post space.

A 5/8-inch diameter button-head, oval shoulder bolt with a minimum 3/8-inch thick hex nut shall be used at all slots.

Three beam guardrail on the bridge shall be 12-gauge steel.

Posts, cap rail angles, bent plates, blockouts, channels and channel splice plates shall be fabricated from ASTM A709 Grade 36 steel and galvanized.

Flat washers 3 x 1 3/4 x 3/16-inch minimum shall be used at all post bolts between the bolt head and beam. The washers shall be rectangular in shape with an 11/16 x 1-inch slot, or when necessary of such design as to fit the contour of the beam. Rectangular washers 3 x 1 3/4 x 5/8-inch shall be used between the blockout and the three beam rail.

Special drilling of the thrie beam may be required at the splices. All drilling details shall be shown on the shop drawings.

Fabrication of structural steel shall be in accordance with Sec 1080.

Expansion splices in the thrie beam rail shall be made at either the first or second post on either side of the joint and on structure at bridge ends. When the splice is made at the second post, an expansion slot shall be provided in the thrie beam rail for connection to the first post to allow for movement.

In addition to the expansion provisions at the expansion joints, expansion splices in the three beam rail and the channel shall be provided at other locations so that the maximum length without expansion provisions does not exceed 200 feet.

Shim plates 6 x 6 x 1/16-inch may be used between the top of the post and the channel member as required for vertical alignment.

Shim plates shall be galvanized after fabrication.

Contractor shall verify all dimensions in field before ordering materials.

See Missouri Standard Plan 606.00 for details not shown.

DATE PREPARED	
10/17/2023	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	11
COUNTY	

JOB NO.
CONTRACT ID.
PROJECT NO.
BRIDGE NO.



[illegible]MISSOURI HIGHWAYS AND TRANSPORTATION  
COMMISSION

105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)

Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No.      of



\* Tack weld same size bar (2'-8" long and centered) as slab longitudinal reinf. Optional to wrap bolt under slab long. reinf. provided that 1" clearance is maintained to bottom of slab.

① Bevel bottom of post (slope 2% or slab cross slope).





**Bridge Rail Notes:**  
Rail posts shall be set perpendicular to roadway profile grade, vertically in cross section and aligned in accordance with Sec 713 except that the rail posts shall be aligned by the use of shims such that the post deviates not more than 1/2 inch from true horizontal alignment after final adjustment. The shims shall be 3" x 1 3/4" and placed between the post and the rail. The thickness of the shims shall be determined by the contractor and verified by the engineer before ordering material for this work.

Rail posts shall be seated on elastomeric pads having the same dimensions as the base plate and 1/16" thickness. Pads may be any elastomeric material, plain or fibered, having a hardness (Durometer) of 50 or greater, and certified by the manufacturer. Additional pads or half pads may be used for shimming for alignment. Post heights shown will increase by the thickness of the pad.

HSS = Hollow Structural Section  
Dimensions of bridge rails are measured horizontally.  
Bridge Rails will be measured to the nearest linear foot for each structure measured from end of slab to end of slab.


Payment for furnishing all materials and labor necessary to install Bridge Rail, complete-in-place, will be considered completely covered by the contract unit price for Bridge Rail (Two Tube Structural Steel) per linear foot.


Guardrail delineators shall be attached to the top of the guardrail post using galvanized anchorage as shown on Missouri Standard Plan 606.00 and in accordance with Sec 606. Delineators on bridges with two-lane, two-way traffic shall have retroreflective sheeting on both sides. Guardrail delineators will be considered completely covered by the contract unit price for Bridge Rail (Two Tube Structural Steel).



**Curb Notes:**  
Top of curb shall be built parallel to grade.  
All exposed edges of curb shall have either a 1/2" radius or a 3/8" bevel, unless otherwise noted.  
Use a minimum lap of 2'-11" for #5-R1 bars.  
The cross-sectional area of curb above the slab = 0.66 sq. ft.  
Concrete in the curb shall be Class B-2.

The curb shall be cured by application of Type 1-D Liquid Membrane-Forming Curing Compound in accordance with Sec 1055 and sealed in accordance with Sec 703. The contractor shall remove all curing compound in accordance with the manufacturer's recommendations before the concrete sealer is applied.  
Measurement of the curb is to the nearest linear foot for each structure, measured along the outside top of slab from end of slab to end of slab.  
Payment for all concrete and reinforcement, complete-in-place, will be considered completely covered by the contract unit price for Concrete Curb (Bridge Rail) per linear foot.



DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 001
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-273-6636)	

TTR1

Guidance

Standard Drawing Guidance (do not show on plans):

- ① Modify as required.

TL-4 (NCHRP 350) bridge rail is typically used on spread box beam bridges and may be used on adjacent box beam bridges where reinforcement is embedded in the beam.

Use only in certain applications because of cost. Acceptable for use when roadway width or site distance is a concern. Curb shall be used to prevent drainage over deck.



TTR2

Guidance

Standard Drawing Guidance (do not show on plans):


- ① Modify as required.

TL-4 (NCHRP 350) bridge rail is typically used on spread box beam bridges and may be used on adjacent box beam bridges where reinforcement is embedded in the beam.

Use only in certain applications because of cost. Acceptable for use when roadway width or site distance is a concern. Curb shall be used to prevent drainage over deck.









ELEVATION OF WING


ELEVATION OF END BENT



DETAIL A



PLAN OF END BENT



ELEVATION OF WING

PART PLAN

OPTIONAL TURNED DRAIN

(Use only when straight drain is not practical.)

**Standard Drawing Guidance (do not show on plans):**

Remove details that do not apply.

Revising for skewed end bent is not necessary nor required unless unusual details of drainage need to be shown.

For end bents with intermediate wing, see Bridge Standard Drawing sheet DRAIN03.

If the drain pipe discharges onto soil, front or side slope (Case 3 and 4 of Standard Plan 609.40), and discharges at greater than 20 feet above the toe of slope, then the possible erosion of the slope should be considered and prevention coordinated with the district.


**Possible solutions:**

A. Provide a drain flume consistent with 609.40.

B. Extend the drain to the toe of slope using the following note (or similar) added to the general notes:

The unperforated drain pipe shall be extended parallel to the slope at a depth of 30 inches until the drain discharges onto rock blanket or the ditch flowline.

C. Add a detail showing the drain extension.



PART SECTION A-A  
(Section thru wing similar)

**General Notes:**

All drain pipe shall be sloped 1 to 2 percent.

Drain pipe may be either 6-inch diameter corrugated metallic-coated steel pipe underdrain, 4-inch diameter corrugated polyvinyl chloride (PVC) drain pipe, or 4-inch diameter corrugated polyethylene (PE) drain pipe.

Drain pipe shall be placed at fill face of end bent and inside face of wings. The pipe shall slope to lowest grade of ground line, also missing the lower beam of end bent by a minimum of 1 1/2 inches.

Perforated pipe shall be placed at fill face side and inside face of wings at the bottom of end bent and plain pipe shall be used where the vertical drain ends to the exit at ground line.

**VERTICAL DRAIN AT END BENTS**  
(Squared end bent shown, skewed end bent similar)



Detailed  
Checked


DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 000
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	

MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION

**MDOT**


105 WEST CAPITOL  
JEFFERSON CITY, MO 65102  
1-888-ASK-MODOT (1-888-275-6636)






ELEVATION OF WING


ELEVATION OF END BENT



DETAIL A



PLAN OF END BENT



ELEVATION OF WING

PART PLAN

OPTIONAL TURNED DRAIN

(Use only when straight drain is not practical.)

**Standard Drawing Guidance (do not show on plans):**

Remove details that do not apply.

Revising for skewed end bent is not necessary nor required unless unusual details of drainage need to be shown.

If the drain pipe discharges onto soil, front or side slope (Case 3 and 4 of Standard Plan 609.40), and discharges at greater than 20 feet above the toe of slope, then the possible erosion of the slope should be considered and prevention coordinated with the district.


**Possible solutions:**

A. Provide a drain flume consistent with 609.40.

B. Extend the drain to the toe of slope using the following note (or similar) added to the general notes:

The unperforated drain pipe shall be extended parallel to the slope at a depth of 30 inches until the drain discharges onto rock blanket or the ditch flowline.

C. Add a detail showing the drain extension.



PART SECTION A-A  
(Section thru wing similar)

**General Notes:**

All drain pipe shall be sloped 1 to 2 percent.

Drain pipe may be either 6-inch diameter corrugated metallic-coated steel pipe underdrain, 4-inch diameter corrugated polyvinyl chloride (PVC) drain pipe, or 4-inch diameter corrugated polyethylene (PE) drain pipe.

Drain pipe shall be placed at fill face of end bent and inside face of wings. The pipe shall slope to lowest grade of ground line, also missing the lower beam of end bent by a minimum of 1 1/2 inches.

Perforated pipe shall be placed at fill face side and inside face of wings at the bottom of end bent and plain pipe shall be used where the vertical drain ends to the exit at ground line.


**VERTICAL DRAIN AT END BENTS**



(Squared end bent shown, skewed end bent similar)


Detailed  
Checked

Note: This drawing is not to scale. Follow dimensions.

Sheet No. of


DATE PREPARED 10/17/2023	
ROUTE	STATE MO
DISTRICT	SHEET NO. 2
COUNTY	
JOB NO.	
CONTRACT ID.	
PROJECT NO.	
BRIDGE NO.	
DESCRIPTION	
DATE	
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION	
	
105 WEST CAPITOL JEFFERSON CITY, MO 65102 1-888-ASK-MODOT (1-888-275-6636)	






ELEVATION OF WING


ELEVATION OF END BENT




DETAIL A



PLAN OF END BENT



ELEVATION OF WING



PART PLAN

OPTIONAL TURNED DRAIN

(Use only when straight drain is not practical.)

**Standard Drawing Guidance (do not show on plans):**

Remove details that do not apply.

Revising for skewed end bent is not necessary nor required unless unusual details of drainage need to be shown.

If the drain pipe discharges onto soil, front or side slope (Case 3 and 4 of Standard Plan 609.40), and discharges at greater than 20 feet above the toe of slope, then the possible erosion of the slope should be considered and prevention coordinated with the district.


**Possible solutions:**

A. Provide a drain flume consistent with 609.40.

B. Extend the drain to the toe of slope using the following note (or similar) added to the general notes:

The unperforated drain pipe shall be extended parallel to the slope at a depth of 30 inches until the drain discharges onto rock blanket or the ditch flowline.

C. Add a detail showing the drain extension.



PART SECTION A-A  
(Section thru wing similar)

**General Notes:**

All drain pipe shall be sloped 1 to 2 percent.


Drain pipe may be either 6-inch diameter corrugated metallic-coated steel pipe underdrain, 4-inch diameter corrugated polyvinyl chloride (PVC) drain pipe, or 4-inch diameter corrugated polyethylene (PE) drain pipe.

Drain pipe shall be placed at fill face of end bent and inside face of wings. The pipe shall slope to lowest grade of ground line, also missing the lower beam of end bent by a minimum of 1 1/2 inches.

Perforated pipe shall be placed at fill face side and inside face of wings at the bottom of end bent and plain pipe shall be used where the vertical drain ends to the exit at ground line.

**VERTICAL DRAIN AT END BENTS**  
(Squared end bent shown, skewed end bent similar)

Detailed  
Checked

DATE PREPARED		10/17/2023	
ROUTE		STATE	
		MO	
DISTRICT		SHEET NO.	
		3	
COUNTY			
JOB NO.			
CONTRACT ID.			
PROJECT NO.			
BRIDGE NO.			
DESCRIPTION			
DATE			
MISSOURI HIGHWAYS AND TRANSPORTATION COMMISSION			
			
		105 WEST CAPITOL	
		JEFFERSON CITY, MO 65102	
		1-888-ASK-MODOT (1-888-275-6636)	

