

ADDENDUM 001 Request for Bid Osceola Maintenance Building Addition RFB 9-160225KH

Bidders should acknowledge receipt of Addendum 001 (ONE) by signing and including it with the original bid. The due date for receipt of bids **has not** changed by this Addendum; the due date is **February 25, 2016 2:00 PM Central Time**. Accordingly, the following clarifications, and or additional information, are believed to be of general interest to all potential bidders. All other terms and conditions remain unchanged and in full force.

Name and Title of Signer (Print or type)	Name and Title of Department Authority Kristi Hixson General Services Senior Specialist
Contractor/Offeror Signature (Signature of person authorized to sign)	Department of Transportation <i>Kristi Hixson</i> (Authorizing Signature)
Date Signed:	Date Signed: 2/18/2016

Plan Sheet:

- Sheet 2** It shall be the contractor's responsibility to relocate the cleanout north of the construction area if it interferes with the new construction.
- Sheet 3** Contractor shall be responsible for relocating generator and/or fuel shut-off on west wall of new structure. Contractor may bury the fuel shut-off in conduit underground OR run it through the building.
- Sheet 3** Detail D3. Contractor responsible for relocating the following items that may be covered by new construction to include: 1) Two condensation drain lines 2) Wireless connection to fuel island. Not shown on plans



Sheet 5 Replace the following Plan Key Notes:

01	EXISTING BLOCKWALL TO REMAIN - CONTRACTOR TO INSTALL NEW WALL / 2"X4" @ 16" O.C. / 5/8" TYPE X GYPSUM BOARD EACH SIDE
02	NEW WALL / 2X4 @ 16" O.C. / 5/8" TYPE X GYP. BOARD EACH SIDE / PAINTED 2 COATS/ 9' HIGH WALL
03	NEW WOOD STUD WALL / 2"X6" @ 16" O.C. / 5/8" TYPE X GYP. BD INSIDE & PAINTED INSIDE 2 COATS. SEE WALL SECTION A10 & A14

****Plan Key Notes 4, 5 and 6 remain as listed on Sheet 5.**

Sheet 5 Plan Key Note 01. Not shown on plans – add to west wall of new structure on plans.

Sheet 7 Replace with Revised Sheet 7 (separate attachment).

Sheet 7 On Revised Sheet 7, add an additional dedicated circuit to south wall of Room 101. Contractor responsible to run conduit above the drop ceiling for data and communications.

Sheet 10 Replace with Revised Sheet 10 (separate attachment).

Sheet 14 Contractor to eliminate Polyfoil Single Bubble Reflective Insulation and install only Drip-X Roofing or equivalent brand.