

ADDENDUM 001 Request for Bid New Florence Sewer and Water Connection Project RFB 9-160713KH

Bidders should acknowledge receipt of Addendum 001 (ONE) by signing and including it with the original bid. The due date for receipt of bids **has not** changed by this Addendum; the due date is **July 13, 2016 2:00 PM Central Time**. Accordingly, the following clarifications, and or additional information, are believed to be of general interest to all potential bidders. All other terms and conditions remain unchanged and in full force.

Name and Title of Signer (Print or type)	Name and Title of Department Authority Kristi Hixson General Services Senior Specialist
Contractor/Offeror Signature (Signature of person authorized to sign)	Department of Transportation <i>Kristi Hixson</i> (Authorizing Signature)
Date Signed:	Date Signed: 7/6/2016

Revised Plan Sheet C-1 and C-2 (separate attachment)

MoDOT retains pump and guard rails from existing lift station as noted on Revised Plan Sheet C-2.

Questions:

Question: Are there temporary bench marks?

Answer: See plan sheet C1 showing the TBM on a curb west of the new water line boring location.



Question: Will the city provide the water meter?

Answer: Contractor to provide the water meter. The water meter shall be manufactured by Badger and shall be installed with a backflow preventer in the meter box. Contractor shall verify with the City of New Florence.

Question: Will contractor be able to use the city's water or required to pump own water through pipe?

Answer: As stated in Specification Section 02726, Part 2.2, C, Item 2 states: Water needed to flush and disinfect after the initial procedure shall be purchased at the current residential rate. Contractor to verify cost with the City of New Florence.

Question: Can contractor bore the water line at their own expense?

Answer: Yes.

Question: Will there be room on lot designated for staging?

Answer: Yes, area on southwest end of the lot may be used for staging. Security of items is Contractor's responsibility.

Question: Can staking be done by contractor or is the contractor required to use a Missouri Registered Land Surveyor?

Answer: The contractor is required to use a Missouri Registered Land Surveyor.

Question: Will there be a waste area for spoils?

Answer: All waste material resulting from the project shall be disposed of off-site as stated on Sheet G1 General Note 12.