

Missouri Department of Transportation
Roberta Broeker, Interim Director

573.751.2551
Fax: 573.751.6555
1.888.ASK MODOT (275.6636)

ADDENDUM 002 Request for Bid Williamsburg Septic System Improvements Project RFB 9-150602KH

Bidders should acknowledge receipt of Addendum 002 (TWO) by signing and including it with the original bid. The due date for receipt of bids **has not** changed by this Addendum; the due date is **June 2, 2015 2:00 PM Central Time**. Accordingly, the following clarifications, and or additional information, are believed to be of general interest to all potential bidders. All other terms and conditions remain unchanged and in full force.

Name and Title of Signer (Print or type)	Name and Title of Department Authority Kristi Hixson General Services Senior Specialist
Contractor/Offeror Signature (Signature of person authorized to sign)	Department of Transportation <i>Kristi Hixson</i> (Authorizing Signature)
Date Signed:	Date Signed: 5/29/2015

- The transfer pipe shown on the Septic System Site Plan on the Plan Sheet between the dosing pump tank and the mounded pad peat fiber biofilter should be two-inch (2") Schedule 40 pipe. The length is still 70 feet.
- Include geotextile fabric to cover the entire interface between the sand and the topsoil, in addition to the geotextile fabric shown on the section detail of the mound system on the Plan Sheet.
- Plan Sheet, Note 1: Replace last sentence stating *Use Liberty Pump Model 287 or approved equal* with **Use Liberty Pump Model 280 or approved equal**.

