

Route W

Sta.	Size	Length	Description
102+22	B-3	34'	Remove existing B-3 pipe culvert and replace with 50' B-3 pipe arch culvert
106+20	B-7	44'	Remove existing B-7 pipe culvert and replace with 50' of B-7 pipe culvert
136+00	18"	30'	Remove existing 18" pipe and replace with 40' of 18" pipe
146+00	B-3	36'	Remove existing B-3 pipe culvert and replace with 40' B-3 pipe arch culvert
153+00	24"	34'	Remove Existing 24" pipe and replace with 50' of 24" pipe.
157+26	42"	44'	Remove existing 42" Pipe and replace with 60' of 42" Pipe
162+00	18"	36'	Remove existing 18" pipe and replace with 60' of 24" pipe.
174+28	24"	36'	Remove existing 24" pipe and replace with 60' of 24" pipe.
186+00	18"	44'	Remove existing 18" pipe and replace with 60' of 24" pipe.
199+41	24"	40'	Remove existing 24" pipe and replace with 60' of 24" pipe.
202+20.5	B-7	38'	Remove 38' of existing B-7 pipe culvert and replace with 50' of B-7 arch pipe
210+11.6	42"	43'	Remove existing 42" pipe and replace with 60' of 42" pipe.
232+47	48"	48'	Remove 48' of 48" pipe, and replace with 75' of 48" pipe.
247+66	18"	40'	Remove 40' of 18" pipe and replace with 60' of 18" pipe.
258+19.5	5x6 box		Remove existing Concrete Box Culvert and replace with 60' of 84" CMP
265+41	18"	34'	Remove existing 18" pipe and replace with 60' of 18" pipe.
270+00	24"	36'	Remove existing 24" pipe and replace with 60' of 24" pipe.
278+16.5	B-3	34'	Remove 34' of B-3 pipe, replace with 50' of B-3 metal pipe arch.
286+29	B-8	44'	Remove 44' of B-8 pipe, collar and two 36" pipes and replace with 60' of B-8 metal Pipe Arch

Route FF

9+33	18"	34'	Remove existing 18" CMP and replace with new 18" CMP
22+91	24"	56'	Remove existing 24" CMP and replace with new 24" CMP
25+70	24"	64"	Remove existing 24" CMP and replace with new 24" CMP
34+00	B4		Remove existing B4 pipe culvert and replace with B4 pipe culvert.
45+30	24"	36'	Remove existing 24" CMP and replace with new 24" CMP
67+33	24"	44'	Remove existing 24" CMP and replace with new 24" CMP
70+00	24"	60'	Remove existing 24" CMP and replace with new 24" CMP
74+30	72"		Extend existing 72" CMP 10' each side of Route FF.
109+50	12"	34'	Remove existing 12" CMP and replace with new 15" CMP
151+10	48"	74'	Remove existing 48" CMP and replace with new 48" CMP
201+09	B9		Remove existing B9 pipe culvert and replace with B9 pipe culvert.
237+74	B7		Remove existing B7 pipe culvert and replace with B7 pipe culvert.