

NOTES:

NOT TO SCALE

- SEWER DOSING PUMP SHALL BE AN ENGINEERED DEMAND DOSED PUMP PACKAGE AND SHALL INCLUDE PUMP, FLOAT SWITCHES ASSEMBLY, DISCHARGE ASSEMBLY, DISTRIBUTION VALVE AND PUMP CONTROL PANEL WITH HIGH WATER ALARM. PUMP PACKAGE SHALL INCLUDE A PUMP CAPABLE OF PUMPING 20 GPM AT 30 FT. TDH. USE LIBERTY PUMP MODEL 280 OR APPROVED EQUAL.
- 2. EXISTING ELECTRIC SERVICE IS LOCATED ON EAST END OF BUILDING. PUMP IS TO BE SINGLE PHASE, 240 VOLT POWER. ELECTRICAL TO CONTROLS IS TO BE
- 3. PLACE SHUTOFF VALVE AND CHECK VALVE IN PUMP TANK, ACCESSIBLE FROM THE SURFACE.
- 4. DISPERSAL THROUGH MOUND SYSTEM SHALL BE BY PROGRAMMABLE DOSING TIMER. DOSING TO BE AS RECOMMENDED BY SYSTEM MANUFACTURER.
- 5. SAND SHALL CONFORM TO ASTM C33 OR AS REQUIRED BY
- 6. ALL PERMITS REQUIRED FOR CONSTRUCTION ARE TO BE OBTAINED AND PAID FOR BY THE CONTRACTOR.

DESIGN NOTES:


MAINTENANCE BUILDING/OFFICE 15 EMPLOYEES AT 25 GPD EACH MAXIMUM TOTAL FLOW PER DAY= 375 GALLONS

ONE 1500 GALLON SEPTIC TANK= 1500 GALLONS 375 GALLONS PER DAY= 4 DAYS = 96 HOURS MINIMUM DETENTION TIME

INDICATION OF HIGH WATER TABLE AT 12" DEPTH CONVENTIONAL LEACHFIELD NOT APPROPRIATE.


SYSTEM SHALL BE TYPE A ANUA MOUNDED PAD SYSTEM WITH PROGRAMMABLE DOSING TIMER, INSTALLED PER ANUA DESIGN AND INSTALLATION


SOIL LOADING RATE= 0.4 GALLONS PER DAY/ PER SQ. FT. AT 12 INCHES DEPTH




PRECAST CONCRETE SEPTIC TANKS SHALL BE S.I. PRECAST (SUHOR INDUSTRIES) 1500 GALLON TWO CHAMBER SEPTIC TANK" OR EQUAL


SEPTIC TANK DETAIL NOT TO SCALE







- 1. GEOTEXTILE FABRIC SHALL BE PLACED AT THE INTERFACE BETWEEN THE SAND FILL AND TOPSOIL.
- 2. THE LAYER OF TOPSOIL IS TO BE A MINIMUM OF SIX INCHES OVER ENTIRE MOUND SYSTEM AND LANDSCAPED AS NECESSARY.
- 3. INSTALLATION TO BE DONE AS REQUIRED BY THE SYSTEM MANUFACTURER.



PHILIP RYAI

O. MODOT FACILITY
I IMPROVEMENTS WILLIAMSBURG, MO. I SEPTIC SYSTEM IN

DETAILS

AND

PLAN

ONSITE

Ž

140204-020 SHEET NO. 1 OF 1